SCIENCE

7 March 1958

Volume 127, Number 3297

REFERENCE SERVICES
ROOM 5614
HEW BLDG., SO.

MAR 7 1958

DIVISION OF SPECIAL
HEALTH SERVICES, PHS

5:10030

NATIONAL LIBRARY OF MEDICINE

Editorial Communicative Accuracy 499

Articles Distance and Relativity: *G. C. McVittie* 501

The Search for Anticancer Antibiotics: *G. F. Gause* 506

Arno B. Luckhardt, Physiologist: *F. C. McLean* 509

News of Science News Articles and Briefs, Scientists in the News; Recent Deaths 510

Reports Growth of Children of the Same Race under Different Environmental Conditions: *W. W. Greulich* 515

Distribution of Incompatibility Alleles among the Complex-Heterozygotes of *Oenothera*: *E. Steiner* and *M. S. Schultz* 516

Fractionation of Stable Isotopes of Sulfur by Thiobacilli: *I. R. Kaplan* and *T. A. Rafter* 517

A New Strain of the Mouse Mammary Tumor Virus: *P. B. Blair* 518

Starch Gel Electrophoresis of Some Invertebrate Sera: *K. R. Woods* et al. 519

Ethanol Protection against the Catalase-Depressing Effect of 3-Amino-1,2,4-Triazole: *G. H. Nelson* 520

Blocking by Picrotoxin of Peripheral Inhibition of Crayfish: *W. G. Van der Kloot, J. Robbins, I. M. Cooke* 521

Book Reviews *Industry and Technical Progress; Principles of Engineering Geology and Geotechnics; Medical Radiation Biology; Parthenogenesis and Polyploidy in Mammalian Development; The Fascination of Numbers; Neutron Cross Sections; Natural Magick; Reptiles Round the World*; New Books 523

Meetings and Societies Program of the Gordon Research Conferences; Society Elections; Forthcoming Events 526

Letters 540

Equipment News 546

CHRONIC DISEASE PROGRAM
Information Office

AMERICAN ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE



Quick . . . accurate . . . gas chromatography

CENCO® vapor phase analyzer

A most practical instrument of wide temperature range for the analysis of gases or volatile liquids by gas chromatography. Based on the elution technique, the Cenco Analyzer gives a simple reliable method of analyzing chemical and petroleum components quickly and accurately. Built around the popular Cenco constant temperature oven, it provides sensitive control from ambient room temperature to 200°C. Handles liquids which boil over 300°C. Quick-change columns, built-in gas sampling valve and unique liquid sampling feature facilitate analyses. Large variety of column materials available.

No. 70130 Cenco Vapor Phase Analyzer comes equipped with Gow-Mac detection cell, sensitive pressure regulator, flowmeter 1 to 83 ml/min range, 10 ft. coiled column of Di-2-ethylhexyl phthalate, syringe, temperature controls, thermometer, built-in regulated power supply, but without recorder..... **$895.00**

Write for Bulletin 275.

cenco

The most complete line of scientific instruments and laboratory supplies in the world

RS

CENTRAL SCIENTIFIC COMPANY

General Offices and Factory—1718-M Irving Park Road • Chicago 13, Illinois
Branches and Warehouses—Mountainside, N. J. • Boston • Birmingham
Central Scientific Co. of California—Santa Clara • Los Angeles
Refinery Supply Company—Tulsa • Houston
Central Scientific Co. of Canada, Ltd.—Toronto • Montreal • Vancouver • Ottawa



HOT OFF THE PRESS!

The most complete labware catalog ever!

350 Pages . . . 8500 Pieces of PYREX® Borosilicate Lab Glassware

New listing method and color-coding make Corning's NEW Catalog even easier to use

This newly published Corning Catalog of PYREX brand Laboratory Glassware is the most complete, easiest-to-use book of its type ever printed.

The idea originated with you. If you were one of the customers we contacted in our Catalog Preference Survey it's likely your ideas are incorporated in Catalog LG-1. Because you use it frequently it was only fair that you had a say in its organization and layout.

For fast finding—new listing method. LG-1 is set up dictionary style. Bold headings at the top outside corner of each page tell you the class of ware and the type of glass of the products listed on that page . . . let you locate any item in the book in just seconds.

For fast finding—color-coded Sections. The Catalog is in six Sections, each with its own color panels at the top and side of each page. For example, the panels in the PYREX® Section are green; VYCOR® Section, blue; Custom Made Section, brown. Merely flip the pages to find what you need.

There's an extensive index and exhaustive cross-indexing, too, so you can find similar items and component parts quickly. Three separate Appendixes (A.S.T.M. Ware, Micro, and Needle Valve Ware) also improve "finding" efficiency.

Custom Made Labware Section. Also at your request, the former Custom Apparatus Catalog joins our Standard Listings. This 143-page Section lists the most demanded modifications of all types of ware. Each item differs from the norm in ways to make your work faster or easier. Included, also, are 13 pages of Micro Ware and 12 pages of Needle Valve Equipped Glassware listings.



Most complete line available anywhere. Flasks, for example, are listed in all six sections.

No eyestrain: LG-1 is color-coded. Each section has its own color panels and is identified in print.

Easy-to-find illustrations. Just flip the pages to find what you need.

Clip the Coupon for Your *Free Copy of LG-1, Corning's* New Lab Glassware Catalog

Corning means research in Glass

CORNING GLASS WORKS

75-3 Crystal Street, Corning, New York

I have not as yet received my free copy of Corning Catalog LG-1. *Please send me one.*

Name.....Title.....

Company.....

Street.....

City.....Zone.....State.....

SCIENCE is published weekly by the AAAS, 1515 Massachusetts Ave., NW, Washington 5, D.C. Entered at the Lancaster, Pa., Post Office as second class matter under the act of 3 March 1879. Annual subscriptions: $8.50; foreign postage, $1.50; Canadian postage, 75¢.



Newly engineered features, such as electronic scale expansion, help analysts make fuller use of the inherent sensitivity of the Perkin-Elmer Model 21 spectrophotometer.

With new electronic scale expansion feature

PERKIN-ELMER MODEL 21 PERFORMS DIFFICULT TRACE ANALYSES EASILY...

A new electronic scale expansion feature for the Perkin-Elmer Model 21 double beam recording spectrophotometer now enables the analyst to make accurate trace analyses, by expanding any section of the spectrum he may wish to study—without changing cell thickness. This new feature, which makes use of the Model 21's unusual sensitivity, has proved to be particularly useful in air and water pollution work, in the study of mono-molecular films and in similar trace analyses.

Offering complete flexibility in resolution, spectral presentation and recording speeds, the Model 21 is available with a full line of accessories. Considered the standard for infrared analysis, it is used in more industrial and academic laboratories than any other infrared instrument. Continuing research and development by Perkin-Elmer engineers, resulting in refinements such as electronic scale expansion, assure the Model 21's leading position in the field of infrared analysis.

For further information write us at 910 Main Avenue, Norwalk, Conn.

INSTRUMENT DIVISION
Perkin-Elmer *Corporation*
NORWALK, CONNECTICUT



Spectra above illustrate the scale expansion feature of the Model 21. Trace quantities (5 parts per million of acetylene in nitrogen) yielded the very weak band at top. Rerunning the spectrum with electronic scale expansion (lower band) shows greatly increased sensitivity, with the band fully resolved.

FIRST: LOOK AT UNITRON'S NEW POLARIZING MICROSCOPE

Here is a precision measuring instrument for both orthoscopic and conoscopic observations, designed to meet the exacting requirements of science, education, and industry. Its many features make it ideal for work in chemistry, crystallography, mineralogy and biology as well as in the technology of paper, glass, textiles and petroleum.

CHECK THESE OPTICAL & MECHANICAL FEATURES

Note that UNITRON'S new Model MPS comes complete with optics and accessories and includes features usually associated only with much more costly models.

- **EYEPIECES:** Micro 5X providing measurements to 0.0025mm. and cross-hair 10X. The eye lenses focus to produce sharp reticle images and are keyed to prevent rotation.
- **OBJECTIVES:** 4X(N.A.0.1), 10X(N.A.0.25), 40X(N.A.0.65), achromatic, strain-free, each with centerable mount.
- **NOSEPIECE:** quick-change type for critical centering.
- **CONDENSER and POLARIZER:** three-lens condenser with upper elements on a swing-out mounting, provides either parallel or convergent light. A dovetail-slide focusing mount and iris diaphragm insure optimum illumination and resolution.
- **POLAROID POLARIZER:** rotatable through 360° and graduated every 45°. Plano-concave mirror.
- **ANALYZER:** Polaroid, in sliding metal mount.
- **BERTRAND LENS:** for the study of interference figures, fixed-focus lens is centerable and mounted in a slideway.
- **STAGE:** diameter 115mm., revolves through 360°, graduated in degrees and reads to 6′ with vernier. The top is calibrated in mms. in two directions and is drilled and tapped for an accessory mechanical stage. Stage clips.
- **COMPENSATORS:** two compensators are included; a quarter-wave plate and first order red plate. These fit into a slot above the objective lens.
- **FOCUSING:** coarse and micrometric fine adjustments.
- **STAND:** heavy stand, arm inclines to horizontal position.



Condenser and Polarizer

THEN: LOOK AT THE PRICE!

Model MPS complete as described, in fitted cabinet.....
Quantity prices on three or more.
Accessory mechanical stage.....

$269 FOB BOSTON
$14.75

AVAILABLE ON FREE 10 DAY TRIAL

Send for complete catalog on UNITRON Microscopes.

THE TREND IS TO UNITRON

UNITRON
INSTRUMENT DIVISION OF UNITED SCIENTIFIC CO.
204-206 MILK STREET • BOSTON 9, MASSACHUSETTS

Please rush UNITRON Catalog on Microscopes.

Name_____
Company_____
Address_____
City_____ State_____ 83a

true
soft beta counting
-simple
operation



THE TMC LP-2A LIQUID PHOSPHOR COUNTER

For precise counting of soft beta emitters such as Carbon 14, Tritium, Sulphur 35, the TMC Model LP-2A Liquid Phosphor Counter offers many exclusive advantages in both operation and design, proven in the various applications of nuclear radiation in all fields of research. Here are the primary reasons for the LP-2A's outstanding performance—

DETECTION . . . Two refrigerated photomultiplier tubes—specially selected and matched for highest sensitivity and lowest accidental coincidence noise—measure and analyze light output. The sample holder is equipped with an interlocking shutter mechanism which permits sample changing without removing phototube high voltage. Overall electronic gain is 100,000 with 0.15 us. rise time.

COUNTING . . . A fast coincidence pulse height analyzer uses coincidence on all levels and pulse height analysis on both amplifier channels. This means that pulses, to be counted, must be analyzed by both detectors simultaneously. (If one pulse falls in the upper channel and the other in the lower channel, it is counted as a lower channel event.) This considerably reduces coincidence noise and photomultiplier selection. Operation with separated channels is also possible.

READOUT . . . Two precision scalers are used—each with a 2.5 us. resolving time and total capacity of up to 10^7 counts, on three decade scaling strips and a mechanical register. One scaler counts all pulses between lower and middle level settings. The second scaler counts pulses between the middle level and upper level (to infinity if desired). This feature permits simultaneous counting of two isotopes with an energy difference as small as 3 to 1.

DYNAMIC DISCRIMINATOR RANGE . . . The dynamic discriminators will maintain stable operation on as little as 5 volts, thus giving them the extremely wide range of 20 to 1. This is of primary importance when counting different isotopes simultaneously. The Model HV-4A Ultra-Stable High Voltage Power Supply may be precisely set to a given voltage and this setting may be later duplicated within a fraction of a volt. Stability is 50 parts per million/hr. or 200 parts/million/day, resulting in minimum drift. This means simpler operation because minimum adjustment is required.

UNITIZED CONSTRUCTION . . . Each component (dual amplifier, analyzer, dual scaler, high voltage source) has its own power supply, thus permitting easy servicing and testing of individual units. All units are housed in a rugged enclosed cabinet and cooled by forced filtered air.

The accurate, dependable components and advanced circuitry design make the LP-2A a research instrument capable of optimum performance and versatility.

Detailed data concerning the LP-2A or catalog "C" which describes the complete TMC line are available on request. TMC also invites your inquiries concerning specific instrumentation recommendations.

TMC **TECHNICAL MEASUREMENT CORPORATION**
140 STATE STREET, NEW HAVEN, CONNECTICUT

SIEMENS
MEASURING
INSTRUMENTS

8 AU

A resolving power better than 15 AU

is guaranteed for the Electron-Microscope

ELMISKOP I

designed for normal routine work and for special research problems in science and industry.

Special features:
Beam voltages 40, 60, 80 and 100 kv.
Direct magnification continuously variable from 200 to 160,000 times.
Fine-focus condenser for transmission of smallest specimen regions down to a diameter of 3 microns.
Adjustable magnetic stigmators in condenser and objective.
Transmission microscopy (bright- and dark-field, stereoscopic and selected area micrographs).
Diffraction (normal transmission diffraction with and without lenses, high-resolving diffraction, reflection diffraction for conducting specimens, simultaneous diffraction, selected area diffraction).
Universal diffraction unit with heating device (optional).
Object cooling stage (optional).

For work in the industrial field and medical research the simplified design

ELMISKOP II is of increasing importance:
Resolving power better than 25 AU.
Beam voltages 40, 50 and 60 kv.
Direct magnification up to 30,000 times.
Accessories for specimen preparation:
Vacuum Evaporating Unit
11-kc Emulsifier

Resolution test with evaporated palladium
direct magnification 100,000 times
total magnification 1,000,000 times

SIEMENS & HALSKE AKTIENGESELLSCHAFT
BERLIN · MÜNCHEN

SIEMENS NEW YORK INC.
350, FIFTH AVENUE · NEW YORK 1, N.Y. · TELEPHONE: LONGACRE 4-7674

THE AHEARN & SOPER CO. LTD.
OTTAWA (CANADA) · P.O. BOX 715 · TELEPHONE: C 34068

SENSATIONAL OPTICAL BARGAINS

Photographers!

Adapt your camera to this Scope for excellent Telephoto shots and fascinating photos of moon!



This is an actual photograph of the moon taken through our Astronomical Telescope by a 17-year-old student.

See the Stars, Moon, Planets Close-Up!

3" ASTRONOMICAL REFLECTING TELESCOPE

ASSEMBLED and READY TO USE!

Famous Mt. Palomar-Type

60 & 120 Power — An Unusual Buy!

Youll see the Rings of Saturn, the fascinating planet Mars, huge craters on the Moon, Star Clusters, Moons of Jupiter in detail. Galaxies! This is a fine quality, American-made telescope engineered and built for clear definition and resolution. Equatorial mount with lock on both axes—you automatically follow stars across the heavens. Aluminized and overcoated 3" diameter high-speed f/10 mirror. Each mirror Focault tested. Telescope comes equipped with a 60X eyepiece and a mounted Barlow Lens, giving you 60 & 120 Power. Accessory eyepieces available for powers up to 250. An Optical Finder Telescope, always so essential, is also included. Sturdy, hardwood, portable tripod.

Free with scope: Valuable STAR CHART and 272 page "Astronomy Book."

Stock No. 85,050-W ..... **$29.50 f.o.b. Barrington, N.J.**
(Shipping wt. 10 lbs.)

4¼" ASTRONOMICAL TELESCOPE!

MT. PALOMAR TYPE



With this scope you can see the craters on the Moon, the rings of Saturn, double stars. Mirror guaranteed to give theoretical limit of resolution. Rack and pinion focusing, removable mirror mount, counterweight. Real equatorial mounting—only one adjustment follows stars! Aluminum tube. 6 Power Finder Telescope. 2 standard size Eyepieces and Mounted Barlow Lens give you powers of 40X, 90X, 120X, 270X. Mirror f/11. Mirror corrected to better than ¼ wavelength. **Stock No. 85,006-W .. $74.50 f.o.b. Order by Stock No. Barrington, N.J.**
Send Check or M.O. — Satisfaction Guaranteed!

Take Telephoto Shots Thru 7x50 MONOCULAR

This is fine quality, American made instrument—war surplus! Actually ⅓ of U.S. Govt. 7 x 50 Binocular. Used for general observation both day and night and to take fascinating telephoto shots with your camera. Brand new, $95 value. Due to Japanese competition we close these out at a bargain price. Directions and mounting hints included.
Stock No. 50,003-W ..... **$15.00 Postpaid**

BUILD A SOLAR ENERGY FURNACE

Wonderful Geophysical Year School Project

Build your own Solar Furnace for experimentation — many practical uses. It's easy—inexpensive. Use your scrap wood. We furnish instruction booklet. This sun powered furnace will generate terrific heat—2000° to 3000°. Fuses enamel to metal. Sets paper aflame in seconds. Use our Fresnel Lens—14¾" diameter . . . f.l. 14".
Stock No. 70,130-W pkg. of 1 .... **$6.00 Postpaid**

AMERICA NEEDS SCIENTISTS!
Stimulate your son's interest—request our FREE CATALOG-W featuring hundreds of scientific and astronomical items. No better time than in this INTERNATIONAL GEOPHYSICAL YEAR!

Now — See The Satellites

NEW, LOW PRICE "SATELLITER" TELESCOPE

First Time — Only $9.95 Postpaid

Get ready for a terrific sky show as more Satellites are vaulted into space. See thrilling sights with our amazing Satellite Scope at unheard of low cost. Also view comets—use as a Rich-field Scope for viewing star clusters. 5 power—wide 12° field—slight distortion at outer edges because of unusual wide field. Use of high quality war surplus optics makes possible this bargain. Full 2" achromatic objective—large 9mm exit pupil for night use. Scope is 10" long, weighs less than one pound.
Stock No. 70,150-W ..... **$9.95 Postpaid**

We are the mfg. of the famous Moonwatch Satellite Telescope!

INFRARED SNIPERSCOPE TELESCOPE & PARTS

See in the dark—without being observed. War surplus Sniperscope M-2, Govt'. cost about $1200. Instrument complete, ready to use. Includes Power Pack, infrared light source. Will operate from 6 V auto battery. Battery or transformer available.
Stock No. 85,053-W $150.00 f.o.b.
Save still more money! Build your own Sniperscope! We will furnish instructions—parts, including: Power Packs, 1P25A image tubes, light units, filters, etc. For details—request FREE Catalog "W".

50-150-300 Power
MICROSCOPE

Low Price Yet Suitable for Classroom Use! Only $14.95
3 Achromatic Objective Lenses on Revolving Turret!

Imported! The color-corrected, cemented achromatic lenses in the objectives give you far superior results to the single lenses found in the microscopes selling for $9.95! Results are worth the difference! Fine rack and pinion focusing.
Stock No. 70,008-W .... $14.95 Postpaid

MOUNTED 500 POWER OBJECTIVE

. . Threaded for easy attachment on above microscope. Achromatic lenses for fine viewing. 3 mm. focal length.
Stock #30,197-W ..... **$5.00 Pstpd.**

Check, Measure, Inspect with this 6 POWER POCKET COMPARATOR (Complete with Leather Case)



MEASURES
- **Angles**
- **Radii • Circles**
- **Linear — in both decimal inches and millimeters.**

HANDY! FAST! ACCURATE!

Used to check layouts, matching on tools, dies, gauges; to check threads, chamfers, wear on cutting tools, etc.
Stock No. 30,061-W .. New Low Price .. $19.50 Pstpd.

MEASURING POCKET MICROSCOPE — 50 POWER

No larger than an ordinary fountain pen, this handy pocket instrument is ideal for making direct reading measurements; for checking small parts and dimensions under powerful magnification. Speeds up quality control. Instrument contains a precision glass etched reticle calibrated for measurements up to 1/10" by .001" divisions. Estimates to .0005" can easily be made. Chrome reflector at base of instrument reflects light on object examined or measured. Sturdy construction assures long, useful service.
Stock No. 30,225-W ..... **$7.95 Postpaid**

New! 2 in 1 Combination! Pocket-Size
50 POWER MICROSCOPE and 10 POWER TELESCOPE

Useful Telescope and Microscope combined in one amazing, precision instrument. Imported! No larger than a fountain pen. Telescope is 10 Power. Microscope magnifies 50 Times. Sharp focus at any range. Handy for sports, looking at small objects, just plain snooping.
Order Stock #30,059-W ..... **$4.50 Postpaid**
Send Check or M.O. Satisfaction Guaranteed!

Fine, American-Made Instrument at Over 50% Saving

STEREO MICROSCOPE



Up to 3" Working Distance —Erect Image—Wide 3 Dimensional Field

Now, ready after years in development — this Instrument answers the long standing need for a sturdy, efficient STEREO MICROSCOPE at low cost. Used in production—in research—in the lab, shop, factory, or at home; for inspections, examinations, counting, checking, assembling, dissecting—speeding up and improving quality control. 2 sets of objectives on rotating turret. Standard pair of wide field 10X Kellner Eyepieces give you 23 power and 40 power. Additional eyepieces available for greater or lesser magnification. A low reflection coated prism erecting system gives you an erect image —correct as to right and left—clear and sharp. Helical rack and pinion focusing. Precision, American-made! 10-DAY TRIAL . . . complete satisfaction or your money back.
Order Stock No. 85,056-W (Shipping wt. approx. 11 lbs.)
Full price ..... **$99.50 f.o.b. Barrington, N.J.**
Send Check or M.O.

NEW! STATIC ELECTRICITY GENERATOR

See a thrilling spark display as you set off a miniature bolt of lightning. Absolutely safe and harmless—perfect for classroom experimentation . . . ideal for Science Clubs. Sturdily made —stands 14" high. Turn the handle and two 9" plastic discs rotate in opposite directions. Metal collector brushes pick up the static electricity, store it in the Leyden jar type condenser until discharged by the jumping spark. Countless tricks and experiments. 24-page instruction booklet included.
Stock No. 70,070-W ..... **$10.95 Postpaid**

BRIGHT BEAM LAMP

Gives brilliant and uniform illumination! Optically designed for all close-work operations. Adjustable to almost any position. Widely used in conjunction with stereoscopic and dissecting microscopes, toolmakers' microscopes, magnifiers and loupes . . . excellent for use with student microscopes. Variable spot of light obtainable from ⅝" diameter, very intense, to about 3", less bright, simply by sliding focus tube back and forth. Complete with bulb and daylight filter, on stand. Money-back guarantee.
Stock No. 15,001-W ..... **$27.50 Postpaid**

SWIVEL-CLAMP MAGNIFIER

This large 4" diameter magnifier will easily clamp onto any regular or fluorescent lighting fixture. With two ball and socket joints you can swivel it to any position. Large 4" ground and polished lens is + 5 dioptre, 8" focal. Use both eyes—see an image with depth to it.
Stock No. 30,249-W ..... **$4.15 Postpaid**

SIMPLE LENS KITS!

Fun for adults! Fun for children! Kits include plainly written, illustrated booklet showing how you can build lots of optical items.

Stock No. 5-W—45 lenses ..... **$ 5.00 Postpaid**
Stock No. 2-W—10 lenses ..... **$ 1.00 Postpaid**
Stock No. 10-W—80 lenses ..... **$10.00 Postpaid**

GET OUR GIANT FREE CATALOG-W

Over 1000 Optical Bargains, 80 Fascinating Pages

Huge selection of lenses, prisms, war surplus optical instruments, parts and accessories. Telescopes, satellite scopes, microscopes, binoculars. Hand spectroscopes, reticles, mirrors, Ronchi rulings, dozens of other hard-to-get optical items. America's No. 1 source of supply for Researchers. Lab. Technicians, Photographers, Hobbyists, Telescope Makers, etc. Ask for catalog W.

ORDER BY STOCK NUMBER . SEND CHECK OR MONEY ORDER . SATISFACTION GUARANTEED!

EDMUND SCIENTIFIC CO., BARRINGTON, NEW JERSEY

Scientific TESTING INSTRUMENTS

MADE BY A FUNCTIONING LABORATORY


U. S. TESTING CO.
INSTRUMENT SHOP
A precision shop completely equipped, manned by a highly trained staff, backed by a constant research and testing quality control.
U. S. TESTING CO.
LABORATORIES
Offering a broad testing service in raw materials, components, and finished products in the fields of chemistry, engineering, microbiology, and physics.

WE MAKE THEM MORE EFFICIENT...BECAUSE WE USE THEM, TOO!

As the only functioning laboratory manufacturing instruments, we are able to harness the talents of the laboratory technician and the instrument technician. Result: the instruments are conventional in operation, simple to calibrate, easy to maintain. They are sensitive, stable, and, in most cases, applicable to multi-purpose testing requirements. And all are, of course, pre-tested in practical performance problems in our own laboratories before they are put on the market.

Our instrument service is four-fold: we design and manufacture new instruments for firms, trade associations, scientific societies, and governmental agencies; we modify existing instruments to meet special needs; we manufacture instruments from existing designs; we operate new instruments where impartial laboratory reports are essential.

Be sure to write for our informative Instrument Service Bulletins, mailed free at regular intervals.



The Universal Pendulum Impact Tester with interchangeable striking heads and weights is broadly applicable to tests on paper, plastics, textiles, rubber, etc., in sheets, foams and solid shapes.

UNITED STATES TESTING COMPANY, INC.

Established 1880

1230 PARK AVENUE, HOBOKEN, NEW JERSEY

Boston • Brownsville • Dallas • Denver • Los Angeles • Memphis • New York • Philadelphia • Providence • San Angelo

SPIDERS SCORPIONS CENTIPEDES AND MITES

The Ecology and Natural History of Woodlice, 'Myriapods' and Arachnids

By

J. L. CLOUDSLEY-THOMPSON M.A., Ph.D.

One of the objects of this book is to indicate some of the innumerable problems awaiting elucidation and to provide a guide to sources for the identification of British species in particular, as well as to other relevant literature. It should be of great interest to natural history workers everywhere. It will also be of use to upper school teachers, and to university students who will find in it valuable information simply portrayed.

Price $9.00

MORPHOGENESIS:

The Analysis of Molluscan Development

By

CHR. P. RAVEN,
Professor of Zoology in the University of Utrecht

This is a survey of the present state of our knowledge on development in the molluscs, both descriptive and experimental. It is mainly centered on the causal analysis of morphogenesis. Comparative embryological points of view have hardly been taken into consideration, but the cytological and cytochemical aspects of development have been especially emphasized. Since the author has been working for nearly 20 years in this field, the researches of his own laboratory take a great place in this book. The literature on cytochemical and experimental embryological investigations on molluscs has been covered as completely as possible.

Price $10.00 **In preparation**

* * *

INTERNATIONAL ABSTRACTS OF BIOLOGICAL SCIENCES

Hon. Editor: C.C.N. Vass., M.Sc., Ph.D., M.B., Ch.B.
Assisted by an Editorial Board of Specialists

This journal abstracts the world literature in a wide field of topics in the basic biological and medical sciences. Owing to the wide range of subjects covered and the increasing number of papers and journals now being published, it is necessary to publish three volumes a year, each in three parts, with name and comprehensive subject indexes appearing every four months, immediately following the appearance of the last issue of each volume.

Price per volume: $28.00, including index
Printed on one side of the paper only: $29.50

Write for fully descriptive leaflets

PERGAMON PRESS

NEW YORK LONDON PARIS LOS ANGELES

122 East 55th Street, New York 22, N.Y. 4 & 5 Fitzroy Square, London W.1.

7 March 1958, Volume 127, Number 3297

SCIENCE

AMERICAN ASSOCIATION
FOR THE
ADVANCEMENT OF SCIENCE

Board of Directors

WALLACE R. BRODE, *President*
PAUL E. KLOPSTEG, *President Elect*
LAURENCE H. SNYDER, *Retiring President*
PAUL M. GROSS
GEORGE R. HARRISON
CHAUNCEY D. LEAKE
MARGARET MEAD
THOMAS PARK
MINA REES
WILLIAM W. RUBEY
ALAN T. WATERMAN
PAUL A. SCHERER, *Treasurer*
DAEL WOLFLE, *Executive Officer*

DAEL WOLFLE, *Executive Officer*
GRAHAM DUSHANE, *Editor*
JOSEPH TURNER, *Assistant Editor*
ROBERT V. ORMES, *Assistant Editor*

Editorial Board

WALLACE R. BRODE — EDWIN M. LERNER
BENTLEY GLASS — WILLIAM L. STRAUS, JR.
KARL LARK-HOROVITZ — EDWARD L. TATUM

Editorial Staff

MARY L. CRABILL, SARAH S. DEES, LUCILLE GUINARD, NANCY S. HAMILTON, OLIVER W. HEATWOLE, YUKIE KOZAI, ELLEN E. MURPHY, BETHSABE PEDERSEN, MADELINE SCHNEIDER, JACQUELYN VOLLMER, MARIA A. WOLSAK

EARL J. SCHERAGO, *Advertising Representative*

SCIENCE, founded in 1880, is published each Friday by the American Association for the Advancement of Science at Business Press, Lancaster, Pa. Entered at the Lancaster, Pa., Post Office as second class matter under the Act of 3 March 1879.

SCIENCE is indexed in the *Reader's Guide to Periodical Literature*.

Editorial and personnel-placement correspondence should be addressed to SCIENCE, 1515 Massachusetts Ave., NW, Washington 5, D.C. Manuscripts should be typed with double spacing and submitted in duplicate. The AAAS assumes no responsibility for the safety of manuscripts or for the opinions expressed by contributors. For detailed suggestions on the preparation of manuscripts, book reviews, and illustrations, see *Science* 125, 16 (4 Jan. 1957).

Display-advertising correspondence should be addressed to SCIENCE, Room 740, 11 West 42 St., New York 36, N.Y.

Change of address notification should be sent to 1515 Massachusetts Ave., NW, Washington 5, D.C., 4 weeks in advance. If possible, furnish an address stencil label from a recent issue. Be sure to give both old and new addresses, including zone numbers, if any.

Annual subscriptions: $8.50; foreign postage, $1.50; Canadian postage, 75¢. Single copies, 35¢. Cable address: Advancesci, Washington.

Communicative Accuracy

The events of the past few months have emphasized something we have known all along—that it is important for scientists to describe their activities to the public in such a way that they will be generally understandable and properly informative. This runs into the practical difficulty that some scientists, when they attempt a "popular" description of their labors and of their ideas, insist on achieving almost the same precision and completeness of statement which they would, quite properly, use in talking to their scientific colleagues. "You must not expect me to say that genes are distributed along a chromosome like different sizes and colors of beads along a string, for I have no satisfactory evidence that genes are as discrete as separate beads, and also I don't know about their sizes and shapes." Such scientists feel the urge to attach to each general statement of a popular exposition all the cautionary qualifications, all the modifying details, and all the scholarly footnotes that they would use in a technical report.

It may be helpful to suggest to such scientists that they consider the concept of "communicative accuracy." This concept rests upon the fact, not always recognized, that the effective accuracy of a written statement depends primarily upon the interpretation given to it by the reader. A statement may be said to have communicative accuracy, relative to a given audience of readers or hearers, if it fulfills two conditions. First, taking into account what the audience does and does not already know, it must take the audience closer to a correct understanding. The better an example of communicative accuracy it is, the more gain in understanding it will achieve—but the basic point is simply that it must gain ground in the right direction. Second, its inaccuracies (as judged at a more sophisticated level) must not mislead, must not be of a sort which will block subsequent and further progress toward the truth. Both of these criteria, moreover, are to be applied from the point of view of the audience, not from the more informed and properly more critical point of view of an expert.

Communicative accuracy is important to all of us all of the time. Consider the illuminating example, recently offered by a newspaper reporter, of the two men coming home from work and greeting their wives. One says, "My dear, when I look into your face, time stands still." The other remarks, "My dear, your face would stop a clock."

WARREN WEAVER

Rockefeller Foundation, New York

Where does progress begin?



Kendall Preston Jr., S.M. in engineering from Harvard University...
graduate of the Laboratories' Communications Development Training Program.

Progress begins in the mind—in the perception and appreciation of new ideas. In the past the ideas that sparked progress too often had to wait on the random interest of genius. Today more and more new ideas come from men trained to an awareness of that which is yet to be accomplished.

At Bell Laboratories, communications science is entering upon its most challenging era in history. As never before, progress will depend upon men who have acquired the special training needed to think creatively in this exciting field.

Bell Laboratories provides the young college graduate with unique opportunities to develop his creative abilities. During his first two years, he spends two or three days a week as part of his job, taking postgraduate courses in basic mathematics, physics and electronics. This he does at a graduate study center which has been established at the Laboratories by New York University. As he gathers a broad fundamental knowledge which will enable him to tackle every type of communications problem, he also gathers credits toward advanced degrees. To round out his education, he spends a third year on special phases of communications technology.

By helping scientists and engineers to reach their top development, Bell Laboratories has helped to make your telephone system the world's best—and will keep it so.

BELL TELEPHONE LABORATORIES

WORLD CENTER OF COMMUNICATIONS RESEARCH AND DEVELOPMENT

7 March 1958, Volume 127, Number 3297 SCIENCE

Distance and Relativity

G. C. McVittie

What does an astronomer mean when he says that the sun and the earth are, on the average, 92,900,000 miles apart? And what bearing can the two theories of relativity have on the matter? It is questions of this kind that I shall try to answer in this article, but I must first warn you that I have been described by my scientific colleagues as an uncompromising empiricist. I daresay that this is true, but it is also a little strange, for all my training and all my research work have lain in theoretical astronomy and not at all in the extremely difficult and fundamental task of making astronomical observations. Perhaps, however, the theoretician does have an advantage over his colleagues who are engaged in observational or experimental work. He can stand slightly to one side and ask himself: What exactly are these men doing, what kind of significance can be attached to the results of their efforts, and in what way are their data really conditioned by theories? To speak in generalities would, I think, be profitless, and it is for this reason that I propose to concentrate on the question of distance in the solar system and to leave aside the equally intricate and fascinating problem of distance in the universe at large.

Large-Scale Distances

It might be thought at first sight that the distance between two objects was such an obvious physical idea that there could be little to say about it. Two marks have been made on a certain bar of platinum that is carefully preserved in France; the separation of the two marks defines the unit of length called the meter. If, then, we want to find the distance from the front door of the J. I. Holcomb Observatory in Indianapolis to the front door of the University of Illinois Observatory in Urbana, all we need do is to lay the meter-bar down successively, starting at the first spot and finishing at the second, and count the number of times we have to repeat the operation. The number so arrived at would give the required distance in meters. But if I were to take any one of you to the Holcomb Observatory, hand you the meter-bar, and tell you to go ahead, I feel sure that you would be at a loss as to how to proceed. You would want to know in what direction to start out, and the specification of a direction means that some angle measured from a standard direction must be furnished. You would also want to know how to allow for the fact that you would at times—admittedly not very often in the flat midwestern plains—be going uphill and at others, down. In other words, how are the accidental errors in the measuring procedure to be dealt with? Again you might ask, if you were of a philosophical turn of mind: Do the two marks on the meter-bar correspond to some immutable degree of separation between them, or is this separation affected by accidental circumstances? Clearly, if in the course of your journey you were forced to pass the meter-bar through the center of a blast furnace in which it was vaporized, you would be hard put to it to know what to do next.

This illustration draws attention to three characteristics of determinations of large-scale distance: that angular measurements are involved, that errors have to be compensated for, and that the persistence of the unit of distance is important. But there are other matters of equal moment. Suppose that we have somehow measured to our satisfaction the distances from the Holcomb Observatory to the University of Illinois Observatory in Urbana and to the Dearborn Observatory in Evanston, respectively. Then is it necessary to repeat the measuring operation between the two last-named observatories in order to find the distance between them? The answer is, unfortunately, yes, if we do not know the geometry of the surface on which these three points lie. But if we do know it, then the rules of the geometry will enable us to calculate the required distance without further appeal to measurements. Conversely, measurements of distances between a sufficient number of points will give us a clue to the geometry that must be used to describe the interrelationships between the distances and the angles that are necessarily involved in them. With geometry, mathematical theory enters into our distance computations and, unfortunately for those who like their science to be simple, there is more than one kind of geometry. For example, the ordinary plane geometry of Euclid that we learn at school is different from the geometry on the surface of a sphere that surveyors use when they are making a survey of the United States. By this I mean that the mathematical formulae that are employed for interrelating distances and angles in the one case are not the same as those used in the other.

If you feel dismayed by the complexity of these problems, I shall now increase your dismay by introducing some further factors that are of the greatest importance in astronomy. The three observatories I have referred to are, to the best of our knowledge and belief, at mutual relative rest, their distances apart remaining unchanged as time goes on. This very simple situation almost never

Dr. McVittie is the head of the University of Illinois Observatory, Urbana. This article is adapted from a paper presented 26 December 1957 at the Indianapolis meeting of the AAAS.

arises in astronomy, nearly every astronomical object being in motion relative to ourselves on earth. Clearly, a distance determination for a moving object is meaningless unless we are also told the time to which the determination refers. Thus, two more elements are involved when the distances of moving objects are concerned—that is, we must know what is meant by the time of occurrence of an event and we must also know how the motions of bodies are governed, what the theories of dynamics and of gravitation may be.

But even if these complications have been allowed for, there is an additional one that enters into distance determinations in astronomy. Up to the present, it has not proved possible for an astronomer to leave the earth and go to any of the bodies whose distances he would like to find. In this respect, he differs from the terrestrial surveyor who can, at a pinch, actually proceed from one point to another on the earth's surface. The astronomer has to rely almost entirely for his knowledge of the astronomical universe on the information conveyed to him through the medium of electromagnetic radiation, whether in the form of optically visible light or in that of radio waves. The behavior of electromagnetic radiation in the astronomical universe is partly determined by experimental evidence in the laboratory but also very largely by a liberal use of theory. In the application to the solar-system distance problem, it can be established experimentally on the terrestrial laboratory scale that light rays travel in straight lines in Euclid's sense of this term. The belief that this is a property of all electromagnetic radiation and that it continues to hold as the radiation travels over the vast spaces between astronomical objects is based on theory, and a theory is something which is constructed by the human mind and which therefore need not enshrine some everlasting truth. When we come to discuss the phenomenon of the bending of light rays, we shall see that this laboratory conclusion about the nature of the paths of light rays cannot always be sustained.

Distance in the Solar System

After this brief survey of the main difficulties of principle that confront the astronomer when he tries to determine the distances of the objects in which he is interested, let us examine the procedures that he in fact employs. The famous astronomer Johannes Kepler, who lived from 1571 to 1630, showed how it was possible to set up a scale model of the solar system without having any accurate notion of the distances involved in terms of miles or kilometers. Suppose that Kepler came back to earth today and that we carefully concealed from him all the accumulated astronomical knowledge of the past 327 years. But suppose that we showed him how to work our modern telescopes and clocks and then suggested that he go ahead and, with this greatly improved instrumentation, repeat the investigations that made him famous. Kepler would no doubt begin by measuring, each day, the angular diameter of the sun. By methods which would be familiar to him, even if they are not to all of us today, he would, by measuring certain other angles at noon each day, determine the sun's position relative to the background of the stars. Note the important point that his observations consist entirely of measuring *angles* and not at all of measuring *distances*.

The changes in the angular diameter of the sun from day to day he would interpret by saying that it was the (unknown) distance of the earth from the sun that was varying; the apparent motion of the sun relative to the distant stars, sometimes faster and sometimes slower during the course of the year, would eventually lead him to the conclusion that the earth was moving round the sun in an ellipse, with the sun in one focus. He would draw on a piece of paper an accurate reproduction of this ellipse, with all the distances relatively correct but with not one of them known in terms of miles or kilometers. Having completed this operation he would take each planet in turn and, again observing angles only, find that each planet moved in an ellipse with the sun in one focus, the reproduction of each ellipse being on the same scale as that used for the earth's orbit.

But in all this there is one point of theory that would seem self-evident to Kepler, though it would not be so to a modern mathematician looking over his work. He would take it for granted that the interrelations between the angles he was measuring and the distances involved were those of Euclidean geometry and that, moreover, the light rays reaching him from the objects he was studying traveled along Euclidean straight lines. To this day astronomers, in dealing with the solar system, make, for most purposes, the some geometrical assumptions that Kepler did. And they express the distances in terms of the astronomical unit of distance, which is nearly, though not quite, the same as the earth's mean distance from the sun.

Turning the astronomical unit into miles or kilometers is a separate problem. Since a scale model of the solar system is at our disposal, all that is required is the measurement of one distance in the system in order to fix the scale. To obtain this, the earth must first be surveyed and the distances between astronomical observatories must be determined. The base lines from which the survey starts are measured, not with the standard meter-bar, but with flexible metal tapes stretched to a given tension, and the belief that a consistent system of distance relations between points on the earth's surface can be established on such a basis depends on a good deal of theory. There must be a theory of the nature of a metal and theories of dynamics and of elasticity—here the classical Newtonian theories are employed—before the surveyors can be sure that using the metal tapes in the way they do is likely to provide an internally self-consistent network of distances. It is also taken for granted that the geometry which interrelates the measurements is the Euclidean, the surface of the earth being regarded as a mathematical surface in a three-dimensional Euclidean space.

Suppose then, that the Euclidean straight-line distance between two widely separated observatories A and B has been thus established, partly by measurements and partly by geometrical calculation. A planet P having been selected, the angles between the lines AP and AB and between BP and AB are observed simultaneously at A and B. Again by means of Euclidean geometry, the distances from A and B to the planet can be calculated and the scale of the solar system determined. In all this procedure, the important elements of principle are: firstly, that all measurements are angular measurements, except for the distances between the ends of the base lines on earth that are established by use of flexible metal tapes; secondly, that calculations are performed through the formulae of Euclidean geometry; thirdly, that the paths of light rays are straight lines in the Euclidean sense; and fourthly, that it must be possible to attach a meaning to the statement that two widely separated events are simultaneous, the two events in question being the observations of the planet from the observatories A and B.

Time and Distance

It is not only by way of this question of simultaneity that time has reared its ugly head; our resurrected Kepler had already tacitly incorporated the notion of time intervals into his scale model of the solar system through his procedure of making observations on successive *days* and in successive *years*. He must have known what a day was and what a year was before he could act in the way he did. And, indeed, the astronomers of today introduce the notion of time into distance computations in the solar system in a much more indirect and yet fundamental way. They have at their disposal all the dynamical theory and the theory of gravitation which were first invented by Isaac Newton in the second half of the 17th century and whose detailed consequences have engaged the attention of mathematical astronomers ever since. As G. M. Clemence (*1*) has pointed out, the unit of time employed in these theories is the average value of the mean solar day during the 18th and 19th centuries, and the astronomical unit of distance is defined as the theoretically predicted radius of the circular orbit around the sun of a planet of very small mass moving at an angular rate, expressed by a fraction given to 11 places of decimals. Now the Newtonian theory of planetary motion contains two very important principles which underlie the three laws of motion. These are, firstly, the postulate that all angular and distance measurements in the universe can be manipulated by the rules of Euclidean geometry and, secondly, that there exists an absolute time. The absolute time is pragmatically defined with reference to the mean solar day during the two centuries referred to, and it is one of the merits of the Newtonian theory that distance measurements and time measurements can be manipulated separately—the first, as I have said, by the rules of Euclidean geometry; the second, on the principle that time is a scalar and that time intervals are not affected by the geometry that is being employed for distances.

I would like to put forward here the view that astronomers are not engaged in discovering eternal truths about the dimensions of the solar system relative to the selected base lines on earth, or even relative to an unknown mean distance of the earth from the sun. They are not even achieving approximations to these truths within some limit of experimental error. In my opinion, the combination of measurements, geometrical argument, and dynamical theory serves to establish an internally self-consistent scheme of distance relationships with which time relations are inextricably intermingled. The magnitudes of the errors do not measure the departure of the scheme from some ideal eternal truth laid up in heaven; rather do they establish a measure of the degree of self-consistency. The adequacy of the scheme can be tested by using it to make predictions of future events—for example, to predict in what part of the sky the planet Mars will be at some date in the future. The prediction can eventually be checked by observation, and this observation in turn will be incorporated into the scheme and will modify it. That the modification may be very slight is irrelevant; its acceptance by astronomers as a natural corollary of their work is the interesting point.

Special Relativity

You will be wondering by this time why I included in my title the subject of relativity, since I have so far made no reference to this theory. The reason is that, in my opinion, the theories of special and general relativity cannot be discussed *in vacuo* but must be envisaged in some context of observational data. You will remember that special relativity owed a good part of its origin to the Michelson-Morley experiment, which was intended to measure the velocity of the earth in its orbit by a purely optical experiment performed in a laboratory from which no celestial object could be observed. The expectation of success depended on calculations based on the principles of the Newtonian theory of motion applied both to the motion of the earth and to the motion of light. The experiment revealed that the expectation was unjustified—that the orbital speed of the earth could not be measured in this way and that this was not due to errors of observation but was a genuine null result.

The special relativity interpretation of this conclusion idealized the situation to the extent that the effect of gravitation was omitted and the earth was regarded as moving in a Euclidean straight line, with constant speed, during the very short time interval occupied by the experiment. It was then shown, firstly, that the hypothesis of the validity of Euclidean geometry could be retained but that, secondly, the assumption of a single absolute time would have to be rejected. On the basis of these two postulates, a new theory of motion could be worked out from which the null result of the Michelson-Morley experiment could be predicted. More precisely, if there are two frames of reference for distance measurements, distances in each being established by identical procedures, and if the frames of reference are in constant relative motion as judged from either frame, then to each frame there must be associated a system of timekeeping of such a kind that the velocity of light has the same value relative to either frame.

The important points that are brought out by special relativity are, firstly, that there is no absolute theory of motion and of the associated dynamics; secondly, that time and distance measurements can be much more closely interwoven than they are in the Newtonian theory of motion; and thirdly, that as a result of this closer interweaving, two events can be simultaneous in one frame of reference but not in another and, concomitantly, that the distance between two events is not an absolute but depends on the frame of reference relative to which it is measured. The device that is employed in relativity theory for interlocking closely time and distance measurements is to use what may be called a four-dimensional geometrical representation for all the events under contemplation. Each event is "plotted," so to speak, as a "point" having four, instead of the usual three, coordinates; three of these fix the position in space of the event relative to some frame of reference, the fourth is a coordinate specifying the instant of occurrence of the event in the same frame of reference.

My own personal view of this procedure is that a geometrical manifold used for such a representation is a mathematical device that is very valuable for purposes of calculation, but I am not convinced that it is anything more than this. A convenient name for the four-dimensional manifold is "space-time," but as for its "reality" or its "physical existence," I would not like to commit myself because I do not know what these terms mean. What I do know, as a theoretician, is that I can make calculations and predict the circumstances of the motions of bodies by using the mathematical technique of the space-time representation.

Let us return to the astronomers in the observatories *A* and *B* who are engaged in determining the distance of the planet *P*. You will remember that an

essential part of the procedure was that their observations had, in principle, to be made at the same instant. But this simultaneity is now dependent on the selection of one of the reference frames of special relativity; there is no absolute definition available. Nor is there any absolute definition of the distance between the two observatories. We might think that we could select the frame of reference relative to which A and B were at rest, which I will call the zero frame, and assume that the time associated with the zero frame was the time kept by the observatory clocks. But if we imagine a second frame of reference moving with uniform speed u with respect to the zero frame, then, in terms of the time appropriate to this new frame, the astronomers at A and at B would not be carrying out their observations simultaneously and the distance from A to B would have a value that differed from that in the zero frame. This difference would depend on the ratio of the square of u to the square of the velocity of light, c.

Now it might be thought that we could eliminate these difficulties by simply asserting that the zero frame had priority over all the other possible ones, but this cutting of the Gordian knot will not do, for there is another principle inherent in relativity theory to which I have not yet referred. It is this: Reference frames, even of the combined space and time variety used in relativity, are elements introduced into the description of the physical situation by the investigator and are therefore alterable at will. Nothing essential must therefore be made to depend on the choice of one reference frame rather than another; all reference frames must be on an equal footing, and we should fix attention on those conclusions that can be demonstrated to be equally valid in every reference frame. It happens that the numerical value of a distance between two events is not an invariant quantity in special relativity but depends on the selected reference frame, and the same applies to the time interval between any pair of events. This is not to say that measures of distances and of time intervals are valueless but that the conditions of measurement must be carefully stated and the relativity of the results must be firmly kept in mind.

If you have followed me so far, you will no doubt have noticed that there is an apparent contradiction between what I have just said about special relativity and what I said earlier about the procedure actually employed by astronomers in establishing distances in the solar system. I have emphasized that, in doing so, these scientists take it for granted that distance is an absolute in the Euclidean sense and that time is also an absolute in the sense of Newtonian dynamical theory.

Since astronomers are acquainted with special relativity, why do they continue to act as if they were not? The answer is that the differences inherent in the use of one frame of reference rather than another depend on the ratio of the square of the relative velocity of the frames to the square of the velocity of light. Now the velocity of light is 186,000 miles per second, and the relative velocities of objects in the solar system rarely attain, say, 70 miles per second. Thus, the ratio of the squares of these velocities will be found to introduce changes in the distances that amount at most to one part in ten million. But the astronomical unit of distance is determined to within the very much larger error of one part in five thousand. Thus, if this is the kind of accuracy we are working to, or, as I would prefer to put it, if this is the measure of the internal self-consistency we aim at, special relativity can be disregarded in direct calculations of distances. But it is not self-evident that the effects of relative velocity on our distance and time computations may not give rise to observable differences from the predictions of Newtonian theory when these effects can be shown to be cumulative in time. To consider this type of question we must pass on to general relativity.

General Relativity and the Solar System

Expositions of general relativity very often give the impression that the only difference between this theory and special relativity lies in the character of the relative motion of the "time and space" frames of reference employed. Whereas in special relativity the frames are in uniform relative motion, in general relativity mutually accelerated frames are considered. This is certainly one aspect of general relativity, but, by itself, the introduction of mutually accelerated frames is not sufficient. The essence of the difference between the two theories is more subtle; it lies in a change of character of the four-dimensional geometrical representation of the events under contemplation. Whereas in special relativity this representation has the geometrical characteristic known technically as "flatness," in general relativity the representations are "curved."

It is not easy to explain this essential difference to nonmathematicians, especially as the terms *flat* and *curved* have so many connotations that their very use in this technical connection is misleading. One can but try to use an analogy drawn from geometrical manifolds of two, instead of four, dimensions. The Euclidean plane is one such two-dimensional manifold, the surface of a sphere is another; the former possesses the geometrical attribute of flatness, the latter, that of curvature.

This difference manifests itself in the geometries appropriate to the two surfaces. Thus, in the Euclidean plane, straight lines are of infinite length, the three angles of a triangle have a sum equal to π, the sum of the squares of the two sides of a right-angled triangle is equal to the square of the hypotenuse, and so on. On the surface of a sphere, great circles are the analogs of straight lines, and they are of finite length; the angles of a spherical triangle do not have a sum equal to π; and Pythagoras' theorem in the form I have stated it is no longer true.

The four-dimensional space-times of general relativity differ from one another and from that employed in special relativity in analogous but far more complicated ways. This is not only because four, as against two, dimensions give rise to greater intricacy but also because one of the dimensions is interpreted physically as referring to the time relations between events. The time and distance measurements made by astronomers are thus interwoven in a more elaborate way than they are in special relativity, and they lead to a new theory of motion and of dynamics. In general relativity it is postulated that each physical situation has its own appropriate space-time, the connection between the two being made through Einstein's gravitational equations. Moreover, the only effects that are taken into account are those of relative velocity (as in special relativity), gravitational attractions, and a peculiar force which is either one of repulsion or of attraction, according as the so-called cosmical constant is a positive or negative number. The physical situation, consisting of a very massive sun around which move planets of relatively infinitesimal mass, has one space-time representation; the whole astronomical universe of galaxies has another, with quite different properties of

curvature. Thus, once again, I would regard these space-times as devices for calculation purposes, rather than as entities having any kind of "physical existence."

But to return to our astronomers studying the solar system. The space-time representation appropriate to this physical situation was worked out almost immediately after Einstein had propounded, in 1917, the general theory of relativity. The geometry of space, by which the relations between the angles and distances that the astronomers measure are calculated, can be shown to be so nearly Euclidean that this classical geometry can be safely employed for most purposes. Similarly, there is a kind of time appropriate to the physical situation which possesses nearly, but not quite, the properties of absolute Newtonian time.

But do not let us be hasty and jump to the conclusion that, if the departures from the Newtonian theories of dynamics and gravitation are so small, we can dispense with general relativity. For these departures can have cumulative effects when we are concerned with predicting how a body in the solar system will move. Observations of the planet Mercury, which has an orbit lying fairly close to the sun, where the gravitational field is strongest, and which also moves with a relatively high orbital speed, had revealed, long before the advent of general relativity, an unexplained motion in space of the planet's point of closest approach to the sun. The amount of this motion was some 43 seconds of arc per terrestrial century, and it was found that general relativity could interpret it in terms of the mass of the sun and the dimensions of the orbit of Mercury.

You might be interested to know what the corresponding figure for an artificial satellite of the earth would be. Let us suppose that the earth is perfectly spherical—which it is not—and that the maximum and minimum distances of the satellite from the surface of the earth are 200 and 600 miles, respectively; and let us ignore the frictional resistance of the earth's atmosphere. Then the point of closest approach of the satellite's orbit would move in space through 1324 seconds of arc in a century. The figure is large compared with that for Mercury in spite of the fact that the earth's gravitational field is incomparably weaker than the sun's and that the satellite's average speed in its orbit is only about one-sixth of Mercury's. The cumulative gain lies in the number of revolutions: in 100 years Mercury goes round the sun about 414 times, whereas in the same period the satellite would circumnavigate the earth nearly 540,000 times.

But to return to the sun. Another striking effect of the non-Euclidean character of the space-time appropriate to the solar system is the phenomenon of the bending of light rays. When the stars beyond the sun are photographed during a total solar eclipse and when the picture is compared with one taken at night, it is observed that the stars appear to be relatively further apart in the eclipse picture than in the other. An effect of this kind is predicted by general relativity, because the paths of light rays in the space-time can be regarded as Euclidean straight lines only in regions remote from the sun, where its gravitational effect is weak. Near the sun itself the geometry departs sufficiently from the Euclidean to give an observable difference. The theoretical prediction is that the distortion of position for a star seen at grazing incidence beyond the sun's disc would be 1.75 seconds of arc. As far as I am able to judge from the results of observations made during six total eclipses since 1919, this figure corresponds to that found from observation.

Conclusions

Let me now try to summarize, in conclusion. Distance determinations in the solar system have always, in the main, consisted of the measurements of angles and of time intervals. Determinations of the positions occupied by a celestial body at successive instants of time have necessarily involved some theory of dynamics and of gravitation. The theories of relativity have shown that time measurements can be interconnected with the distances deduced from the angular measurements in a more intimate way than that postulated by Newton. This has had as a consequence the development of dynamical and gravitational theories different from his. In addition, each physical situation has its own system of time and distance interconnections, obtained through the mathematical device of four-dimensional geometrical representations in which time is regarded as a fourth coordinate interwoven with the three spatial coordinates. General relativity has achieved an interpretation of phenomena in the motions of the planets and of light which had escaped the Newtonian net. I wish I had the space to explain, and that you had the endurance required to absorb, the further applications of these ideas to the universe at large, where distances are measured in millions of light-years instead of in millions of miles.

Reference

1. G. M. Clemence, *Science* 123, 567 (1956).

The Search for Anticancer Antibiotics

Some Theoretical Problems

G. F. Gause

Although the empirical approach is inevitable in the search for anticancer antibiotics, the efficiency of the screening increases when one combines empiricism with the theoretical analysis of specific metabolic differences between normal and malignant cells and utilizes these differences for the detection of substances that selectively inhibit those aspects of metabolism which are peculiar to the cancer cell.

As is well known, much work still remains to be done by the biochemists on the analysis of the specific metabolic differences between normal and malignant cells. It seems likely, however, that hereditary injury of the respiratory system of the cancer cell is one of the established characteristics of malignant growth. This impairment was first observed by Warburg about thirty years ago and, in spite of some criticism, has been entirely substantiated by more recent studies (*1, 2*). Measurements of the metabolism of malignant human cells show that hereditary deficiency of respiration is sometimes accompanied by a hereditary decrease, and sometimes by an increase, of aerobic glycolysis in the various strains of cancer cells (*3*).

It is to be recalled that alterations of metabolism peculiar to malignant growth can take place in cells of various living organisms. Julian Huxley was right in his recent generalizations (*4*) that "cancer is not merely a medical problem; it is a biological phenomenon, whose elucidation is bound up with advances in a number of key fields of present-day biology. . . . Neoplastic tumours are widespread in the organic realm."

The author is professor in the Institute for Antibiotic Research of the Academy of Medical Sciences of the U.S.S.R., Moscow. This article is based on a paper presented in New York on 21 Nov. 1957 at the Pasteur Fermentation Centennial sponsored by Chas. Pfizer & Co., Inc.

If Huxley is correct, could one not obtain some equivalents of cancer cells in microbiology? That is, could one not obtain biochemical mutants of microorganisms with hereditary impairment of their respiratory system and, most important of all, utilize these mutants as tests in screening for antibiotics that selectively inhibit malignant growth?

Microorganisms with Injured Oxidation

Some studies in this direction have been recently made in the Institute for Antibiotic Research of the Academy of Medical Sciences in Moscow. The first stage of investigations consisted in the production of biochemical mutants of microorganisms with injured oxidation. Gause, Kochetkova, and Vladimirova (*5*) used for this work yeast cells, *Saccharomyces cerevisiae* strain AN-2. Under the action of trypaflavine, which, according to Ephrussi and his collaborators (*6*), induces in yeast mutations with a deficient cytochrome system, we obtained six different mutant strains. The data on the respiration and aerobic glycolysis of these strains are given in Table 1. In all six mutant strains studied by us there was a strong hereditary injury of the respiration; the oxygen consumption in various mutant strains was decreased to 1/10 to 1/200 of that of the parent cells. It is interesting to record in this connection that, in some mutants, the injury to respiration was accompanied by an increase of aerobic glycolysis (strains 7, 22, and 25); in others, aerobic glycolysis was only slightly enhanced (strains 11 and 26); and finally, in one of the mutant cultures (No. 33), the aerobic glycolysis was decreased as compared with the value characteristic for the parent culture. In other words, in biochemical mutants of yeast with impaired oxidation, aerobic glycolysis can change in different directions, in the same way as it was observed in studies of aerobic glycolysis of malignant cells belonging to different strains. It is only now, one hundred years since Pasteur began his work in this important field, that we come to the understanding that, in biochemical mutants, aerobic glycolysis can change independently of alteration in the respiratory system.

Furthermore, we obtained mutant strains of yeast with injured respiration under the action of ultraviolet radiation and of camphor; the latter, according to Bauch (*7*), possesses strong mutagenic action upon yeasts. The data on the respiration and aerobic glycolysis of these strains are presented in Table 1.

For the rapid detection of the biochemical mutants of yeast cells with deficient oxidation, we worked out a specific method of staining their colonies, enabling us to distinguish by color the colonies of mutants from those of the normal cells. The leucobase of methylene blue was used for this purpose. Roskin (*8*) observed that normal human cells rapidly oxidize the colorless leucobase and stain themselves with deep blue color, whereas cancer cells under the same conditions of experiment remain colorless because of their deficiency in respiration. We observed that this principle of differential staining can be employed for diagnostic purposes to detect the biochemical mutants of yeast cells with impaired respiration, if the leucobase of methylene blue is added to the beer-wort agar media before the latter is poured into the petri dishes. The growing colonies of normal yeasts acquire deep blue color, whereas the colonies of mutants remain colorless, to the extent that they are unable to oxidize leucobase into methylene blue because of the deficiency of their respiratory system.

Besides yeast cells, Gause, Kochetkova, and Vladimirova (*9*) also used staphylococci for producing biochemical mutants with deficient respiration. The staphylococci turned out to be particularly useful as tests for the detection of substances possessing selective inhibitory action upon cells with an impaired respiratory system. Under the action of ultraviolet radiation of *Staphylococcus aureus* strain 209, we obtained three mutant cultures, Nos. 1, 2, and 3, which differed from the original parent strain by the small size of their colonies, by a de-

creased growth rate, and by a hereditary deficiency of respiration, as is shown by the data presented in Table 2. Table 2 shows that, in different strains of mutant staphylococci, the consumption of oxygen decreases to 40 to 65 percent of that of the parent culture. The decrease of oxygen consumption in the biochemical mutants of staphylococci is not as great as it is in the biochemical mutants of yeasts, in which oxidation, as is shown by the data of Table 1, may sometimes decrease to 1/200 of that of the parent culture—that is, it is practically excluded under aerobic conditions. As is well known, the consumption of oxygen in cancer cells may often decrease to half of the value characteristic for normal cells. In other words, the impairment of the respiratory system of cancer cells is quantitatively more like that of biochemical mutants of staphylococci than it is like the respiratory deficiency in the mutant strains of yeasts.

Some biochemical differences between mutant strains of staphylococci Nos. 1, 2, and 3 will not be considered at present. Let me only note that the respiration of all these mutant strains is much less sensitive to cyanide than is the respiration of the parent culture. This fact points to a deficiency of the cytochrome system as a cause of impaired respiration in the mutant strains.

Use of Mutants for Testing

Having outlined briefly some characteristics of the biochemical mutants of yeast and staphylococci with impaired respiration which have been obtained by us, we can now pass on to what seems to be the essential part of the investigation —namely, the use of these mutants as tests in screening for antibiotics that selectively inhibit cells with impaired respiratory systems. For this purpose, 2500 different cultures of actinomycetes freshly isolated from various soils were streaked upon nutritive agar in petri dishes, and after 48 hours of growth at 28°C they were cross-streaked by suspensions of different microorganisms, including parent cultures and mutant strains of staphylococci and yeast cells. According to the data obtained by T. P. Preobrazhenskaia and E. S. Kudrina (*10*), 53 cultures (that is, about 2 percent) possessed selective inhibitory action upon the biochemical mutants of staphylococci with impaired oxidation. These cultures did not inhibit the growth of

Table 1. Respiration and aerobic glycolysis in biochemical mutants of *Saccharomyces cerevisiae* with impaired oxidation (from Gause, Kochetkova and Vladimirova, *5*). Q_{O_2} shows the consumption of oxygen in cubic millimeters per hour, and Q_{CO_2} gives the production of carbon dioxide in cubic millimeters per hour, calculated for 1 milligram of the dry weight of yeast.

Culture	Respiration		Aerobic glycolysis	
	Number of experiments	Q_{O_2}	Number of experiments	Q_{CO_2}
Control (parent)	19	41.8	24	326.0
Trypaflavine 7	4	4.2	6	427.0
Trypaflavine 11	4	5.1	4	388.0
Trypaflavine 22	4	0.2	6	414.0
Trypaflavine 25	4	0.2	4	411.7
Trypaflavine 33	4	6.0	4	282.0
Trypaflavine 26	4	5.2	4	360.5
Camphor 27	4	4.2	2	339.3
Camphor 4	4	3.5	2	386.0
Camphor 23	4	10.5	4	353.0
Camphor 2	4	10.9	4	410.0
Ultraviolet 10	8	2.9	8	321.0



Fig. 1. Selective inhibitory action of a culture of actinomycete upon mutant staphylococci with impaired oxidation.



Fig. 2. Selective inhibitory action of a culture of actinomycete upon mutant strains of staphylococci and of yeast cells with impaired oxidation.

Table 2. Respiration in biochemical mutants of *Staphylococcus aureus* 209 with impaired oxidation (from Gause, Kochetkova and Vladimirova, *9*). Q_{O_2} shows the consumption of oxygen in cubic millimeters per hour calculated for 1 milligram of the dry weight of bacteria.

Culture	Number of experiments	Q_{O_2}
First series		
Control (parent)	10	95.2
Ultraviolet-1	4	65.0
Ultraviolet-2	8	49.5
Ultraviolet-3	4	44.0
Second series		
Control (parent)	10	104.5
Ultraviolet-1	6	64.5
Ultraviolet-2	6	51.7
Ultraviolet-3	6	41.3

normal staphylococci belonging to different strains, nor did they inhibit the growth of the other test microorganisms employed, as is shown in Fig. 1. Therefore, in the usual screening program, these 53 cultures would not be recognized as antagonists and probably would be discarded. Nevertheless, these cultures produce specific antibiotic substances that selectively inhibit the growth of staphylococci with deficient respiration. In this way, the use of biochemical mutants of staphylococci helps us to detect antibiotics which remain "invisible" if the usual method of investigation is employed.

The 53 cultures mentioned above belonged mostly to type 1, which is represented in Fig. 1 These cultures selectively inhibited the growth of only mutant strains of staphylococci with impaired respiration; they were not active against normal staphylococci, yeast mutants, or the other microorganisms employed. Ten of these cultures produced chemical substances which not only inhibited the growth of biochemical mutants of staphylococci but also inhibited in vitro the cells of ascites tumors of mice.

The antibiotic action of the second type, which is shown in Fig. 2, was encountered more rarely. In this case, antagonists inhibited the growth of mutants with deficient respiration in staphylococci as well as in yeasts, whereas the growth of the parent cultures and of the other microorganisms was not affected. We observed only eight antagonists of this type; among these, six cultures inhibited in vitro the cells of ascites tumors of mice.

Some cultures of actinomycetes which selectively inhibit, in petri dishes, the growth of biochemical mutants of microorganisms with deficient respiration, possess also the capacity to produce selectively inhibiting substances in the course of their submerged growth in liquid nutritive media. The isolation of the active substances and the study of their chemical nature are of great interest.

From cultures of various actinomycetes, M. G. Brazhnikova, T. A. Uspenskaia, and I. N. Kovsharova (*11*) isolated chemical substances that possessed selective inhibitory action upon the biochemical mutants of staphylococci with deficient respiration. One of these, antibiotic No. 992, was obtained in crystalline form. This substance is inactive toward normal staphylococci and other microorganisms, but it inhibits the growth of biochemical mutants of staphylococci with deficient respiration (strain ultraviolet-3) in the dilution of 1/5,000,000. That is, the mechanism of action of this antibiotic is directly opposite to that of albomycin, an antibiotic which inhibits only the growth of normal staphylococci and does not affect mutants with deficient respiration (*9*). According to the data of V. A. Shorin and O. K. Rossolimo (*12*), antibiotic No. 992 slightly inhibits in vivo the growth of experimental ascites tumors of mice.

Conclusion

It is too early to say at present whether the chemical substances that selectively inhibit the growth of biochemical mutants of microorganisms might acquire some practical importance in the future for the treatment of malignant growth. But it is already clear that these substances are very interesting from the theoretical viewpoint. The biochemical mutants give us an opportunity to select substances with definite mechanisms of inhibitory action instead of carrying out a purely empirical search for new antibiotics.

The deficiency of respiration may depend upon many different enzymes, and it should be subjected to special analysis. It was found, for example, that mutant strains of staphylococci with deficient respiration (ultraviolet-2 and ultraviolet-3) are not identical. In strain ultraviolet-3 the respiration is more strongly injured and is less sensitive to cyanides than it is in strain ultraviolet-2. We observed antibiotics which did not inhibit the growth of common microorganisms and were at the same time active only against mutants of ultraviolet-2, but not against mutants of ultraviolet-3. In this way the biochemical mutants of microorganisms give us an opportunity to detect "invisible" antibiotic substances, selectively inhibiting some specific biochemical systems of the living cell. It seems probable that further work along these lines may stimulate closer cooperation between those conducting screening programs for antibiotics and biochemists; such cooperation might be helpful in the design of screening programs.

In summary, we can say that, in screening for new anticancer antibiotics, the two following generalizations may be helpful. (i) There is a possibility of obtaining the equivalents of cancer cells in microbiology—that is, biochemical mutants of microorganisms with deficient respiration and probably with some other alterations in cell metabolism which are specific for malignant growth. (ii) There is a possibility of using these biochemical mutants for the detection of new substances that selectively inhibit those specific features of cell metabolism which are characteristic of the malignant growth.

References and Notes

1. O. Warburg, *Uber den Stoffwechsel der Tumoren* (Springer, Berlin, 1926); *Science* 124, 269 (1956); *Experientia* 13, 125 (1957).
2. H. Lettré *et al.*, *Naturwisssenschaften* 44, 335 (1957).
3. J. Leslie *et al.*, *Nature* 178, 1179 (1956).
4. J. Huxley, *Biol. Revs. Cambridge Phil. Soc.* 31, 474 (1956).
5. G. F. Gause, G. V. Kochetkova, G. B. Vladimirova, *Doklady Akad. Nauk S.S.S.R.* 117, 1 (1957).
6. B. Ephrussi *et al.*, *Ann. inst. Pasteur.* 76, 351, 510 (1949).
7. R. Bauch, *Naturwissenschaften* 29, 503 (1941).
8. G. J. Roskin, *Microscopiceskaia Technika* (Moscow, 1951).
9. G. F. Gause, G. V. Kochetkova, G. B. Vladimirova, *Doklady Akad. Nauk. S.S.S.R.* 117, 4 (1957).
10. T. P. Preobrazhenskaia and E. S. Kudrina, in press.
11. M. G. Brazhnikova, T. A. Uspenskaia, I. N. Kovsharova, in press.
12. V. A. Shorin and O. K. Rossolimo, in press.

Arno B. Luckhardt, Physiologist

Arno Benedict Luckhardt was born in Chicago, Illinois, on 26 August 1885, the son of Gustav Adolph and Aurelia (Weber) Luckhardt. At the age of 12 he entered Conception College—then a Benedictine abbey—in Missouri, and in 1903 he entered the University of Chicago, from which he received the B.S. degree in 1906. This was followed by the Ph.D. degree in 1911 and the M.D. degree from Rush Medical College in 1912. On 24 April of the same year he married Luella Catherine LaBolle, and she and their three children—Hilmar Francis, Paul Gregory and Mary Aurelia (Miesse)—survive him.

His entire professional life was spent at the University of Chicago. Beginning as an assistant in bacteriology in 1908, he joined Anton Julius Carlson in the department of physiology in 1909 and advanced through the department, attaining the rank of professor in 1923 and the designation of Dr. William Beaumont Distinguished Service Professor in 1947. After retiring to the status of distinguished service professor emeritus in 1950, he continued his professional interests and activities to the end of his life. He died in Miami Beach, Florida, on 6 November 1957, and is buried near the former home of his wife, at Somonauk, Illinois.

This simple chronological statement does not begin to do justice to the talented, versatile, and dedicated person that was Arno Luckhardt. He was, first and foremost, a teacher and investigator in physiology. His pupils were many, and he was especially beloved by his graduate students, to whom he gave himself unstintingly. He will be best remembered for his introduction of ethylene gas as an anesthetic, but his contributions relative to the physiology of gastric secretion, gastrointestinal motility, the visceral sensory nervous system, and the function of the parathyroid glands were equally outstanding. As a result of his work, for example, it became possible for the first time to keep experimental animals alive following complete removal of the parathyroid glands and to prevent and relieve parathyroid tetany, which customarily followed this operation; his methods were applied successfully in human surgery.

It was characteristic of Arno Luckhardt that when he became interested in the potential anesthetic properties of ethylene gas, which he was the first to recognize, and after having performed the appropriate experiments with animals, he and his associate, J. Bailey Carter, inhaled it and put themselves to sleep. A demonstration was given to physicians and surgeons on 14 March 1923, and within three days the gas was in use as an anesthetic at the Presbyterian Hospital of Chicago. Having become convinced that he had made a significant discovery, Luckhardt records the fact that he himself inhaled an ethylene-oxygen mixture to the point of anesthesia some 700 to 800 times, without any bad aftereffects. After 900 successful operations under ethylene-oxygen anesthesia had been recorded, it was given to the public and the profession free, and without patent rights to anyone; this is in striking contrast to the attempts at commercial exploitation that followed the introduction of ether anesthesia in 1846. Luckhardt's discovery not only resulted directly in the introduction of a new and improved anesthetic; it also gave added impetus to the search for other new agents and new methods of administering them, and to the steps leading to the creation of a new specialty of anesthesiology.

Arno Luckhardt was a man of many interests; he was attracted to the problems of dental care and cooperated actively with dentists and dental organizations in promoting higher professional standards in dental therapeutics and in dental journalism. He was also active in cultivating closer medical-dental relationships in the interest of obtaining a higher level of health care for the public. In 1930 he became a charter member of the Council on Dental Therapeutics of the American Dental Association and served on this council until 1948. In recognition of his services to dentistry he was made an honorary fellow of the American College of Dentists in 1933. On 4 November 1957, two days before his death, he was made an honorary member of the American Dental Association, at its meeting in Miami Beach, Florida, and addressed the association in response.

His wide interests included the history of the medical sciences, and he made significant contributions in many areas, notably to the record of William Beaumont's studies of the physiology of digestion. He collected Beaumontiana, and also a large and important library of books and pamphlets related to the history of medicine. But he was more than a collector; his early education in Medieval Latin gave him the ability and the urge to read and enjoy many classics of medicine in the original. He collaborated with James Henry Breasted in the interpretation of the Edwin Smith surgical papyrus, "the oldest scientific book in America and the oldest nucleus of really scientific medical knowledge in the world." He acquired a unique collection of medical manikins, which gave him much pleasure.

Luckhardt served on the Council of the American Physiological Society; he was secretary from 1930 to 1932 and president from 1932 to 1934. He was president of the Federation of American Societies for Experimental Biology in 1934. He was active in the Society for Experimental Biology and Medicine and served on its editorial board and as associate editor of the *Proceedings*. As a Rockefeller fellow he visited Germany in 1924–25 and during his visit was elected to membership in the Kaiserliche Akademie der Naturforscher. For many years he was a member of the Chicago Literary Club, and he served a term as president. He was one of the founders of the Gamma Alpha graduate scientific fraternity.

Scientist, scholar, and teacher, Arno B. Luckhardt made a great contribution to his university, his profession, his fellow scientists, and his pupils. Physiology, medicine, surgery, and dentistry have been enriched by his contributions to human welfare. But the man was greater than the sum of his parts; his memory will live long with the many who admired, respected, and loved him and his works.

FRANKLIN C. MCLEAN
University of Chicago

News of Science

National Science Foundation Budget

The National Science Foundation budget for fiscal year 1959 will be $140 million if the President's recommendations are followed by Congress. This amount is exactly $100 million greater that the 1958 appropriation; how the actual appropriation for 1959 will compare with the current $40 million will depend upon Congressional action. The proposed increases are spread over practically every item in the foundation's budget, but the largest increases are in the field of science education, for which approximately a fivefold increase has been recommended.

Estimated expenditures for 1958 and budget proposals for 1959, expressed in thousands of dollars, for some of the major items are given in Table 1. The proposed research facilities and the amounts for each are: biological research facilities, $2 million; southern hemisphere astrograph, $1.2 million; solar research telescope, $5 million; radio and optical astronomy facilities, $700,000; and university nuclear reactor facilities, $1.5 million.

The foundation plans to increase all of its fellowship programs and to start some new ones. The smallest increase is in the regular predoctoral fellowships, which will increase from 776 to 970 if appropriations are granted. The increase in regular postdoctoral fellowships is from 100 to 200; in senior postdoctoral fellowships from 42 to 100; and in science faculty fellowships from 90 to 300. The following new fellowship programs are planned: 2500 summer fellowships for high school science and mathematics teachers (these are in addition to the institutes that have been conducted for several years and that are mentioned below); 2000 summer fellowships for college and university teaching assistants to enable them to study or engage in research during the summer months; 800 pre-service fellowships for persons who would like to become high school teachers of science or mathematics but who have not received the necessary education; and 1250 training grants for fellows who would be chosen jointly by the foundation and the university at which the recipient planned to take his graduate work.

The summer institute program is in for a big increase if plans go through. Institutes for high school teachers would be increased in number from 103 to 320, and institutes for college teachers from 5 to 36. In addition, support would be available for 20 short-term (about 2 weeks) summer conferences on special topics for college teachers, for 10 summer institutes for members of the faculties of technical training institutes, and for 20 summer institutes for elementary school supervisors who want additional training in science or mathematics.

Institutes lasting through the academic year are also scheduled to increase in number. The increase for regular, full-time institutes for high school teachers is from 17 to 30, and for institutes (usually on Saturdays) for teachers who are in service from 30 to 200. Comparable in-service institutes for elementary school teachers have not been offered by the foundation in the past, but 125 are scheduled in the new budget.

Two entirely new programs are planned to give special opportunities for science instruction or research experience to students. One of these programs would provide science instruction for from 4 to 8 weeks, on 80 campuses, for 4000 able high school students. The other would provide research experience for 1500 selected college undergraduates in special institutes offered on 60 campuses.

Table 1. National Science Foundation budget in thousands of dollars.

Item	Estimated expenditure for 1958	Proposed budget for 1959
Support of basic research (approximately evenly divided between physical and biological sciences)	$16,000	$40,000
Research facilities (about 5/6 in physical sciences)	6,000	12,000
Survey and reports on scientific resources	174	290
Dissemination of scientific information	855	1,879
Attendance at international meetings	125	500
Research on scientific information problems	266	414
Pre- and postdoctoral fellowships	3,265	21,000
Institutes for teachers	9,790	35,500
Special projects in science education	655	15,400
Improvement of course content	611	6,000
International science education program	0	1,000
Clearinghouse for scientific manpower information	248	830

Parliament of Science

The planning committee for the AAAS Parliament of Science that is to take place in Washington, 15, 16, and 17 March (see editorial, 9 Feb.) has released a statement which includes the background philosophy that led to the meeting and that guides the committee in its planning:

"The power of man through science is currently assuming a new order of magnitude. Power has always been sought avidly. Sometimes it has been used disastrously; often it has been used wisely. How America shall keep abreast of the developments in science and scientific technology; how it shall help avoid disaster; how it shall ensure that new knowledge (the age-old synonym for power) will be used for the benefit of mankind in general and its citizens in particular are among the most important questions before the public today.

"But the American public is disturbed, worried, and confused. We were supposed to be well in the lead, scientifically and technologically. Now, all of a sudden, this comfortable assumption is challenged. We are 'behind.' It isn't clear just what this statement means, or whether the serious versions of its possible meanings are in fact true. But there is no denying the general concern, and the almost frantic determination to 'do something about it.'

"The concern and the determination are, we believe, justified. But it is imperative that we sort out our ideas, brush off as superficial certain spectacular but minor items, and try to see our problem in its true dimensions.

"Not long after the discovery of fission, we began to sense the fact that man's impending control of atomic and nuclear power made possible, and indeed made inevitable, the beginning of a new age. As the still more vast potentialities of fusion were made available for destructive purposes, and as it became clear

that these incredible forces would presently be tamed for nonmilitary use, the magnitude of our break with the past became visibly greater and greater.

"We are just beginning to see that even these advances, tremendous as they are, constitute the signal, rather than the substance, of what is to come. Our successful probing into the nucleus of the atom is but an example of the clear fact that science is entering a new and accelerated stage of advancement, which will give to man the possibility of control over his environment, over himself, and over his destiny, which we have as yet only vaguely sensed. By probing the atom, man is exploding into the universe. With prospects that are—just as they were in the case of nuclear energy—both marvelous and frightening, we are on the threshold of an equally revolutionary probing of the cell and of the mind.

"Man is breaking with the past, its limitations and its safeguards. The prize is greater than ever before—so are the risks. The question is not, 'Do we like this?' The question is, 'What role do the people of the United States wish to play in the drama of the future?' We cannot hide. We must not relax. How can we play a noble part?

"What concerns us here is far and away larger than any question about a satellite, or even about a battery of long-range guided missiles, although these dramatic devices have precipitated discussion, and have produced a readiness to consider drastic action.

"We are in fact saying that man is on the very edge of a new relation to the atom, to the cell, to himself, and to the universe in which he is set. Many forces have been active, but clearly it is science which has been chiefly instrumental in bringing about this new relation. The new relation will place new demands on all man's resources—especially on his capacity to handle this new power with restraint and decency.

"This scientific revolution will totally dwarf the industrial revolution and the other historical instances of great social change. It will be more compelling, and will pose more urgent problems, due both to the pace and the magnitude of the changes which now impend.

"What faces man is not, in any restricted sense, a scientific problem. Scientific issues are vitally and almost universally involved. The special knowledge of the scientist is necessary, to be sure; but that knowledge would be powerless or dangerous if it were not effectively pooled with the contributions of social scientists, humanists, statesmen, and philosophers and brought to the service of all segments of our society.

"What on earth—excuse us, it is difficult to adjust—what in the universe ought we to do? The scientists certainly have no arrogant illusion that they have the answers. But they do want to help. At the very least, they have the duty of briefing their colleagues in other fields. They are, moreover, convinced that the time is overripe for a more understanding collaboration between their special profession and the rest of society.

"Because it is urgent for scientists to organize their own thinking about the problems raised in the preceding paragraphs, and urgent for society to understand those problems and their implications, the Council (the legislative body) of the American Association for the Advancement of Science decided that the Association should convene a special meeting, widely representative of all fields of science, to consider certain definite and pressing aspects of the current problems. For obvious practical reasons, the discussion will be largely restricted to actual proposals for increasing support for science and improving education."

Exchange of Scientists

During the 5-year period 1952–56, 6108 scientists participated in the State Department's international educational exchange program. Of the total number of persons exchanged during that period, one out of every five was a scientist.

Of the nearly 5000 scientists who came to the U.S., the largest number were in the field of medicine; others were in engineering, chemistry, physics, mathematics, and biochemistry.

More than 1200 American scientists went abroad to lecture, study, or conduct advanced research. The largest groups were in physics, chemistry, engineering, and mathematics.

The range of scientific pursuits which relate to peaceful uses of atomic energy has grown tremendously in the last few years. During 1956, 183 exchanges under the State Department's program were related to such endeavors.

Research in Human Behavior

A citizens' group of 15 people closely associated with behavioral science urges a national effort to expand research in human behavior as a means of fostering improved international relations and strengthening national defense. In a 7000-word statement the group describes the perils of inaction in the "sciences of man" and outlines a series of recommendations for action by both governmental and private agencies.

The group, which is a temporary body, was organized some 3 months ago by James G. Miller, director of the Mental Health Research Institute at the University of Michigan. It came into being following a discussion with Vice President Richard Nixon. The proposed program was also discussed with James R. Killian, Jr., special assistant to the President for science and technology, and with members of his committee. The Ford Foundation awarded a grant to the AAAS to support the group's work.

The statement, which may be obtained from Dr. Miller, says, in part:

"The present situation facing our country calls for an evaluation of the role and potential contribution of behavioral science. This is the combined endeavor of many fields, investigating all aspects of behavior leading to understanding of human beings as individuals and in social relations.

"Behavioral science therefore includes many studies in the fields of anthropology, biochemistry, ecology, economics, genetics, geography, history, linguistics, mathematical statistics, neurology, pharmacology, physiology, political science, psychiatry, psychology, sociology, and zoology.

"Applications ramify into advertising, business administration, education, government, human engineering, labor relations, law, medicine, military science, operations research, personnel selection, public relations, and many other aspects of human endeavor. Some of these sciences are still in early stages of development, but American research in them at the moment has a clear lead over Russian, which is constricted by Communist dogma.

"Behavioral science has demonstrated its usefulness to human welfare and national security. Its further development could increase its contribution in areas of international relations, military defense, and national vigor.

"To accomplish these goals, the following recommendations are offered:

"I. Formation of an advisory panel of behavioral scientists to work closely with the special assistant to the President for science and technology. There is need for more understanding, backing, and use of behavioral science throughout the government and by the people of the United States, and for encouraging the scientists themselves in their research tasks.

"II. Provision of increased funds for behavioral science research, training, and facilities in the National Science Foundation, the Department of Defense, the National Institutes of Health, the Atomic Energy Commission, and other appropriate governmental and private agencies, in order to: (i) establish additional university programs or institutes to conduct research in designated crucial areas; (ii) finance more fellowships, both predoctoral and postdoctoral, especially in all the social sciences; (iii)

increase financial support for basic research in behavioral science; (iv) make available special facilities for behavioral science, including buildings and equipment; and (v) support centers devoted to foreign area studies."

Revised Apportionments on Fish and Game Restoration

Revised apportionments of federal aid funds to the states for restoration of fish and game have been announced by the Department of the Interior. The new apportionment is based on Treasury certifications of money available from excise taxes on certain sporting goods. Under the revisions the 48 States and Hawaii will receive $21,306,000 for fish and game restoration instead of the $25,130,000 previously announced. The revised figure for game restoration is $16,974,000 compared with the $19,130,000 allotted previously; the amount available for the restoration of fish is $4,332,000 instead of $6,000,000.

This money is distributed to the individual states and to Hawaii in accordance with formulas established by law and based upon license sales and land and water areas. Distribution is made on a reimbursable basis, with the states financing projects initially and being repaid $3 in federal aid money for each $4 expended, or a net expenditure of $1 state money and $3 from federal funds.

In addition to the afore-mentioned apportionments, Alaska is to receive $90,000 for game restoration and $75,000 for its sport fishery. Guam, Puerto Rico, and the Virgin Islands will each receive $12,000 for game restoration, and each will get $10,000 for fish restoration. These amounts are fixed by law rather than by formula.

Legislation also provides that no state can receive more than 5 percent of the total apportioned for game restoration, nor can it receive less than 0.5 percent of that amount. Limits for fish restoration apportionment are 5 percent maximum and 1 percent minimum.

Kolthoff Comments on Soviet Trip

I. M. Kolthoff, head of the analytical chemistry department of the University of Minnesota, has recently returned from the U.S.S.R., where he attended a symposium for scientists in his field and lectured at Moscow University. Some of his comments about the trip follow.

"When I arrived in Moscow December 1 it had been 12 years since my last visit to the Russian capital. The great official respect for scientists and the prestige of the Russian Academy of Sciences which were already quite evident in 1945 were made plain to me immediately again. At the airport, the reception committee expedited my passage through customs and immigration procedures with no fuss or red tape and no bother to me.

"I had been invited to Moscow to take part in a three-day symposium. . . . Other participants . . . included 18 scientists from the 'satellite' countries. . . . Harry Irving of Oxford University was the only other guest from a capitalist country.

"There were, in addition, three Chinese chemists present—two men and a woman. One of the men and the young lady had taken their Ph.D. degrees in the United States (University of Wisconsin, 1937, and University of Illinois, 1951). . . . The third Chinese chemist had won his Ph.D. at the University of Munich under the late Professor Hoenigschmidt, one of the world's experts on the determination of atomic weights.

"Although all three Chinese were avowed Communists and supporters of the Red Government in Peiping, the two American-educated chemists referred with affection to their stay in the United States. Indeed, throughout all the many talks and discussions which we had in Moscow, Irving and I never heard a disagreeable word about the United States and Britain.

"The Chinese trio spoke flawless English, and we conversed without inhibition. They admitted that their education system is not yet as advanced as Russia's; it is possible to get only a bachelor's degree in China. But they hope study for advanced degrees will become possible reasonably soon.

"I was impressed by the large number of Chinese studying for advanced degrees at Moscow University. This educational link between Russia and China is not without significance in world affairs, and I could not help regretting once again our government's policy which makes it impossible for us to play a part in training China's future scientific and educational leaders.

"The Chinese chemists invited me to visit them at home and proposed to have an official invitation extended to me on their return. I would have been happy to accept, but sadly had to admit that again in this respect State Department policy might stand in the way.

"This is too bad, for scientific visitors like myself are in a unique position to establish much-needed relations with countries like China. From scientific contacts frequently come exchanges of opinion on other matters.

"As to scientific research in the Soviet Union, we found that—as was true in 1945—most work is carried out in special institutes, which are under the auspices of the U.S.S.R. Academy of Sciences and entirely separate from a university. Except for the fact that most of the advanced research workers also teach at a university (with extra pay), there is no direct relationship between a university and the institutes. . . . Emphasis is entirely on fundamental research, for which apparently unlimited funds are being made available.

"In 1945, I had noticed that practically none of the instruments and equipment was of Russian make. This time I was impressed, if not awed, by the fact that almost all the instruments for refined measurement are made in Russia. . . . .

"The number of research workers in chemistry is greater in Russia than in this country. The quality of their work varies from excellent and good to acceptable. Their papers and journals, in general, compare favorably with those in the Western World. . . . [But] the great advancements in pure and applied science are brought about by contributions of an original and fundamental nature. In this respect the Russians have not got the lead over the West as far as chemistry is concerned. But they definitely hold their own. . . .

"There is no reason for hysteria now. But we do need fully to recognize the fact that fundamental research is the source of applied research and that no nation can remain strong without leadership in basic research."

Grants, Fellowships, and Awards

Behavioral sciences. The most serious difficulty encountered by the Russell Sage Foundation in its work for more effective collaboration between the social sciences and the professional services is the scarcity of trained personnel. In order to help meet this shortage, the foundation offers postdoctoral residencies in operating agencies or professional schools for the purpose of providing qualified sociologists, social psychologists, and anthropologists with specialized training and experience relevant to professional practice. Award recipients must not be over 35 years of age and must definitely be interested in careers involving applications of behavioral science in a field of professional practice. For information, write to the Russell Sage Foundation, 505 Park Ave., New York 22, N.Y.

Biophysics. The Massachusetts General Hospital has established a biophysics training program designed to assist candidates holding doctorate degrees in mathematics, physics, or engineering to apply their knowledge to biological and medical problems. This program is supported by the National Institutes of Health and is presented with the co-

operation of Massachusetts Institute of Technology. Appointments will be for a minimum period of two or three years. The salary range will depend on previous research experience and other qualifications. For information, communicate with the Physics Research Laboratory, Massachusetts General Hospital, Fruit St., Boston, Mass.

Gravity. The Gravity Research Foundation has announced that for the ninth year it is offering five awards for short essays on gravity. The awards will be made on 2 June for the best 1500-word paper on the possibilities of discovering: (i) some partial insulator, reflector or absorber of gravity, or (ii) some alloy, or other substance, the atoms of which can be agitated or rearranged by gravity to throw off heat, or (iii) some other reasonable method of harnessing, controlling, or neutralizing gravity. Essays must be received *before 15 April* by the Gravity Research Foundation, New Boston, N.H. The foundation will send detailed instructions on request.

Medical student research. The Lederle Laboratories Division of the American Cyanamid Company has announced that it is making available to medical schools throughout the United States and Canada its publication, *Lederle Medical Student Research Fellowships.* These fellowships, in amounts not exceeding $600 per year for any one individual, are intended to relieve in part the financial burden of students who desire to devote their summer vacations to research in the preclinical departments. The selection of students to receive such awards will be made by the dean of the medical school, or by the regularly constituted committee of the faculty charged with such selections.

News Briefs

Beginning 31 March, the Atomic Energy Commission will no longer accept new requests for gamma irradiation service from the public when the requested service is readily available commercially. A recent commission survey indicates that at least 16 academic and industrial organizations are prepared to provide gamma irradiation service on a commercial basis. A list of these organizations, showing the gamma flux available, the number and size of samples that can be accommodated, and the approximate amount of space available, may be obtained from the Office of Industrial Development, Atomic Energy Commission, Washington 25, D.C.

* * *

The Crop Protection and Pest Control Exhibition that is being organized by *World Crops,* international journal of agriculture, will be held 12–15 May at the Royal Horticultural Society's new hall in London. The organizers hope for a minimum attendance of 25,000, drawn from all over Europe.

* * *

Russell Cave, near Bridgeport, Ala., the oldest known site of human habitation in the southeastern United States, has been given to the Federal Government by the National Geographic Society as a national archeological monument.

* * *

As part of the safety precautions for the forthcoming nuclear tests at the Eniwetok Proving Ground, the U.S. Atomic Energy Commission has announced the danger area that will be established in the Pacific Ocean effective 5 April. The area is generally rectangular in shape and comprises roughly 390,000 square nautical miles. It is approximately the same size as the danger area used in the 1956 test series, but its east and west boundaries have been shifted approximately 120 nautical miles to the west. It is estimated that most, if not all, of the danger area will be disestablished during August 1958.

* * *

Plans for the new museum building of history and technology for the Smithsonian Institution have been approved by a Special Joint Committee of the Senate and House of Representatives, the Regents of the Smithsonian Institution, the Commission of Fine Arts, the National Capital Planning Commission, and the General Services Administration. Construction will start early next summer.

* * *

The following chemicals are wanted by the National Registry of Rare Chemicals, Armour Research Foundation of Illinois Institute of Technology, 13 W. 33rd St., Chicago 16, Ill.: 2-hydroxy-*n*-caprylic acid; α-methyl styrene oxide; *p*-dinitrosobenzene; *l*-ethylcyclohexanol; *m*-hydroxyphenylpropionic acid; monofluoroacetic anhydride; *n*-pentacosane; *l*-phenylcyclohexene; *n*-dotriacontane; 4-chloro-2-hydroxy-3,3-dimethylbutyric acid; pentaphenylethane; *n*-tetracosane; 2,4-dichloro-3,3-dimethylbutyric acid; mellon; cinchomeronic acid (pyridine-3:4-dicarboxylic acid); α,α-dimethylsuccinic acid; 1,2-anthraquinone; diethyl disulfide; humulene; and 2-methylacrylic acid (isocrotonic acid).

* * *

A millenary celebration for Al-Mas'udi, 10th-Century Arab geographer, traveler, and encyclopedist, was held recently in India at Muslim University, Aligarh, under the joint auspices of the Institute of Islamic Studies, Aligarh, and the Indian Society for the History of Science. In addition to the many Indian papers presented, there were some 30 papers from different parts of the world, including the United Kingdom, the United States, the Soviet Union, France, the Netherlands, Egypt, Lebanon, and Iran. Among those present from abroad were Bernard Lewis, Von Grunebaum, Myron Smith, Academician Tolstov, Nicola Ziadeh, and Said Naficy.

* * *

The Columbia Broadcasting System has announced that a televised symposium on science, "The Role of the Scientist in America's Future" will take place on 16 March from 5 to 6 P.M. Participants will include Joseph Kaplan, Howard L. Bevis, Clifford C. Furnas, and William L. Laurence of the *New York Times.*

* * *

The National Science Foundation has announced plans for a conference on "Research and Development and Its Impact on the Economy," to be held in Washington in the spring. The conference will focus attention on the economic importance of the nation's research and development activities, now estimated to account for annual expenditures of about $10 billion, more than 2 percent of the gross national product. The effect of such expenditures in stabilizing and promoting the growth of the economy, especially in periods of recession, will be one of the principal topics of discussion.

Scientists in the News

LAURENCE H. SNYDER, retiring president of the AAAS and chairman of its board of directors, will become president of the University of Hawaii on 1 July. He is at present dean of the Graduate College at the University of Oklahoma.

MANSON BENEDICT, professor of nuclear engineering, has been appointed head of the department of nuclear engineering that is to be established at Massachusetts Institute of Technology.

Under the new cultural and technical exchange agreement between the United States and the U.S.S.R., HUBERT A. LECHEVALIER, an associate professor of microbiology at the Rutgers Institute of Microbiology and codiscoverer of neomycin, plans to leave for Moscow in about 6 months. Lechevalier is an assistant to Selman A. Waksman, winner of the 1952 Nobel Prize in physiology and medicine as codiscoverer of streptomycin.

In exchange, the Soviet Union has agreed to send the Rutgers Institute G. K. SKRIABIN, a ranking member of the microbiological research team directed by N. A. Krassilnokov of the Soviet Academy of Sciences. Skriabin is expected to arrive here early in March.

BALTHASAR VAN DER POL, director of the International Radio Advisory Committee in Geneva, Switzerland, will hold the Victor Emanuel professorship at Cornell University for the spring term. Van der Pol gained international prominence for his discovery of relaxation oscillations, and he has made significant contributions to pure mathematics, particularly in number theory.

HARRY WEXLER, director of the Weather Bureau's Office of Meteorological Research, has been awarded the Department of Commerce gold medal "for significant contributions to the science of meteorology in extending the knowledge of the upper atmosphere, for the direction and encouragement of a broad program of meteorological research, and for outstanding leadership in the 1957–58 International Geophysical Year program." Wexler is chief scientist of the U.S.–IGY Antarctic Program.

HENRY G. HOUGHTON of Massachusetts Institute of Technology has received the American Meteorological Society's Award for outstanding services to the society. He was honored "for his important contributions to the growth of the American Meteorological Society through his guidance as president, as secretary, and his unfailing service in Council and Committee work."

Navy Distinguished Public Service Awards, the highest honor the Secretary of the Navy can bestow upon civilians, were presented recently to the director and four members of the staff of the Johns Hopkins University Applied Physics Laboratory, Silver Spring, Md. At the same time Navy Meritorious Public Service Citations, the second highest honor, were presented to four other members of the laboratory staff. All the awards were made for work on the Terrier guided missile.

Those who received the Distinguished Public Service Awards were RALPH E. GIBSON, director of the laboratory since 1947; ALEXANDER KOSSIAKOFF, assistant director for technical operations; HENRY H. PORTER, assistant director of planning; RICHARD B. KERSHNER, supervisor of the Terrier division; and ROBERT C. MORTON, supervisor of the Terrier weapons system group.

Those who received the Meritorious Public Service Citations were ALVIN R. EATON, JR., supervisor of the aerodynamics group; RICHARD T. ELLIS, supervisor of the Terrier development and test group; ROLAND W. LARSON, the supervisor of the Terrier electronics group; and THOMAS W. SHEPPARD, assistant supervisor of the Terrier division.

JOSEPH S. MITCHELL, Regius professor of physics at the University of Cambridge (England), will deliver Harvard University's annual Dunham lectures on 10, 12, and 13 March on "Studies in Radiotherapeutics."

SAVERY F. CONEYBEAR has been named to the newly created position of director of new products development at the Colgate–Palmolive Company, New York, N.Y. He was formerly a director of research in the company's research and development department.

FINN BRUDEVOLD, director of dental research at the Eastman Dental Dispensary and assistant professor of dental research at the University of Rochester, has been appointed professor of dentistry at Harvard University and chief of dental medicine at the Forsyth Dental Infirmary. His appointment will be effective on 1 August. Brudevold will participate in the new postdoctoral program in dental education being undertaken jointly by Harvard and Forsyth that makes available to outstanding students the opportunity of training for a career in academic dentistry.

VINCENT G. FITZSIMMONS, consultant of the Naval Research Laboratory, has been awarded the Meritorious Civilian Service Award, the Navy's second highest award, in recognition of his "role in the development of new lubricant systems for both military and industrial uses."

HENRY K. BEECHER, Dorr professor of research in anesthesia at Harvard Medical School, lectured recently before the Royal Society of Medicine in London. Also, he has been invited to be one of the chairmen at a symposium, to be held 24 and 25 March in London under the sponsorship of the Wellcome Trust, on quantitative methods in human pharmacology and therapeutics.

EDMUND A. PRENTIS, who took his degree in mining engineering at Columbia University in 1906, has been selected as the recipient of the 1958 Alexander Hamilton Medal of the Association of the Alumni of Columbia College. The Medal, which will be presented at a dinner at the university on 30 April, is given annually to a former student or a member of the college faculty "for distinguished service in any field of human endeavor." Prentis, for many years a member of the New York engineering firm of Spencer, White and Prentis, has been a director of many important engineering projects, including the 1950 reconstruction of the White House and construction of tunnels for New York subways.

MANUEL F. MORALES, former head of the physical biochemistry division of the Naval Medical Research Unit at Dartmouth College, has assumed his new position as professor of biochemistry at Dartmouth Medical School. LAFAYETTE H. NODA, DOROTHY JEAN BOTTS, and SIDNEY A. BERNHARD, have been appointed associate professors of biochemistry to collaborate with Morales.

ALLAN R. A. BEEBER has been appointed vice president for research and development for the Arkwright Finishing Company, Fiskeville, R.I. He was formerly director of research for the Keuffel & Esser Company in Hoboken, N.J.

Recent Deaths

JOSEPH E. AVENT, Knoxville, Tenn.; 79; retired professor of educational psychology at the University of Tennessee; former president of Martha Washington College at Abingdon, Va.; 12 Feb.

BELA C. BALAS, Newton, N.J.; formerly a physician in New York; had been an associate professor at Loyola University in Chicago for 16 years; 16 Feb.

AARON BESNER, Bronx, N.Y.; 36; nuclear physicist; had been working on the development of a nuclear-powered locomotive for the Walter Kidde Nuclear Laboratories, Garden City, N.Y.; 14 Feb.

JOHN H. CLEWELL, Montclair, N.J.; 71; retired associate director of E. I. du Pont de Nemours & Co. research laboratory in Arlington; 11 Feb.

ARCHIBALD EDGAR, Yonkers, N.Y.; 64; mechanical technician with Columbia University's cyclotron laboratories in Irvington, N.Y.; 12 Feb.

A. S. GIORDANO, Sarasota, Fla.; 65; pathologist and serologist of South Bend, Ind.; for 30 years director of the South Bend Medical Foundation; performed research on diagnoses of brucellosis and serology of syphilis; 15 Feb.

WALTER S. HUXFORD, Chicago, Ill.; 65; professor of physics at Northwestern University and former director of research for the National Defense Research Council; 13 Feb.

HAROLD R. MIXSELL, Locust Valley, N.Y.; 72; pediatrician; former editor of *Archives of Pediatrics*; 14 Feb.

CONSTANTINE RICCIUTI, Philadelphia, Pa.; 38; research chemist at the laboratory of the U.S. Department of Agriculture, Wyndmoor, Pa.; 10 Feb.

FRANCIS E. SENEAR, Winnetka, Ill.; 68; retired professor and head of the department of dermatology of the University of Illinois Medical School; 12 Feb.

Reports

Growth of Children of the Same Race under Different Environmental Conditions

Numerous observations on the rate of physical growth and development of children of different racial groups have been made in recent years, especially in connection with nutritional surveys conducted under the auspices of the World Health Organization and other international agencies in various parts of the world. In general, the children studied have been reported to be somewhat retarded or, in other cases, much retarded in their growth and development as compared with Caucasian children of the same sex and age in the United States. There has been a tendency to attribute the observed retardation, at least in part, to racial differences in the rate at which growth and development proceed. It is believed that the findings here reported briefly indicate the desirability of reexamining the assumption that such racial differences do in fact exist.

We recently compared the stature, weight, sitting height, and skeletal age of 898 American-born Japanese children in California with the corresponding characters of children of the same sex and age in Japan (*1*). As had been anticipated, the California children were found to be significantly taller, heavier, and more advanced in their skeletal development than comparable children in Japan, but the magnitude of the observed differences had not been anticipated.

At every age included in our study (6 to 19 years), the American-born Japanese boys exceeded in average stature the boys of Japan by an amount greater than the increase which has taken place in the average stature of the boys of Japan since the beginning of the present century (Fig. 1). The American-born Japanese girls exceeded the girls of Japan in average stature to a like degree, but only up to the age of 14 years. Thereafter, their superiority in average stature, though considerable, was somewhat less than the average gain in stature for the girls of Japan since 1900 (Fig. 2). This sexual difference is believed to have its basis in the relatively greater increase which has occurred in the average stature of the women as compared with the men of Japan during the last half-century.

Since the ratio of sitting height to stature is usually considered to be a racial character, it was rather surprising to find that, up to about the time of puberty, the American-born Japanese boys and girls were distinctly longer-legged than the children of Japan. Early in adolescence, however, the two groups became almost indistinguishable in ratio of leg length to total height.

It is evident, therefore, that during the prepuberal years the growth of the lower limbs of the Japanese children living in California was greater in proportion to the growth of the rest of their bodies than that of the children of Japan during the same period. This is probably a result of the more rapid growth rate of the California children, which, in turn, seems to be attributable to their more adequate diet and to the other more favorable environmental conditions in which they were reared.

It should be noted that the more rapid growth rate of the American-born Japanese children did not modify significantly the ratio of sitting height to stature of the older children. Our findings, therefore, are consistent with the view that this ratio is a valid racial character of adult Japanese.

A finding of especial relevance to the question of the existence of racial differences in the rate of physical growth and development of children was provided by a comparison of the skeletal age of the American-born Japanese children with that of the Caucasian children of the Brush Foundation study on which the Greulich-Pyle radiographic standards of skeletal development are based (*2*). The latter groups consisted of a large number of healthy children from Cleveland (Ohio) families who were well above average in economic level. In general, these children were taller, heavier, and more advanced in their skeletal development than other groups of children in the United States for whom comparable data were available.

Of the American-born Japanese children, only the 5-, 6-, and 7-year-old boys were found to be significantly retarded in their skeletal development as compared with the Cleveland children of the same sex and age. There was no significant difference in skeletal status between the two groups of boys from 8 to 12 years of age, but from 13 to 17 years the American-born Japanese boys were significantly more advanced skeletally than the Cleveland boys. The skeletal development of the American-born Japanese girls from 10 to 17 years of age was significantly more advanced than that of the Cleveland girls. The two groups of girls did not differ significantly from



Fig. 1. Average standing height of American-born Japanese boys compared with that of boys in Japan, in 1900 and 1952.



Fig. 2. Average standing height of American-born Japanese girls compared with that of girls in Japan, in 1900 and 1952.

All technical papers and comments on them are published in this section. Manuscripts should be typed double-spaced and be submitted in duplicate. In length, they should be limited to the equivalent of 1200 words; this includes the space occupied by illustrative or tabular material, references and notes, and the author(s)' name(s) and affiliation(s). Illustrative material should be limited to one table or one figure. All explanatory notes, including acknowledgments and authorization for publication, and literature references are to be numbered consecutively, keyed into the text proper, and placed at the end of the article under the heading "References and Notes." For fuller details see "Suggestions to Contributors" in *Science* 125, 16 (4 Jan. 1957).

each other in skeletal status at any other ages included in our study.

The most extensive study of the skeletal development of children in Japan is that reported by Sutow (*3*) and by Sutow and Ohwada (*4*), who assessed hand radiographs made of 1220 boys and 1150 girls of Hiroshima during 1951–52. These were apparently healthy children who served as controls in the Atomic Bomb Casualty Commission's study of the children who survived the atomic bombing of that city. Sutow and Ohwada reported that, on the basis of the Greulich-Pyle radiographic standards, the Hiroshima children were less advanced skeletally than the Cleveland children at every age considered in their study—that is, from 6 to 19 years. Their relative retardation ranged from 6 to 24 months in boys and from 9 to 24 months in girls.

Sutow suggested that the observed retardation in the skeletal development of the Japanese as compared with the Caucasian children might be due, at least in part, to some racial difference in the rate at which normal growth and development proceed in the two groups. However, he stressed as important factors contributing to their relative retardation in skeletal development the deprivations in food and other essentials which the Japanese children had experienced during World War II and the years immediately following its close.

Our findings on the American-born Japanese children do not support the view that the less advanced skeletal status of the children in Japan is attributable to some racial difference between Japanese and Caucasians. It seems more probable that, like their smaller average stature and their relatively shorter legs during childhood, the skeletal retardation of the children in Japan results from a less adequate diet and from other environmental conditions which are not so conducive to optimal growth as those existing in this country.

These findings, especially the observed similarity in skeletal status between the California Japanese and the Cleveland Caucasian children, indicate the need for caution in interpreting the relatively retarded growth and development of children in less favored parts of the world as the expression of some basic genetic difference between them and our own children (*5*).

WILLIAM WALTER GREULICH
Department of Anatomy, Stanford University School of Medicine, Stanford, California

References and Notes

1. W. W. Greulich, *Am. J. Phys. Anthropol.*, in press.
2. W. W. Greulich and S. I. Pyle, *Radiographic Atlas of Skeletal Development of the Hand and Wrist* (Stanford Univ. Press, Stanford, Calif., 1950).
3. W. W. Sutow, *Hiroshima J. Med. Sci.* **2**, 181 (1953).
4. W. W. Sutow and K. Ohwada, *Clin. Pediat. (Japan)* **6**, No. 11 (1953).
5. The study on which this report is based was supported by grant A-624 from the National Institutes of Health and by a grant from the Wenner-Gren Foundation for Anthropological Research.

22 November 1957

Distribution of Incompatibility Alleles among the Complex-Heterozygotes of Oenothera

In earlier papers (*1*), evidence was presented indicating the presence of an incompatibility allele mechanism in oenotheras of the *biennis* group 1, a phylogenetic group of true-breeding translocation heterozygotes. This is a preliminary report (*2*) of the occurrence of incompatibility alleles in other phylogenetic groups of the genus *Oenothera*.

The oenotheras of *biennis* group 1 are composed of two genomes or "complexes" of seven chromosomes each. These are designated as the alpha and beta complexes and are characterized by completely different arrangements of their chromosome ends. As a result, at meiosis a circle of 14 chromosomes occurs, and only two kinds of spores are produced, one carrying the alpha, the other the beta, complex. Such plants, which are naturally self-pollinating, produce only alpha · beta combinations among the offspring. The absence of alpha · alpha or beta · beta combinations among the progeny is attributed to a balanced lethal system. In outcrossing these forms, it becomes apparent that one complex is transmitted to the offspring predominantly through the egg and the other largely through the pollen. This serves as a basis of distinguishing the alpha and the beta complexes, the latter coming through the pollen, the former through the egg.

In the *biennis* group 1 races, the alpha complex carries an incompatibility allele (S_1), while the beta complex carries an allele which has no incompatibility effect (S_1). The S_1 allele of the alpha complex serves as a pollen lethal, because in self-pollinations development of pollen carrying the alpha complex will be inhibited by the presence of the same S_1 allele in the style. The incompatibility allele mechanism thus acounts for one-half of the balanced lethal system so well known to *Oenothera*.

The incompatibility allele mechanism suggests an attractive hypothesis explaining the origin of the complex-heterozygotes. In two isolated populations showing orthodox cytogenetic behavior, the occurrence of random segmental interchange can, over a period of time, result in the differentiation of the two populations with regard to the arrangement of their chromosome ends. If interchange is extensive enough, the two populations may come to be characterized by completely different segmental arrangements. Let us suppose that one of these populations possesses an incompatibility allele system, while the other does not. If the two populations now come into contact and hybridization occurs between them, the hybrids will be complete translocation heterozygotes, producing only two kinds of spores. One of these will carry an S_1 allele; thus, pollen of this type will not develop in a self-pollination, and one type of segregate (alpha · alpha) which is structurally homozygous cannot occur. If megaspore competition occurs, and the complex carrying the S_1 allele is the one which succeeds in producing the embryo sacs, the other segregate which is structurally homozygous (beta · beta) will also be eliminated. Thus, such a hybrid will be true-breeding from its inception. In this way, the highly specialized oenotheras could have arisen simply through a single hybridization. Once established, of course, the nature of the cytogenetic mechanism allows the accumulation of recessive detrimental and lethal genes which reinforce the original balanced lethal system of incompatibility alleles and megaspore competition.

The strength of this hypothesis depends to a large extent upon the demonstration of the existence of incompatibility alleles in the other phylogenetic groups of complex-heterozygotes in the subgenus. If incompatibility alleles are found in the alpha complexes of most complex-heterozygotes, the hypothesis would seem to have general significance in explaining the origin of the complex-heterozygote.

Largely through the work of Cleland and his associates, several hundred collections of *Oenothera* from North America have been cytogenetically analyzed and classified accordingly into eight different phylogenetic groups (*3*). A study has been undertaken to survey the complex-heterozygotes among these collections for the presence of incompatibility alleles in their alpha complexes. The particular phylogenetic groups with which work has begun are the *strigosa*, the *biennis* group 2, the *biennis* group 3, and the *parviflora*. Some unforeseen difficulties in obtaining the critical hybrid combinations in many of the crosses has so far limited the collection of data regarding the distribution of incompatibility alleles in these groups. However, certain races (listed in Table 1) have been shown to possess incompatibility alleles.

It is interesting to note that the races *grandiflora* de Vries and Beaufort both

Table 1. Races of *Oenothera* which have been shown to possess incompatibility alleles.

strigosa	*biennis* group 2	*biennis* group 3	*parviflora*
Brookston	Indian River	Coudersport III	muricata
Fargo	Victorini	Linville	
Granger	Waterbury	Mountain Lake	
Heber		Newfound Gap	
Iowa 6		Smethport	
Iowa 12			
Palmer Lake			

lack S_1 alleles. These races were previously interpreted as hybrids between the structurally homozygous, self-fertile *grandiflora* group and the *biennis* group 1 (*4*). The absence of incompatibility alleles in the complexes *neoacuens* (*grandiflora* de Vries) and alpha *Beaufort* confirm the earlier interpretation.

The above data indicate that incompatibility alleles may well be characteristic of the alpha complexes of most complex-heterozygotes. With the exception of the *grandiflora* de Vries and the Beaufort collections, all races which are complex-heterozygotes and which have so far been tested possess incompatibility alleles.

ERICH STEINER
MARY S. SCHULTZ
Department of Botany,
University of Michigan, Ann Arbor

References and Notes

1. E. Steiner, *Genetics* 41, 486 (1956); *Am. J. Botany* 44, 582 (1957).
2. This work was supported by a National Science Foundation grant (NSF G-3298) to one of us (E.S.).
3. R. E. Cleland *et al.*, *Indiana Univ. Publs. Sci. Ser.* 16, 1 (1950).
4. E. Steiner, *Evolution* 6, 69 (1952); H. T. Stinson and E. Steiner, *Am. J. Botany* 42, 905 (1955).

18 November 1957

Fractionation of Stable Isotopes of Sulfur by Thiobacilli

Tudge and Thode (*1*) have calculated thermodynamically that H_2S in equilibrium with elementary sulfur in aqueous solution shows no fractionation of the stable sulfur isotopes S^{32} and S^{34}. This can be interpreted to mean that during the oxidation of H_2S to sulfur, both isotopes react with equal rapidity. It was also found by Jones and Starkey (*2*) that *Thiobacillus thioxidans,* when it was grown on sulfur (it oxidizes sulfur to sulfate), likewise produced no fractionation.

In experiments carried out by our group with *Thiobacillus concretivorus* obtained in pure culture by C. D. Parker of the Melbourne and Metropolitan Board of Works (Australia) and grown on elementary sulfur, results not unlike those of Jones and Starkey (*2*) were obtained. The sulfur used was commercial sulfur and sulfur (of volcanic origin) from White Island, New Zealand. Very little fractionation was obtained in these experiments, and there certainly appeared to be no definite enrichment of the light isotope. Enrichment of S^{32} varied from +0.05 to −0.16 percent. Thus, if the results are to be taken as significant, there is a small enrichment of S^{34} during the oxidation

$$S \rightarrow SO_4^{--}$$

In preliminary experiments with *T. concretivorus* grown on H_2S as the sulfur source, enrichment of the lighter isotope could be detected when the products of the oxidation, sulfur and sulfate, were analyzed. Cultures of *T. concretivorus* were grown by C. D. Parker in an atmosphere containing approximately 200 ppm of H_2S at room temperature (20° to 25°C). After 8 to 10 days the sulfur which had formed as a pellicle was filtered from the culture medium, and the sulfate formed in the culture was precipitated as barium sulfate.

The results represented in Table 1 demonstrate that there is a significant enrichment of S^{32} both in sulfur and sulfate. In experiment 3, the sulfate was not precipitated in the culture solution but was separated by washing the filter papers, on which the sulfur was filtered, with water and then precipitating this solution with barium chloride. This may be the reason for the reduced enrichment.

In order to test whether fractionation occurs during abiological oxidation of H_2S, a Kipps apparatus was left standing for some weeks at approximately 23°C, and the sulfur formed at the top of the apparatus due to oxidation of H_2S was separated out. The sulfur showed a depletion of 0.3 ± 0.1 percent of the S^{32}/S^{34} ratio with respect to that of the H_2S, a change in the opposite direction to that of biological oxidation. This indicates that the biological oxidation of H_2S by *Thiobacilli* leads to an enrichment of S^{32} in the final products.

In addition to the afore-mentioned laboratory experiments, measurements were carried out on samples collected in natural environments where a sulfur cycle was in progress. The results represented in Table 2 indicate a definite enrichment of S^{34} in gypsum and sulfates with respect to the associated sulfur.

Although the sulfate in the concrete of sewers may be formed as a result of the biological and abiological oxidation of H_2S as well as of the microbial oxidation of sulfur (Parker, *3*), the gypsum crystals surrounding the sulfur nodules at Lake Eyre (South Australia) appear to be formed by the microbial oxidation of sulfur only (Baas Becking and Kaplan, *4*). It is difficult at this stage to interpret the results in order to establish with certainty whether an enrichment of S^{34} does take place, since part of the sulfate may redissolve and a physical fractionation may occur. Further, it is conceivable that a proportion of the gypsum found under these natural conditions may be of secondary origin, having at some stage entered a cycle in which sulfate reduction was taking place and so being enrichced in S^{34}. We draw attention to these factors as complications which deter us from drawing a definite conclusion. From field observations and under the conditions in which the samples were collected and analyzed, we consider, however, that the enrichment

Table 1. Fractionation of sulfur isotopes during the oxidation of H_2S by *Thiobacillus concretivorus.*

Sample	S^{32}/S^{34}	Relative enrichment of S^{32} (%)
Experiment 1		
Sulfide used	22.12	0.0
Bacterial sulfur	22.18	0.3 ± 0.1
Bacterial sulfate	22.29	0.8 ± 0.1
Experiment 2		
Sulfide used	22.14	0.0
Bacterial sulfur	22.27	0.6 ± 0.1
Bacterial sulfate	22.33	0.9 ± 0.1
Experiment 3		
Sulfide used	22.14	0.0
Bacterial sulfur	22.26	0.5 ± 0.1
Bacterial sulfate	22.28	0.6 ± 0.1

Table 2. S^{32}/S^{34} isotope ratios of sulfur and sulfate formed by the oxidation of sulfur.

Sample and locality	S^{32}/S^{34}	Relative enrichment of S^{32} (%)
Melbourne sewer		
Sulfur from concrete surfaces	22.29	0.7 ± 0.1
Sulfate from concrete surfaces	22.14	0.0
West side, Sulphur Peninsula, Lake Eyre		
Sulfur nodule	22.49	0.6 ± 0.1
Gypsum crystals around sulfur	22.36	0.0
East side, Sulphur Peninsula, Lake Eyre		
Sulfur nodule	22.34	0.4 ± 0.1
Gypsum crystals around sulfur	22.25	0.0

of S^{34} illustrated in Table 2 as a result of the biological oxidation of sulfur to sulfate is significant. This may be considered as further evidence confirming results on laboratory experiments that S^{32} is not enriched, but rather, depleted, during the oxidation of sulfur to sulfate by *Thiobacilli* (*5*).

I. R. KAPLAN*
Division of Fisheries and Oceanography, Commonwealth Scientific and Industrial Research Organization, Cronulla, New South Wales, Australia
T. A. RAFTER
Division of Nuclear Sciences, Department of Scientific and Industrial Research, Lower Hutt, New Zealand

References and Notes

1. A. P. Tudge and H. G. Thode, *Can. J. Research* 28B, 567 (1950).
2. G. E. Jones and R. L. Starkey, *Appl. Microbiol.* 5, 111 (1957).
3. C. D. Parker, *Sewage and Ind. Wastes* 23, 1477 (1951).
4. L. G. M. Baas Becking and I. R. Kaplan, *Trans. Roy. Soc. S. Australia* 79, 52 (1956).
5. We wish to acknowledge the help of Dr. C. D. Parker, who provided pure cultures of *T. concretivorus* and the sulfur and sulfate from cultures grown on H_2S.

* Present address: Bacteriology Department, University of Southern California, Los Angeles 7, Calif.

18 December 1957

A New Strain of the Mouse Mammary Tumor Virus

The mammary tumor virus, transmitted from generation to generation through the mother's milk, is an important factor in the development of mammary tumors in mice. Although it has been postulated that this virus should show genetic autonomy and variability (*1*), this has not been established. The possibility that the mammary tumor viruses possessed by different inbred strains of mice may not be identical has been indicated by reports of differences in characteristics of tumor development (such as tumor incidence or mean age of tumor development) which occur when two such strains are crossed reciprocally (*2*). However, evidence of stable alterations in the activity of the virus within an inbred strain, in which the virus is detectable both before and after the change, has not been reported. To verify the assumption that the appearance of a new characteristic within a strain is the result of a change in the mammary tumor virus, it is necessary to compare the new and the original stocks in situations wherein the virus is the only variable, both in the test mice and in the females supplying virus to the test mice. In addition, the altered activity of the virus must be observed through several generations of mice to insure the stability of the change.

In our laboratory a fortunate combination of circumstances has resulted in a situation in which a change in a characteristic of an inbred strain of mice can be traced to an alteration in the activity of the mammary tumor virus. A line of Heston A mice (A/HeCRGL), inbred for over 85 generations, has been maintained in this laboratory since 1950. The mean age of mammary tumor development in the breeding females has consistently been about 12 months. In 1953 it was discovered that females in one branch of the stock were developing mammary tumors at about 8 months of age. This latter group was separated out, and it has been maintained separately as the A/viCRGL subline. It is at the present time in its 13th generation.

The experiments described below, in which all mice have been maintained as breeding females, were set up to determine whether this change in mean age of tumor development was the result of a change in the mouse or in the virus (*3*). In all experimental groups, some mice are still alive. Therefore, the final mean ages of tumor development may be slightly different from those reported here. However, the remaining mice are either so old or so few in number that their deaths (due to mammary tumors) will not affect the significance of the tumor age differences.

In the generations of stock mice concurrent with the experimental groups discussed below, 90 females of the A/He strain had a mean age of tumor development of 12.7 months; 111 females of the A/vi subline had a mean age of tumor development of 8.6 months (Table 1, experiment 1).

Reciprocal hybrids (34 A/He × A/vi hybrids, 51 A/vi × A/He hybrids) of the two stocks were collected, and their mean ages of tumor development were determined (Table 1, experiment 3). Each group of hybrid mice developed mammary tumors at a mean age similar to that of the strain to which their maternal parents belonged. These two groups of mice were identical genetically but differed in maternal influences.

Newborn mice of the A/vi subline were transferred to and nursed by females of the A/He strain and vice versa. Fourteen animals that received A/He milk either had a late age of tumor development or are alive and more than 13 months old, despite the fact that they are otherwise A/vi females; 25 females that received A/vi milk had an early mean age of tumor development despite the fact that they were otherwise A/He females (Table 1, experiment 2). Thus, the difference in mean age of tumor development is evidently mediated by factors carried in the milk.

The activity of the mammary tumor virus has been followed for two generations beyond the reciprocal hybrids by fostering females of the A/vi stock upon both groups of hybrids (Table 1, experiment 4) and by collecting the offspring of these fostered females (Table 1, experiment 5). In both of these generations, groups of 22 and 25 mice whose mammary tumor virus was originally from A/He mice are developing mammary tumors at a later age than did groups of 21 and 34 mice whose mammary tumor virus was originally from the A/vi stock. Thus, the two viruses have retained their difference in activity through these generations, despite the fact that the mice carrying each of them were similar in genotype in each generation. This eliminates the possibility that the difference in mean age of tumor development reported here is the result of a change in the genotype of the host which is expressed in the activity of the mammary tumor virus passed to the offspring.

Table 1. Summary of experiments involving the mammary tumor viruses of the A/He strain and the A/vi subline and their influence on the mean age of mammary tumor development in breeding female mice. Symbols designate genotype (in hybrids the female parent is mentioned first); numbers in parentheses indicate mean age, in months, of tumor development; arrows indicate transfer of the virus.

Expt.	Transfer of virus from A/He strain	Transfer of virus from A/vi subline
1	A/He (12.7)	A/vi (8.6)
2	↓ ↘ A/vi (> 12.8)	↓ ↘ A/He (9.6)
3	F_1* (13.1)	F_1† (9.4)
4	↓ A/vi (11.9)	↓ A/vi (9.6)
5	↓ A/vi (> 11.4)	↓ A/vi (9.4)

* A/He × A/vi. † A/vi × A/He.

The various experimental situations have shown the stability of the difference between the two viruses. Possible differences in the response of other strains of mice to these two strains of virus are being tested in a series of current experiments. In addition, the possibility of there being serological differences between the two viruses is being investigated.

PHYLLIS B. BLAIR
Department of Zoology and Cancer Research Genetics Laboratory, University of California, Berkeley

References and Notes

1. C. C. Little and P. A. Gorer, in H. Gruneberg, *The Genetics of the Mouse* (Cambridge Univ. Press, Cambridge, England, 1943), appendix I.
2. J. J. Bittner, *Cancer Research* 8, 625 (1948).
3. I am greatly indebted to Professor K. B. DeOme for advice on the conduct of this study. Most of this work was done during the tenure of predoctoral fellowships in biology from the National Science Foundation. This study was further aided by cancer research funds of the University of California and by a grant (MOR-27) from the American Cancer Society.

23 December 1957

Starch Gel Electrophoresis of Some Invertebrate Sera

An interest in the phylogenic emergence of characteristic serum proteins has prompted us to examine the electrophoretic properties of the blood of several invertebrate forms (*1*.)

The method of zone electrophoresis in starch gel described by O. Smithies (*2*) was used to separate serum proteins of fourteen species of decapod Crustacea, two species of Arachnoidea, and two species of Mollusca. Sera from 6 to 12 different specimens of each form were examined. Soluble starch was produced by treatment of potato starch with acetone-HCl (*3*) at 36.1°C for 70 minutes (*4*). Gels were prepared from this soluble starch in 0.030*M* sodium borate buffer of *p*H 9.05, and electrophoresis was carried out at 10°C for 16 hours with a potential of 4.5 v/cm. Members of each species were collected from restricted habitats, with the exception of the green crab. A specimen from waters near Scotland (*5*) gave electrophoretic patterns identical to those of specimens from the Woods Hole region. Within a given species, differences in sex, size, or stages of the molt cycle produced no significant difference in the electrophoretic patterns.

Representative patterns for each form included in the present series are illustrated in Fig. 1; that for a normal human serum is shown at the bottom for comparison and orientation. The cathodic region into which gamma globulins usually migrate is at the left of the origin, while in the human pattern albumin occupies the most prominent and extensive zone in the anodic region. Among the invertebrates studied, there is no indication that serum proteins having electrophoretic properties similar to those of mammalian gamma globulins occur in the serum. Figure 1 also indicates that the serum proteins of these invertebrates are highly species specific above the generic level, although similarities between closely related forms are observed.

From the Arthropoda we have studied, the three species of the fiddler crab (*Uca*) have nearly identical serum electrophoretic patterns. The two species of hermit crab (*Pagurus*) also give patterns which are quite alike. In some cases such similarities might be extended to groupings of families, as demonstrated by the patterns obtained for the calico crab (*Ovalipes*) when compared with those obtained for the green crab (*Carcinides*). An exception, however, is the blue crab (*Callinectes*), the third representative of the family Portunidae which was sampled. This species has practically no similarity to the other two with respect to electrophoretic pattern. This indicates the need for caution in interpreting the significance of the observations thus far obtained in invertebrates correlating morphology with serum protein patterns. A further example of the need for caution in applying this technique to taxonomic problems is indicated by comparing the pattern produced by serum of the lobster (family Homaridae) with the pattern obtained from the serum of the mole shrimp, *Emerita talpoida* (family Hippidae). The two patterns are nearly identical even though the forms are taxonomically in different families.

Comparing the two representatives of



Fig. 1. Starch gel electrophoretic patterns of hemocyanin-containing sera, scorpion venom, oyster serum, and normal human serum. The position at which the samples were applied is indicated by the arrow below the figure. The cathodic area is to the left of the origin, and the anodic area is toward the right.

Arachnoidea cited in Fig. 1, we find that the horseshoe crab (*Limulus*) has quite a different serum protein composition from that of its nearest living relative, the scorpion (*Hadruras arizonensis*) (*6*). Scorpion venom produced a pattern quite unlike scorpion serum, its proteins migrating toward the cathode in a fashion similar to that found in electrophoresis of human gamma globulin.

From the Mollusca we have studied, a species of Cephalopoda and one of Gastropoda are presented here. Serum from the squid (*Loligo pealii*) yielded two major components of moderate mobility, while that from the oyster gave two slow components. No respiratory proteins have been found in oyster blood, and the bands which developed are probably due to other types of serum proteins, the concentrations of which are relatively low.

Hemocyanin is the principal serum protein of many invertebrates, and, in the case of the spiny lobster (*Panulirus interruptus*), it forms a single boundary upon electrophoresis in the Tiselius apparatus (*7*). The boundary method has also revealed the presence of other proteins amounting to less than 3 percent of the total protein. The dense bands found in patterns obtained by zone electrophoresis in starch gel are thus probably due to hemocyanin, even though more bands than one are frequently found. Studies with the ultracentrifuge of the *p*H stabilities of hemocyanins from several different species have demonstrated that these proteins aggregate reversibly near their isoelectric points and yield products of high sedimentation constants ($S_{20}>22$) (*8*). Molecular sieve properties of starch gel might be expected to prevent the admission of such large particles into this medium, as is demonstrated by the failure of some macroglobulins ($S_{20}>19$) to migrate into such gels (*9*). However, since the *p*H of the gel buffer is usually above the alkaline limits of the stability range for the aggregated molecular species, the dissociated hemocyanins ($S_{20}\cong 17$) are observed. The appearance of more than one dense band in these electrophoretic patterns indicates that, at alkaline *p*H, hemocyanins usually dissociate into nonidentical constituents even though the dissociation products have ultracentrifugal homogeneity (*8*). The possibility arises that the copper-containing protein moiety responsible for enzymatic oxygen transport may have been isolated electrophoretically from other protein components of a polymer of higher molecular weight. This possibility should be tested by location of the copper in the electrophoretic patterns since we are presently confronted with the alternative that hemocyanins may distribute copper between more than one dissociation product.

Despite the few exceptions which might prove to have important biological significance, the results of these studies indicate that the electrophoretic patterns of the serum proteins of closely related invertebrates have a remarkable degree of specificity. These findings suggest that starch gel electrophoresis of serum proteins may be useful in certain racial studies, taxonomic problems, and considerations of biochemical individuality.

KENNETH R. WOODS†
ELIZABETH C. PAULSEN*
RALPH L. ENGLE, JR.,† JAMES H. PERT
Marine Biological Laboratory, Woods Hole, Massachusetts, and *Department of Medicine, New York Hospital–Cornell Medical Center, New York*

References and Notes

1. This study was supported in part by the National Cancer Institute, U.S. Public Health Service (grant No. C 1905).
2. O. Smithies, *Biochem. J.* 61, 629 (1955).
3. Batch number 584 potato starch, obtained from Morningstar-Nichol, New York, N.Y., was used in these investigations.
4. J. H. Pert *et al., Clin. Research Proc.* 5, 156 (1957).
5. Serological Museum sample No. 57-2786 was kindly contributed by Dr. Alan Boyden, Department of Zoology, Rutgers University, New Brunswick, N.J.
6. We are indebted to Dr. Herbert L. Stahnke, Poisonous Animal Research Laboratory Arizona State College, Tempe, for sending us live scorpions in the mail.
7. A. Tyler and C. B. Metz, *J. Exptl. Zool.* 100, 387 (1945).
8. I.-B. Eriksson-Quensel and T. Svedberg, *Biol. Bull.* 71, 498 (1936).
9. R. L. Engle, Jr., K. R. Woods, J. H. Pert, *J. Clin. Invest.* 36, 888 (1957).

* Present address: Department of Zoology, Rutgers University, New Brunswick, N.J.
† Lalor fellow, 1957.

26 August 1957

Ethanol Protection against the Catalase-Depressing Effect of 3-Amino-1,2,4-Triazole

In 1941 Greenstein *et al.* (*1*) reported that the liver catalase activity of rats and mice bearing extrahepatic tumors is markedly lowered. Nakakara and Fukuoka (*2*) in 1948 reported the separation of tumor fractions which, when injected into mice, lowered the liver catalase activity. In extension of this finding, Greenfield and Meister (*3*) have been able to isolate fractions of various tumors which have a marked in vivo effect on the lowering of the liver catalase activity in mice. Recently Heim *et al.* (*4*) have been able to reproduce all the catalase changes occurring in a cancer host by the use of 3-amino-1,2,4-triazole (AT) in a normal animal. They reported that 3 hours after an intraperitoneal injection of AT, in a dose of 1 g/kg of body weight, the liver catalase activity of rats is reduced to 10.9 percent of control values. This depressing effect on catalase activity gradually subsides, and 72 hours after the injection of AT the activity returns to 84.6 percent of control values.

Nelson *et al.* (*5*), while studying the effects of AT on ethanol metabolism, discovered that ethanol, if injected prior to AT, protected the dog from the catalase-depressing effect of AT. One experiment with the rat indicated that the effect was not species specific. It is the purpose of this report to establish the protective action of ethanol in the rat and to report this phenomenon in more detail.

Adult male Sprague-Dawley rats were used throughout the experiments. The animals were allowed free access to Purina laboratory chow and water until the day of the experiment; on this day, food and water were withheld. 3-Amino-1,2,4-triazole (*6*) was injected intraperitoneally as a 10 percent aqueous solution in a dose of 1 g/kg. Ethanol was injected intraperitoneally in a dose of 1 g/kg as a 20 percent (wt./vol.) solution in isotonic saline. Ethanol was injected 1 hour prior to the injection of AT. When isotonic saline was substituted for the ethanol injection, it too was injected 1 hour prior to the injection of AT. At a designated time after the injection, the animal was sacrificed by a blow on the head. A small specimen of liver was removed, washed free of blood, blotted dry, weighed, diluted with nine times its weight of 0.01*M* potassium phosphate buffer (*p*H 6.8), and homogenized in a chilled glass tissue grinder. The 1:10 homogenate was diluted with phosphate buffer to give a final dilution of 1:500. Catalase activity was determined by a modification of the assay procedure of Feinstein (*7*), perborate substrate being used, and is expressed as milliequivalents of sodium perborate destroyed per milligram of liver. Blood ethanol determinations were carried out by the method of Aull *et al.* (*8*).

From the summary of results given in Table 1 it can be seen that, 1 hour following the injection of AT, the catalase activity is reduced to 8.6 percent of control values. At ½ hour after the injection of AT, the catalase activity is 19.8 percent of control values. There appears to be quite a variation in the activity ½ hour following the AT injection, as is shown in the comparatively large standard deviation. It is also shown that, if the animal is pretreated with ethanol (1 g/kg) 1 hour prior to the injection of AT, the catalase activity 1 hour following the AT injection is reduced only slightly if at all. Ethanol per se does not affect the catalase activity of the control animals. If the animal is pretreated with a dose of saline (in an amount equivalent to that of saline in a dose of ethanol), no protective action against AT effects is seen.

Table 1. Effect of injections of ethanol, saline, and 3-amino-1,2,4-triazole (AT), alone or in various combinations, on liver catalase activity.

No. of animals	Injection			Interval between injection and sacrifice (hr)	Catalase activity ± S.D.† (mEq/mg of liver)
	Ethanol* (g/kg)	Saline	AT (g/kg)		
4	0	0	0		1.131 ± 0.120
3	1	0	0	2	1.068 ± 0.093
6	0	0	1	0.5	0.224 ± 0.183
4	0	0	1	1	0.097 ± 0.031
3	0	Amt. equal to that in 1 g/kg dose of ethanol	1	1 (after AT)	0.116 ± 0.026
6	1	0	1	1 (after AT)	0.982 ± 0.235

* In saline. † S.D. = standard deviation.

It was decided to determine whether the protective effect of ethanol was permanent or temporary.

In order to determine this, a group of animals was injected with ethanol followed in 1 hour by an injection of AT. Two blood samples were drawn from each rat, the first from 0 to 11 minutes following the AT injection, the second from 60 to 181 minutes following the withdrawal of the first sample. The rat was sacrificed at from 0 to 125 minutes following the withdrawal of the second blood sample. Immediately after the animal was sacrificed, a sample of liver was removed, and the catalase activity was determined. Since the animals were sacrificed at from 60 to 258 minutes following the AT injection, any significant change in catalase activity could not be due to the time interval between AT injection and sacrifice. It has been shown (*5*) that, in the rat, 60, 120, 180, and 240 minutes following AT injection, the catalase activity is 13.7, 14.9, 8.7, and 9.6 percent of control values, respectively. Marshall and Fritz (*9*) established that blood ethanol disappearance follows a straight line with time at all blood ethanol concentrations except at low levels (< 10 mg percent), at which levels disappearance follows an exponential curve.

In view of this, the approximate time at which all ethanol leaves the animal's body may be determined by preparing a graph of the blood ethanol concentrations with time and by extrapolating the blood ethanol line to zero concentration. This was done for each rat, and the number of minutes of ethanol metabolism remaining at the time of sacrifice was determined. If the animal was sacrificed before all ethanol had left its body, the number of minutes of ethanol metabolism remaining is designated by a plus sign. If the animal was sacrificed after all ethanol had left its body, the number of minutes of ethanol metabolism remaining is designated by a minus sign.

Figure 1 shows a plot of the catalase activity against the number of minutes of ethanol metabolism remaining at the time of sacrifice. It can be seen that, approximately 60 to 120 minutes before all ethanol disappears from the animal's body, the AT begins to take effect and the liver catalase activity begins to decrease. The activity falls rather rapidly from the point that represents 60 minutes before all ethanol has disappeared. Within 30 minutes after the disappearance of all ethanol, maximum depressing effects of AT are observed. Perhaps this lag in AT effect is partly or wholly the result of the lag in disappearance of ethanol when low concentrations of blood ethanol are reached. However, as Fig. 1 demonstrates, the ethanol effect is temporary; AT begins to take effect shortly before all ethanol has left the body, and maximum depressing effects are observed shortly after all ethanol has disappeared.



Fig. 1. Liver catalase activity in rats previously injected with ethanol and 3-amino-1,2,4-triazole and sacrificed with varying times of ethanol metabolism remaining.

Recently Alexander (*10*) has shown that ethanol reverses the in vitro catalase-depressing effects of an ethanol-soluble boiled aqueous extract (BAE) of normal rat liver. He states that this extract continuously generates H_2O_2, which is decomposed predominantly to oxygen and water in the presence of catalase but with the formation of some inactive catalase-H_2O_2 complex II. This results in decreased catalase activity. When ethanol is present in the system, it removes the H_2O_2 formed and is itself peroxidized to acetaldehyde in the process, thus preventing the accumulation of complex II. In this manner, in the presence of ethanol and ethanol-soluble boiled aqueous extract, catalase activity remains normal. He concludes that the catalatic inhibition of this extract is due to autoxidation of ascorbic acid and sulfhydryl groups in the extract.

The efficiency of ethanol in protecting against the inhibition of AT suggests a mechanism similar to that described by Alexander with ethanol-soluble boiled aqueous extract. However, in the absence of information concerning autoxidation or metabolism of AT, definite conclusions cannot be drawn.

GEORGE H. NELSON

Department of Biochemistry, University of South Dakota Medical School, Vermillion

References and Notes

1. J. P. Greenstein, W. V. Jensette, J. White, *J. Biol. Chem.* 141, 327 (1941).
2. W. Nakakara and F. Fukuoka, *Japan. Med. J.* 1, 271 (1948).
3. R. E. Greenfield and A. Meister, *J. Natl. Cancer Inst.* 11, 997 (1951).
4. W. G. Heim, D. Appleman, H. T. Pyfrom, *Science* 122, 693 (1955).
5. G. H. Nelson *et al.*, *Quart. J. Studies Alc.* 18, 343 (1957).
6. Contributed by American Cyanamide Company, Agricultural Chemical Division.
7. R. N. Feinstein, *J. Biol. Chem.* 180, 1197 (1949).
8. J. C. Aull, Jr., W. J. Roberts, Jr., F. W. Kinard, *Am. J. Physiol.* 186, 380 (1956).
9. E. K. Marshall, Jr., and W. F. Fritz, *J. Pharmacol. Expil. Therap.* 109, 431 (1953).
10. N. M. Alexander, *J. Biol. Chem.* 227, 975 (1957).

7 November 1957

Blocking by Picrotoxin of Peripheral Inhibition in Crayfish

In vertebrates, inhibition takes place within the central nervous system. But a crayfish "thinks in its claws" (*1*). More prosaically, in the Crustacea both excitation and inhibition take place in the peripheral muscle. Because these events are at the fringes of the crayfish body, it is easy to assay drugs for effects on the inhibitory process. The drug we found to block inhibition is picrotoxin (*2*) (which is known to pharmacology for setting off convulsions when injected into a mammal).

The preparation used was the claw of the crayfish, *Orconectes immunis*. The

amputated claw was arranged so that the finger's movement was recorded on a revolving drum. The closer muscle was cut from the finger, and the excitatory and inhibitory nerves to the opener muscle were dissected free and placed on separate stimulating electrodes. The claw was perfused with a buffered modification of van Harreveld's crayfish Ringer's solution (*3*). Picrotoxin, when used, was dissolved in the Ringer's solution.

One way in which we recorded inhibition was by stimulating the excitatory nerve tetanically until a contraction was well developed and by then briefly stimulating the inhibitory nerve as well. During the stimulation of the inhibitory nerve, the contraction decreased (Fig. 1, IA). After the claw had been perfused with picrotoxin solution (Fig. 1, IB), the contraction was no longer affected by stimulation of the inhibitory nerve.

Inhibition was also seen when the excitatory nerve and the inhibitory nerve were stimulated together at the outset (Fig. 1, IIA). With this method there was either no contraction, showing that the inhibition was complete (as in the illustration), or the muscle contracted at a rate slower than normal, showing that the inhibition was partial. The extent of the inhibition depended on the ratio of the frequency of inhibitory nerve stimulation to the frequency of excitatory nerve stimulation (*4*). After perfusion with picrotoxin, the muscle responded to concurrent stimulation of the excitatory and inhibitory nerves as if the excitatory nerve alone had been stimulated (Fig. 1, IIB). Picrotoxin had blocked inhibition.

The extent to which inhibition was blocked depended on the concentration



Fig. 1. The effect of stimulating the excitatory (e) and inhibitory (i) nerves running to the opener muscle of the crayfish claw. An upward deflection of the signal trace indicates that the nerve was stimulated at a rate of 60 stimulations per second. (IA) Stimulation of the inhibitory nerve during the contraction caused by stimulating the excitatory nerve; (IB) same as IA, but 30 minutes after the perfusion of $10^{-4}M$ picrotoxin; (IIA) initial simultaneous stimulation of the excitatory and of the inhibitory nerves; (IIB) same as IIA, but after the perfusion of picrotoxin.



Fig. 2. The percentage inhibition at intervals following the onset of perfusion of $10^{-4}M$ picrotoxin. The excitatory nerve was stimulated at a rate of 60 stimulations per second. The inhibitory nerve was simultaneously stimulated at a rate of 21 stimulations per second (dotted line) or at 150 stimulations per second (broken line). At the time indicated by *R*, perfusion of picrotoxin was stopped and perfusion with Ringer's solution was begun.

of picrotoxin. Picrotoxin ($10^{-6}M$) had almost no effect, while higher concentrations progressively decreased the effect of inhibitory nerve stimulation. The action of picrotoxin was almost independent of *p*H over the range tested (from *p*H 6.3 to *p*H 7.7).

The time course of the action of picrotoxin was determined by stimulating both the excitatory and inhibitory nerves at intervals after the onset of picrotoxin perfusion. The percentage inhibition was measured from the record (*5*). One experiment was plotted as shown in Fig. 2. Originally the contraction was completely inhibited when the inhibitory nerve was stimulated at rates of either 21 or 150 stimulations per second. Soon after picrotoxin was introduced, inhibitory nerve stimulation at a rate of 21 per second produced no inhibition, while stimulation at 150 per second gave only partial inhibition. The graph also shows that the effect of picrotoxin was eliminated by washing the drug out of the claw.

The mechanism of picrotoxin action was then investigated. It was evident that picrotoxin does not act by selectively blocking the conduction of nerve impulses along the inhibitory nerve, for inhibition was normal after the nerve had been soaked in picrotoxin, so long as the muscle was free of the drug. And the excitatory mechanism was not interfered with, for it remained normal long after the muscle and the nerves were exposed to picrotoxin.

The analysis may be carried further by assuming that the inhibitory nerve releases an inhibitory transmitter at its ending. Picrotoxin might block inhibition by slowing the release of the inhibitory transmitter or by affecting some later step in the inhibitory mechanism—for example, by blocking the combination of the inhibitory transmitter with a receptor molecule. It seems unlikely that picrotoxin slows the release of the inhibitory transmitter, because Florey, McLennan, and Elliott have shown that the crayfish stretch receptor and the crayfish muscle can be inhibited by a chemical from the mammalian brain, and that this chemical's inhibitory action on the stretch receptor is blocked by picrotoxin (*6*). And our data are also consistent with the idea that picrotoxin blocks the combination of the inhibitory transmitter with a receptor molecule.

It may be concluded that picrotoxin reversibly blocks peripheral inhibition in crayfish muscle. Probably picrotoxin joins with the receptor molecule and thereby blocks the action of the inhibitory transmitter; that is, picrotoxin appears to have a "curarelike" action on this inhibitory synapse. Perhaps the convulsions and central nervous system excitation produced when picrotoxin is injected into a mammal are caused by a similar mechanism.

WILLIAM G. VAN DER KLOOT
Department of Zoology, Cornell University, Ithaca, New York

JAY ROBBINS
College of Physicians and Surgeons, Columbia University, New York, New York

IAN M. COOKE
Biological Laboratories, Harvard University, Cambridge, Massachusetts

References and Notes

1. C. A. G. Wiersma, in *Recent Advances in Invertebrate Physiology* (Univ. of Oregon Press, 1957); P. Hoffman, *Z. Biol.* 63, 411 (1914); 64, 247 (1914).

2. The experiments described in this report were carried out at the Biological Laboratories, Harvard University, and at the Department of Zoology, Cornell University. They were supported, in part, by grants B703 and B-1089 from the Institute of Neurological Diseases and Blindness, U.S. Public Health Service. They were also aided by a summer fellowship from the College of Physicians and Surgeons of Columbia University. The picrotoxin was obtained from the Fisher Scientific Co.

3. This modification was made by adding 55 ml of 0.2*M* trismaleate buffer to 945 ml of crayfish perfusion fluid. The crayfish perfusion fluid was the Ringer's solution of van Harreveld [*Proc. Soc. Exptl. Biol. Med.* 34, 428 (1936)] with the $NaHCO_3$ omitted.

4. G. Marmont and C. A. G. Wiersma, *J. Physiol. (London)* 93, 173 (1938).

5. The percentage inhibition is defined as:

$$\frac{C_e - C_{ei}}{C_e} \times 100$$

where C_e is the initial rate of contraction with stimulation of the excitatory nerve alone and C_{ei} is the initial rate of contraction when both the excitatory nerve and the inhibitory nerve are stimulated.

6. E. Florey, *Arch. intern. physiol.* 62, 33 (1954); E. Florey and H. McLennan, *J. Physiol. (London)* 129, 384 (1955); K. Elliott and E. Florey, *J. Neurochem.* 1, 181 (1956).

14 October 1957

Book Reviews

Industry and Technical Progress. Factors governing the speed of application of science. C. F. Carter and B. R. Williams. Oxford University Press, London, 1957 (order from Oxford University Press, New York). viii + 244 pp. $4.

One of the most difficult of man's tasks is keeping a perspective on the "present"—remembering how much the present depends on the past and how little the future will resemble the present. C. F. Carter and B. R. Williams have tried to develop some of this perspective with regard to the role of science and scientific personnel in British industry.

In this task, the authors seem to have steered a wise course. Rather than supply answers, they have tried to present the major problems of effective utilization of science and scientific personnel, in the circumstances and current traditions of British industry, in the context of that industry's present economic, social, and political environment. In presenting these problems in this frame of reference, they also expose the fallacies of many simple panaceas which are proposed from time to time.

As in most problems of this size, it turns out that an evolution, rather than answers, seems to be required for substantial improvements—an evolution involving large segments of a country's human resources: management, scientists, teachers, government employees, and so on. Members of each of these segments must learn more about the problems and about the roles they can play in the segments. *Industry and Technical Progress* can serve this required orientation function quite well.

I find one major disquieting over-all note in the book. It seems tacitly to assume that the way to technical progress will be through profit motives of industry. This assumption seems closely akin to the largely discredited "theories of the firm," based solely on economic concepts, for describing the activities of companies. It appears, more and more, that economic concepts alone are not adequate in considering industrial companies and that consideration of elements of political and social behavior is also required. And, with regard to technical progress, man's simple but God-given scientific curiosity would seem much too important a factor to be overlooked. I would put it to the authors that the driving force behind individuals in large company research organizations is still simple curiosity—and that technical innovations result to a much greater extent out of this curiosity than out of commercial pressures.

HARLAN D. MILLS
Princeton University

Principles of Engineering Geology and Geotechnics. Geology, soil, and rock mechanics, and other earth sciences used in civil engineering. Dimitri P. Krynine and William R. Judd. McGraw-Hill, New York, 1957. xiii + 730 pp. Illus. $10.

The appearance of an engineering text with the word *geotechnics* in its title is a healthy sign of the steady development of earth studies by engineers. Much as professional engineers dislike the word *technology* (and its derivatives) when applied to their work, they have generally welcomed the use of *geotechnics*, in view of its obvious advantages. It has a direct French equivalent (*"Geotechnique"* having already been adopted as the name of an international journal in this field); it has a useful parallel in the word *geophysics*; and it is succinctly descriptive of the study of the engineering uses to which the materials that constitute the earth's crust are put. It is this field that is treated in the volume under review.

The volume is a veritable storehouse of information, indicative of the senior author's lifetime of experience and of the use by the junior author of some of the accumulated corporate experience of the U.S. Bureau of Reclamation, where he serves as engineering geologist on the staff of the chief engineer. The book is well illustrated and well indexed, being up to the usual high standard of McGraw-Hill volumes from the standpoint of production.

Readers of *Science* will want to know the audience for whom this volume is intended. A detailed study of its contents, made in an attempt to determine this, leads to somewhat puzzling results. The book is far too large and diffuse to serve as a college textbook. As the authors themselves state, "case histories have been used only for the elucidation of principles," and this is therefore not a collection of case histories of the type that can be so valuable an aid to the practicing, as also to the embryo, engineer. And as a reference book it has the unfortunate feature of merely directing the reader to another reference on all too many important topics.

So much work has clearly gone into the preparation of the book that one regrets being unable to give it unqualified praise. With the mounting volume of technical literature, however, such a collection of undigested material—useful though the lists of individual references are—is not as helpful as it might be. The arrangement of the book is a fair indication of the additional attention in assembling and pruning of contents that it so clearly needs. Seven of the 19 chapters, for example, deal successively with "Subsurface Exploration," "Maps and Airphotos," "Rock as a Construction Material," "Tunnels," "Frost and Permafrost," "Shore-line Engineering and River Improvement," and "Elements of Sedimentation Engineering [sic]." If there is order or logic in this arrangement, it has escaped my attention.

As a useful guide to current American literature in the field of geotechnics, the book can be highly commended. At the same time, it can serve as a telling example of the fact that, in order to be fully effective, a good book requires something more than the collection between two covers of a vast quantity of factual information, useful and interesting though this may be.

ROBERT F. LEGGET
Division of Building Research, National Research Council, Ottawa, Ontario

Medical Radiation Biology. Friedrich Ellinger. Thomas, Springfield, Ill.; Blackwell, London; Ryerson, Toronto, 1957. xxxiv + 945 pp. Illus. $20.

Medical radiation biology is defined by the author as comprising clinical radiation biology and experimental radiation therapy. However, this book can in no sense be described as a text on radiation therapy. It is rather a book in which the author intends to compile "the rationale on which the role of radiation as a health hazard and as a therapeutic agent is based."

The book, with some 4600 references

occupying one-fourth of the 950 pages, is divided into four parts: (i) fundamental radiation biology; (ii) biology of ionizing radiations; (iii) biology of ultraviolet radiation; and (iv) photobiology. There are numerous textual references to the bibliography, but the usefulness of the volume as a reference work is limited by the absence of an index.

A comprehensive review of the gross and microscopic effects of radiation on each organ system is presented. This extensive pathophysiologic discussion is amply documented by carefully selected references to articles published in the English, French, and German languages.

For one author to attempt a review and critical summary of the extensive fields outlined above is indeed an ambitious project. Certainly the treatment of specialized subjects will not satisfy the expert in the field. The book's usefulness must therefore lie in its attempt to serve as an introduction to radiobiology and as a link between fields in radiobiology.

Surgeons and internists, not to mention radiotherapists, will pause at the sentence, "for the general public radiation therapy and treatment of cancer are almost synonymous." In the discussion of the radioactive iodine (I^{131}) therapy for hyperthyroidism, there are several errors, not the least of which are two errors in the formula to be used for calculation of the number of millicuries of radioactive iodine required to deliver a certain radiation dose to the thyroid.

In summary, this volume by a mature and forthright clinician and investigator may be useful to the experienced radiologist who wishes a survey, simply presented, of the field of radiobiology. It is not recommended for those uninitiated in the fundamentals of radiation physics or radiobiology, or both.

J. L. STEINFELD
National Institutes of Health

Parthenogenesis and Polyploidy in Mammalian Development. Cambridge Monographs in Experimental Biology No. 7. R. A. Beatty. Cambridge University Press, New York, 1957. xi + 132 pp. Illus. $3.

R. A. Beatty of the department of animal genetics of the University of Edinburgh has given us a very complete and critical account of parthenogenesis and heteroploidy in mammals. He is uniquely qualified for this task, for several reasons: together with M. Fischberg, now at Oxford, he has made a thorough investigation of spontaneous and induced heteroploidy in eggs and embryos of mice; in 1954 he published [*Intern. Rev. Cytol.* **3** (1954)] a lucid review under the title "How many chromosomes in mammalian somatic cells?", which summed up our knowledge of the real and, in some cases, spurious inconstancy of somatic chromosome numbers; last, but not least, he is probably the only mammalian cytologist who has had the enterprise to count his own chromosomes, in dividing cells of a hair follicle (I believe he found 48—or was it 46?).

The author places the primary emphasis on the "cytological variables" which furnish the known or surmised mechanisms of origin of the various observed or theoretically expected chromosome numbers. The principal variables are the suppression of the first or second meiotic division in the egg, or of the first cleavage mitosis, either with or without fertilization of the egg (amphimictic versus apomictic routes). In consideration of the various possible combinations of these variables, the material is classified in chapters 3, 4, and 5 under the headings "The eight apomictic routes in the major group," "The eight amphimictic routes in the major group," and "A minor group of routes of development." This treatment is logical but tends to make the organization of the material unnecessarily complicated, since the actual route which gave rise to some abnormal chromosome numbers is often not known with certainty. It might have been preferable to classify the various cases first according to chromosome number and then to subdivide these primary categories into secondary classes on the basis of the known or probable mode of origin.

A few omissions or inaccuracies should be mentioned. The paper by Ursula Jahn (1952) on colchicine-induced tetraploidy in *Rana esculenta* (which appears to be connected with gigantism, in contrast to all other observations on polyploid amphibia) is not mentioned; the study by A. A. Humphries (1956) on the occurrence of abnormal meiotic divisions in untreated coelomic or oviducal eggs of *Triturus viridescens*, which demonstrates the probable origins of spontaneous polyploids in this species, probably appeared too late to be considered. The term "poikiloploidy" mentioned on page 6 was first used by Levy (1920) to designate the occurrence of different abnormal chromosome numbers within the same embryo. The statement (page 9) that, "in amphibians, an *inverse* proportion exists between cell or nuclear volume and the number of chromosome sets" is obviously wrong, as is the assertion that the number of heterochromatic spots, important in determining the number of chromosome sets in tissues of some insects, has been used for the same purpose in amphibians by Fankhauser and Humphrey (1943); we used the number of nucleoli exclusively.

In chapter 6 Beatty discusses some general aspects of parthenogenesis and polyploidy in mammals. These include (i) the debated role of polyploidy in mammalian evolution; (ii) the question of whether polyploid mammalian fetuses are viable (so far no polyploid mouse embryos have ever been found after midterm); (iii) the question of whether spontaneously parthenogenetic mammals ever come to term and could be identified (which the author thinks highly improbable); (iv) some specific genetic aspects of parthenogenesis and polyploidy, such as gene dosage; (v) sex determination and fertility in polyploids; and (vi) their size and growth rate.

Beatty's book will be an important guide for all those who are interested in developmental genetics and the cytology of mammals and will stimulate many new experiments in this fascinating and relatively new field.

G. FANKHAUSER
Princeton University

The Fascination of Numbers. W. J. Reichmann. Essential Books, Fair Lawn, N.J., 1957. 176 pp. $4.

The theory of numbers is a many-sided mathematical theory, but first and foremost it is concerned with the properties of the integers 1, 2, 3, 4. . . . It is a fascinating theory; it has some problems which are so easy to formulate that an intelligent youngster in the eighth grade can fully understand them but so difficult to solve that the united effort of the greatest mathematicians of the last three centuries was unable to master them. The integers may have a singular attraction for an exceptionally gifted youngster and open his mind to science. Therefore, it is to be deplored that divisibility, prime numbers, and similar topics are almost completely neglected by our high schools (they are taught in the corresponding European schools). Under these circumstances a good popular book dealing with these topics would be highly welcome.

The present book deals with such topics, but, unfortunately, in my opinion, it does not fulfill the great promise of the subject matter. The sequence in which the topics are treated seems almost random. The difference between inductive evidence and strict proof is nowhere emphasized; both are often omitted without warning, but the worst of it is that neither is really neatly presented. Little previous knowledge is asked from the reader, and that is right; but there are a few pages, some right in the middle of the book, where the reader is sud-

denly supposed to understand logarithms or trigonometry or infinite series, or infinite continued fractions. There are a few incorrect assertions, some disconcerting typographical errors, and a few places where the author misapplies the simplest mathematical terms, such as *equation* or *identity*.

G. POLYA

Stanford University

Neutron Cross Sections. Donald J. Hughes. Pergamon, London and New York, 1957. x + 182 pp. Illus. $5.

Neutron Cross-Sections, by D. J. Hughes, is a monograph devoted to assisting people who do not have training in nuclear theory and who must use cross sections. As director of the neutron cross-sections compilation work at Brookhaven Laboratory, Hughes was in an excellent position to judge what terms caused nonphysicists the most trouble. The first chapter of the book is devoted to introducing the reader to the language of neutron physics by use of the terms in context; this monograph is not a dictionary.

The second chapter is devoted to the nomenclature employed by theoretical physicists in developing models to explain and correlate the experimental data. This chapter is a very nice demonstration of Hughes' ability as a writer to cover a complex subject concisely and simply.

In the last four chapters Hughes acquaints the reader with some of the details of specialized areas of neutron physics.

Those working in the fields of differential cross sections and inelastic scattering cross sections will probably regret that the author does not make a greater effort to clarify terminology in these areas.

A. WATTENBERG

Laboratory for Nuclear Science, Massachusetts Institute of Technology

Natural Magick. A volume in *The Collector's Series in Science*. John Baptista Porta. Derek J. Price, Ed. Basic Books, New York, 1957. ix + 419 pp. Illus. $7.50.

To penetrate the mystery of the rise of "modern science" in the 16th and 17th centuries, it is not enough to know something of Copernicus, Galileo, and the other giants. The republication of Porta's book (edition of 1658)—long a guarded treasure of the rare-book rooms of libraries—offers a pleasant and profitable tour through what the editor calls the "plain-lands" of early science, from which these giants sprang. This work is typical of a vast forgotten literature, best described in modern terminology as popular encyclopedias of the arts and sciences. Porta was no hack writer, however, but a competent, if not a profound, natural philosopher whose contributions to science were not insignificant. He was instrumental in founding the first modern "academy of science" (the Accademia Secretorum Naturae), and its proceedings are reflected in the present book.

The volume is attractively bound and boxed. The reproduction of the archaic type face of the original is a questionable advantage, but no great obstacle to the enjoyment of what may best serve as a sort of scientists's bedside book. According to his mood, the reader can sample the science and lore of magnetism before Gilbert or of optics before the telescope and microscope; or he can peruse relatively lucid accounts of the transmutation of metals or of the "new" fad in chemistry—distillation. In a lighter mood, he can discover how women were beautified in these centuries, or how secret communications were accomplished. Anyone interested in the history of science, or in history at all, can find profit and enjoyment in this book.

ROBERT MULTHAUF

Smithsonian Institution

Reptiles Round the World. A simplified natural history of the snakes, lizards, turtles, and crocodilians. Clifford H. Pope. Knopf, New York, 1957. xv + 204 pp. Illus. $3.50.

The author, well-known for previous herpetological works, both technical and semipopular, has prepared this new book with the younger generation in mind—the boys and girls whose interest in nature is beginning to be centered on a particular branch of natural history.

The professional scientist always faces a serious task in undertaking a book of this kind. Almost never is there a question of knowledge of the subject; the problem is one of presenting the subject in abbreviated and simplified form, yet in so well-balanced and attractive a manner as to encourage the young reader into expanding his field observations and studies. In this respect Pope has succeeded admirably. The book is interesting and instructive, and the facts regarding the several groups of reptiles are presented in the orderly manner so necessary for supplying the young reader with a basic understanding of the extent of the several groups and the subdivisions within them. Technical terms are largely avoided, as are the restrictions of taxonomy, since discussions are seldom carried below the generic level.

The subject is treated from two major viewpoints: first, there are chapters on the different features of reptile life, such as locomotion, food, reproduction, size, growth, enemies, and habits; these are followed by a survey of the distribution, by continents, of each major group. The discussions are illustrated by many attractive sketches by Helen Damrosch Tee-Van.

This book can be recommended as a foundation upon which the budding herpetologist can build his further studies. Among other sound advice, it even contains a word of caution to the youngster of exhibitionist tendencies who aspires to make a career of handling snakes before shocked but fascinated audiences (mostly female). The museums and zoos requiring herpetological curators are too few to supply a livelihood for more than a fraction of these aspirants; besides which, the duties of herpetological curators almost never involve such spectacular but nonscientific exploits.

LAURENCE M. KLAUBER

San Diego Museum of Natural History, San Diego, California

New Books

The Frogfishes of the Family Antennariidae. No. 3383, Proceedings of the U.S. National Museum, vol. 107. Leonard P. Schultz. Smithsonian Institution, Washington, D.C., 1957. 58 pp.

Discovery. No. 2, 1957. University of Melbourne. Melbourne University Press, Carlton, N.3, Victoria, 1957. 96 pp. 2s. 6d.

International Sanitary Regulations. Adopted by the Fourth World Health Assembly in 1951 and amended by the eighth and nine assemblies in 1955 and 1956. Annotated edition. World Health Organization, Geneva, 1957 (order from Columbia University Press, New York). 127 pp. $1.

Four Basic Aspects of Preventive Psychiatry. Report of the First Institute on Preventive Psychiatry held at the State University of Iowa, 3 Apr. 1957. Ralph H. Ojemann, Ed. State University of Iowa, Iowa City, 1957. 122 pp. $2.

The Biology and Systematics of the Pinfish, Lagodon Rhomboides (Linnaeus). Bulletin of the Florida State Museum, Biological Science, vol. 2, No. 6. David K. Caldwell. University of Florida, Gainesville, 1957. 98 pp. $1.25.

Handbuch der Physik. vol. XVI, *Electric Fields and Waves*. S. Flügge, Ed. Springer, Berlin, 1958. 760 pp. DM. 158.

Metabolism of the Nervous System. Derek Richter. Pergamon Press, New York and London, 1957. 613 pp. $16.

Queues, Inventories and Maintenance. The analysis of operational systems with variable demand and supply. Philip M. Morse. Wiley, New York; Chapman and Hall, London, 1958. 211 pp. $6.50.

Meetings and Societies

Program of the Gordon Research Conferences

The Gordon Research Conferences for 1958 will be held from 9 June to 29 August at Colby Junior College, New London, N.H.; New Hampton School, New Hampton, N.H., and Kimball Union Academy, Meriden, N.H.

Purpose. The conferences were established to stimulate research in universities, research foundations, and industrial laboratories. This purpose is achieved by an informal type of meeting consisting of scheduled lectures and discussion groups. Sufficient time is available to stimulate informal discussions among the members of a conference. Meetings are held in the morning and in the evening, Monday through Friday, with the exception of Friday evening. The afternoons are available for recreation, reading, or participation in discussion groups, as the individual desires. This type of meeting is a valuable means of disseminating information and ideas to an extent that could not be achieved through the usual channels of publication and presentation at scientific meetings. In addition, scientists in related fields become acquainted and valuable associations are formed that often result in collaboration and cooperative efforts between different laboratories.

It is hoped that each conference will extend the frontiers of science by fostering a free and informal exchange of ideas among persons actively interested in the subjects under discussion. The purpose of the program is not to review the known fields of chemistry but, primarily, to bring experts up to date on the latest developments, to analyze the significance of these developments, and to provoke suggestions concerning the underlying theories and profitable methods of approach for making new progress.

In order to protect individual rights and to promote discussion, it is an established requirement of each conference that no part of the information presented is to be used without specific authorization of the individual making the contribution, whether in formal presentation or in discussion. Scientific publications are not prepared as emanating from the conferences.

Registration and reservations. Attendance at the conferences is by application. Individuals interested in attending the conferences are requested to send their applications to the director at least 2 months prior to the date of the conference. *All applications must be submitted on the standard application form,* which may be obtained by writing to the office of the director. This procedure is important because certain specific information is required in order that a fair and equitable decision on the application may be made. Attendance at each conference is limited to approximately one hundred individuals.

The director will submit the names of those requesting authorization to attend the Conference Committee for each conference. This committee will review the names and select the members in an effort to distribute the attendance as widely as possible among the various institutions and laboratories represented. A registration card will be mailed to those selected, as soon as possible. Advance registration by mail for each conference is required, and registration is completed on receipt of the card and a deposit of $15 (checks are to be made payable to the Gordon Research Conferences). The deposit of $15 will be credited against the fixed fee for the conference if the individual attends the conference for which he has applied. A registration card not accompanied by the $15 deposit will not be accepted.

The board of trustees of the conferences has established a fixed fee of $100 for each conference. This fee was established to encourage attendance for the entire conference and to increase the special fund that is available to each conference chairman for the purpose of assisting conferees who attend a conference at total or partial personal expense with their travel or subsistence expenses, or with both. This fixed fee will be charged regardless of the time a conferee attends the conference—that is, for periords of from 1 to 4½ days. It is divided as follows: registration fee, $40 ($15 for administration and $25 for the special fund); room and meals, $60 (including gratuities), for 5 days. An additional charge of $1 per night per person will be made for a room with private bath or for a single room, of which there are a limited number available. These rooms will be assigned in the order that applications are received.

Members attending a conference are expected to live at the conference location because one of the objectives of the conferences is to provide a place where scientists can get together informally. It is to the advantage of all participants to attend a conference for the entire week. If special circumstances warrant living elsewhere, a registration fee of $50 is charged.

The fixed fee will cover registration, room (except room with private bath or single room), meals, and gratuities. It will not provide for golf, telephone, taxi, laundry, conference photograph, or any other personal expenses.

Conferees on total or partial personal expense who are living at the conference location, may request a reduction of $25 (the amount allotted for the special fund) in the fixed fee. Application for this special fee ($75) must be made when the registration card is returned to the director.

Accommodations are available for a limited number of women to attend each conference, and also for wives who wish to accompany their husbands. All such requests should be made at the time the attendance application is submitted, because these accommodations, limited in number, will be assigned in the order that specific requests are received. Children under 12 years of age cannot be accommodated. Dogs or other animals will not be permitted in the dormitories.

Special fund. The special fund is provided for by the board of trustees from the registration fees and is made available to the chairman of each conference for the purpose of assisting scientists from academic and government institutions who could not otherwise attend or participate because of financial limitations. This fund is provided with the object of increasing the participation of research workers from academic and government laboratories; its use is not limited to scientists who have been invited by the chairman to attend a conference in order to present a paper. The money is to be used as an assistance fund only and may be used to contribute toward traveling expenses or subsistence expenses at the conference, or both. Total travel and subsistence expenses will not usually be provided.

Cancellations. The cancellation of an approved application for attendance at a conference will cause forfeiture of the $15 deposit.

Attendance. Requests for attendance at the conferences or for additional information should be addressed to W. George Parks, Director, Department of

Chemistry, University of Rhode Island, Kingston, R.I. From 9 June to 29 August, mail should be addressed to Colby Junior College, New London, N.H.

Colby Junior College

Petroleum

Philip D. Caesar, *chairman*
George H. Denison, *vice chairman*

9–13 June. R. E. Kallio, "Microbial oxidation of hydrocarbons"; W. H. Bauer, "Oxidation of boranes"; P. S. Bailey, "Mechanisms of ozonolysis of hydrocarbons"; H. G. Wolfhard, "The physics and chemistry of combustion"; R. J. Gordon, "Application of a single molecular orbital model to combustion reactions"; E. B. Rifkin, "New advances in the chemistry and physics of antiknock action"; Andrew Fono, "Homolytic reactions induced by metal salts"; Joseph Weiss, "Radiation induced oxidation of hydrocarbons"; Glen A. Russell, "Fundamental processes in autooxidation of hydrocarbons."

Separation and Purification

Lyman C. Craig, *chairman*
Edmond S. Perry, *vice chairman*

16 June. Joel H. Hildebrand, "What solubility theory has to offer"; J. L. Torgesen, "The retention of impurities by growing crystals"; H. L. Meltzer, "Three phase countercurrent distribution."

17 June. W. E. Henderson, "Separations by filtration through membranes"; O. Smithies, "Zone electrophoresis in starch gels"; K. Hickman, "Recovery of water."

18 June. H. A. Sober, "Chromatography with columns of modified cellulose"; M. A. Mitz, "Effect of CO_2 on chromatograms with modified cellulose"; A. T. James, "Vapor-liquid chromatography."

19 June. D. F. Peppard, "Mechanism of extraction of metallic cations by acid esters of orthophosphoric acid"; B. S. Weaver, "Separation of rare earths by liquid-liquid extraction."

20 June. W. Greiner, "A commercial countercurrent solid-liquid extraction process"; M. W. Fogle and C. C. DeWitt, "An engineering approach to the separation of amino acids."

Catalysis

Vladimir Haensel, *chairman*
R. P. Eischens, *vice chairman*

23–27 June. H. L. Pickering and H. C. Eckstrom, "Infrared studies of adsorbed species on evaporated metal films"; J. Halpern, "Homogeneously catalyzed reactions of molecular hydrogen in solution"; D. E. O'Reilly, "Nuclear magnetic resonance studies of catalytic solids"; T. R. Hughes, R. J. Houston, and R. P. Sieg, "Carbon monoxide chemisorption on supported metal catalysts by radiotracer measurements in a flow system"; G. Parravano, "Oxygen affinities of metal catalysts"; G. S. John and R. J. Mikovsky, "Average properties of fluidized catalysts"; F. C. Tompkins, "Chemisorption and catalysis"; Herman Pines, W. O. Haag, and Gaston Benoy, "Alumina—a catalyst and a support"; H. Kloosterziel, "Hydrogen-deuterium exchange and redistribution reactions of hydrocarbons on solid catalysts."

Polymers

T. G. Fox, *chairman*
F. R. Eirich, *vice chairman*

30 June. H. Mark, "Recent advances in polymer chemistry"; C. Sadron, "Recent research in the Centre de Recherches sur les Macromolecules of Strasbourg"; J. C. W. Chien, "Kinetics of ethylene polymerization by soluble organotitanium-aluminum catalysts."

1 July. A. Korotov, "Kinetics and mechanism of polymerization of vinyl monomers by metallo-organic compounds"; J. W. L. Fordham, "Stereoregular polymers from free radical initiators"; J. R. Schaefgen, "Laterally ordered polymers."

2 July. W. Slichter, "NMR studies of some stereospecific polymers"; W. R. Krigbaum, "Thermodynamics of the polystyrene-cyclohexane system near the Flory theta temperature."

3 July. E. L. Wittbecker, "Interfacial polycondensation"; P. W. Morgan, "Fundamentals of interfacial polycondensation"; W. Kern, "The importance of uniformity of structure in macromolecular chemistry."

4 July. R. K. Graham, "The synthesis and characterization of graft copolymers"; Y. Landler, "Physical and mechanical properties of some graft copolymers obtained by preozonization."

Textiles

Emery I. Valko, *chairman*
Leonard Smith, *vice chairman*

7 July. H. Mark, "Deformation mechanism of polymers"; Norman J. Abbott and Freddy Khoury, "Tenison changes in textile structures during wetting and drying."

8 July. W. A. Sisson, "The structure and properties of viscose rayons"; R. E. Seaman and J. C. Shivers, "Elastic textile fibers based on condensation polymers."

9 July. C. M. Conrad, "Relationships between mechanical behavior and chemical modification of cotton"; Helmut Zahn, "Some new results in wool chemistry."

10 July. A. A. Burgeni and E. V. Painter, "Movement of fluids in fibrous beds: capillary sorption, permeation"; F. W. Minor, L. C. Buckles, E. Wulkow, and A. M. Schwartz, "The transport of liquids in textile assemblies."

11 July. C. Schlatter, "Mechanism of fiber and yarn lubrication."

Corrosion

Joseph E. Draley, *chairman*
P. M. Aziz, *vice chairman*

14–18 July. The nature of metal surfaces: H. Juretschke, "The atomic nature of metal surfaces"; C. S. Smith, "Metallography and corrosion." *Adsorption on metals*: J. T. Law, "The adsorption process on semiconductors"; L. S. Bartell, "Optical studies of adsorption from solution"; R. T. Gomer, "Field and ion emission microscopy"; P. W. Selwood, "Magnetization and surface chemistry." *Oxides on metals*: J. V. Cathcart, "The microtopography of oxide films on metals"; Jerome Kruger; "The growth of oxide films on copper in water containing oxygen"; W. D. Feitknecht, "Chemistry of the corrosion products formed on Cu, Cd, Zr, and Fe in aqueous solutions"; E. A. Gulbransen, "Crystal habits in localized corrosion and oxidation processes in relation to metal structure." *Electrode reactions*: J. O'M. Bockris, "The mechanism of anodic dissolution of metals and the inhibition of corrosion." *Passivity*: Review of Darmstadt passivity colloquium and general discussion on passivity mechanisms.

Vitamins and Metabolism

Lemuel D. Wright, *chairman*
Harry P. Broquist, *vice chairman*

21 July. Klaus Schwarz, "The factor 3 potencies of selenium compounds in dietary liver necrosis and in other deficiencies"; M. L. Scott and M. C. Nesheim, "Selenium as a nutrient for chicks"; E. L. R. Stokstad and R. G. Eggert, "Role of vitamin E and selenium in the nutrition of the pig"; Lester J. Reed, "Nature and reactions of protein-bound lipoic acid"; David E. Metzler, "Catalysis of pyruvate decarboxylation by thiamine and thiamine analogs."

22 July. Victor W. Rodwell, Miyoshi Ikawa, Benjamin E. Volcani, and Esmond E. Snell, "The bacterial oxidation of pyridoxine"; Sidney Weinhouse, "Factors influencing entry and removal of blood glucose"; John Spizizen, "Metabolism of viruses"; Boris Magasanik, "Histidine biosynthesis"; H. Waelsch, A. Neidle, and D. D. Clarke, "Amine metabolism."

23 July. G. Popjak, J. W. Cornforth, R. H. Cornforth, J. Gosselin, R. G. Gould, I. Youhotsky-Gore, and A. de Waard, "Biosynthesis of squalene and sterol from mevalonic acid"; T. T. Tchen, "The earlier stages of steroid biogenesis"; E. Kodicek, "Studies on sterols in microorganisms"; David B. Sprinson, P. R. Srinivasan, and J.

Rothschild, "The metabolic reactions between glucose and aromatic compounds"; D. W. Woolley, "Serotonin"; Byron E. Leach, Robert G. Heath, and Mathew Cohen, "Studies with taraxein."

24 July. June Lascelles, "Factors involved in the synthesis of porphyrins and related pigments by microorganisms"; Peter B. Danneberg, "Chemotherapeutic studies with fluorinated pyrimidines"; Samuel Bieber, "Uracil antagonists and tumor inhibition"; Howard A. Schneiderman, "Chemistry and physiology of insect hormones"; Hugh S. Forrest, "Metabolic reactions of biopterin."

25 July. J. R. Couch, "Mineral metabolism in the avian species"; James S. Dinning, "The role of vitamins C and B_{12} in one-carbon metabolism"; N. W. Flodin, "Amino acid fortification."

Instrumentation

N. B. Nichols, *chairman*
Clifford E. Berry, *vice chairman*

28 July–1 Aug. Invited papers. William A. Baum, "Image tubes and their astronomical applications"; Philip G. Gilman, "Automatic data logging"; John H. Heller, "Challenging problems in medical and biological instrumentation"; P. C. Hoell, "Electron beam dosimetry"; C. Lester Hogan, "Masers"; R. N. Lane, "Solions"; Marcus O'Day, "Worth-while rediscoveries from 100 years ago"; H. I. Schiff, "The use of the mass spectrometer in studying free radicals and other short-lived species."

Contributed papers. R. P. Bigliano, "Analog computers as process control elements"; Erik Blomgren, "Some new principles and devices for the study of electrochemical phenomena"; W. M. Flook, "New instrument developments"; A. S. Iberall, "Some transfer functions of the human in a control situation"; Joseph M. Kime, "An indoor coefficient of restitution tester for golfballs and baseballs"; Sidney Lees, "A physical basis for control system dynamics"; C. G. McIlwraith and J. B. Breazeale, "Instrument applications of low friction magnetic bearings"; Eugene Mittelman, "Heat transfer measurements under dynamic conditions"; C. B. Moore, "A noncontacting static meter for textile yarn"; Henry J. Noebels, "New instrumentation for measuring substances in the ppm region"; Louis Rosenthal, "An automatic heating-cooling curve apparatus"; E. W. Silvertooth, "Tracking instrumentation for balloon-borne telescope"; Lloyd Slater, "The academic stature of instrumentation"; Harry Sohon, "A novel method of measuring electrical phase angles"; Frederick Vanderschmidt and J. C. Simons, Jr., "New instruments using radioisotopes as ionizing sources"; R. R. Webster, R. L. Uphoff, and J. F. Laycak, "An acoustic volume gage."

Elastomers

Edwin B. Newton, *chairman*
Paul G. Carpenter, *vice chairman*

4 Aug. W. Postelnik, "Status of the high temperature polymer program"; W. F. Watson, "Mechanico-chemical reactions of polymers"; G. S. Trick, "Effects of microstructure on crystallization rates of elastomers."

5 Aug. M. Berger, "Kinematics of a rolling tire and its application to tire performance"; D. C. Edwards and E. B. Storey, "The union of butyl rubber with carbon black"; A. M. Gessler, "Subnormal structure channel blacks and their reinforcing effect in rubber."

6 Aug. B. Ellis and G. N. Welding, "Vulcanization characteristics of natural rubber gum stock ACS-1"; C. J. Jankowski, R. F. Neu, and R. L. Zapp, "New vulcanization studies with butyl rubber"; David Craig, D. E. Diller, R. B. Fowler, F. A. Regenass, E. H. Rowe, W. L. Semon, J. J. Shipman, and H. Tucker, "Perdeuterio SN rubber."

7 Aug. Maurice Morton and Alan Rembaum, "Some aspects of homogeneous anionic polymerization"; Paul Fugassi, "The sorption of benzene by natural and synthetic polymeric hydrocarbons"; Melvin Mooney, "The rheology of visco-elastic materials."

8 Aug. Henno Keskkula, J. A. Schmidt, and J. G. Cobler, "Methods of studying rubber-polystyrene compositions."

Food and Nutrition

Robert H. Silber, *chairman*
Lester J. Teply, *vice chairman*

11 Aug. Aline U. Orten, "The intestinal absorption of amino acids"; Alfred E. Harper, "Amino acid balance and imbalance"; James M. Hundley, "Vegetable proteins in human nutrition"; Theodore Van Itallie, "Physiological aspects of hunger and satiety."

12 Aug. Roselyn Alfin-Slater, "Further observations in fatty acid nutrition"; Albert Behnke, "Changes in gross body composition and in adipose tissue as a result of caloric restriction"; F. N. Andrews, "Hormonal relationships to nutrition in domestic animals"; Franklin C. McLean, "Hormonal and nutritional factors in osteoporosis."

13 Aug. R. R. Williams, "Food supplementation in relation to world food shortage"; O. L. Kline, "Food supplementation"; Olaf Mickelson, "Is toxicology enough for a food protection program?"; Josef Warkany, "Nutritional experiments as an instrument of research in congenital malformations"; Josef Brozek, "Recent developments in studies of the relations between nutrition and behavior."

14 Aug. Mark Hegsted, "The establishment of nutritional requirements of man"; Calvin Woodruff, "Infant nutritional requirements—fact, fancy, and calculations"; Arnold Schaefer, "Nutritional surveys in the Near and the Far East"; William J. Darby, "The program of nutrition of the World Health Organization."

15 Aug. S. H. Wittwer, "Effect of gibberellin on plant growth and composition"; Kenneth Beeson, "Effects of fertilizers on the nutritional value of plants."

Medicinal Chemistry

Maynard B. Chenoweth, *chairman*
Alfred Burger, *vice chairman*

18 Aug. Symposium on fundamentals in medicinal chemistry: Bernard Belleau, "Fundamental principles governing adrenergic blocking activity of beta-haloalkylamines"; E. J. Ariens, "Affinity and intrinsic activity in medicinal chemistry"; George B. Brown, "Some biologically active purine derivatives"; B. R. Baker, "Mechanisms of action of certain non-competitive inhibitors."

19 Aug. Symposium on fundamentals in pharmacology: Walter F. Riker, "An analysis of quaternary ammonium action at the neuromuscular synapse"; Edith Bülbring, "The function of 5-hydroxytryptamine in peristalsis"; Desmond R. H. Gourley, "Effects of drugs on active transport"; Aser Rothstein, "The cell surface as the site of action of drugs and metals."

20 Aug. Symposium on central nervous system stimulants: John H. Biel, "Chemistry of some central stimulants"; Leo G. Abood, "The psychotogenic action of piperidyl benzilates and related substances"; Lewis Danziger, "Some servo mechanisms in medicinal chemistry"; Mildred C. Rebstock, "Natural and synthetic antibiotic families."

21 Aug. Symposium on adrenal cortical inhibition and aldosterone: W. L. Bencze and M. J. Allen, "Chemistry of amphenone-analogs"; J. J. Chart and H. Sheppard, "Pharmacology of amphenone-analogs"; K. Heusler, O. Wieland, H. Ueberwasser, and A. Wettstein, "A new total synthesis of aldosterone"; Dickinson W. Richards, "Pharmacology of the lung: present knowledge and future needs."

22 Aug. Symposium on salicylates: Richard V. Heinzelman, "Chemistry of newer salicylates"; William B. Bass, "Pharmacology of newer salicylates"; Raymond W. Houde, "Analgesics related to salicylic acid: clinical studies in patients with pain due to cancer."

Cancer

H. G. Schlumberger, *chairman*
Frederik B. Bang, *vice chairman*

25 Aug. J. J. Biesele, "Early cytological effects of carcinogens"; Stanfield Rogers, "Mechanism of urethane-induced lung carcinoma in mice"; Wilhelm Hueper, "Carcinogenic studies on

water soluble and insoluble macromolecules"; S. C. Sommers, "Pathological evidence of endocrine imbalance in cancer patients"; J. Leighton, "Mechanisms of tumor invasion as seen in tissue culture."

26 Aug. L. Kilham, "Fibroma of squirrels transmitted by a virus immunologically related to the Shope rabbit fibroma virus"; R. C. Mellors, "Fluorescent antibody study of viruses in experimental neoplasms"; J. A. Reyniers, "Germ-free animals and cancer research." Alfred Gellhorn, *chairman*: Abraham Goldin, "Competitive analogue-metabolite relationships in cancer chemotherapy"; Julian J. Jaffé, "The chemotherapy of neoplasms using azauracil and azauridine"; J. F. Holland, "Tumor suppressive activity in tumor ascites fluid."

27 Aug. E. Zwilling, "Differentiation of early chick embryo tissues following disaggregation and reaggregation"; D. McKay, "Histochemistry of the migrating primordial germ cell"; G. Barry Pierce, "Tissue—and organogenesis in mouse teratomas"; H. S. Fleming, "Organoid growth of transplants in the eye"; W. F. Loomis, "The role of CO_2 tension in cell differentiation (*Hydra*)."

28 Aug. E. C. Hammond, "Epidemiological methods in cancer research"; Lalla Iverson, "Incidence of chorioepithelioma in Southeast Asia"; J. Higginson, "Cancer in the South African Bantu"; E. S. Wynne, "Epidemiology of 'cancer eye' in cattle"; H. Innes, "Divergent susceptibilities of animal species to different types of cancer."

29 Aug. Henry Plaine, *chairman*: A. E. Kehr, "Genetic tumors in plants (*Nicotiana*)"; Madge T. Macklin, "Heredity in human cancer"; F. Friedman and L. Burton, "Etiology of tumors in *Drosophila*."

New Hampton School

Physical Metallurgy

John Frye, Jr., *chairman*
Walter R. Hibbard, Jr., *vice chairman*

Microstructures: Their Origin and Influence on Properties

9–13 June. Special techniques: H. Wilsdorf, "Electron microscopy"; R. M. Fisher, "Electron probe analyzer"; R. Gomer, "Emission microscopy"; A. V. Baez, "X-ray microscopy." *Dislocations studies*: W. G. Johnston, "Etch pits"; S. A. Kulin, "X-ray techniques"; D. C. Robinson, "Electron microscopy"; A. R. Lang, "Berg-Barrett techniques." *Precipitation and 2nd phases*: J. Cahn, "Quantitative metallographic techniques"; Jack Washburn, "Precipitation on dislocations"; John Hilliard, "Kinetics of precipitate nucleation and growth"; A. J. Kelly, "Deformation of single crystals of age hardened aluminum alloy"; A. J. Cochart, "Role of second phases in creep." *Deformation and fracture*: J. R. Low and R. W. Guard, "Slip in iron alloys"; Morris Cohen, "Brittle behavior in steel"; Peter Gibbs, "Brittle fracture of crystals"; Jack Gilman, "Dislocations and fracture." *Oxidation and corrosion*: W. D. Forgeng and W. W. Webb, "Crystal growth during oxidation"; Ralph Condit, "Sulfurization of iron"; D. Van Rooyen, "Oxidation nucleation"; V. J. Albano, "Metallic films"; D. Vermilyea, "Oxidation kinetics."

Proteins and Nucleic Acids

Paul Zamecnik, *chairman*
Stanford Moore, *vice chairman*

16–20 June. Structural studies on nucleic acids. Unusual constituents of nucleic acids. The mechanism of synthesis of ribonucleic acid and of deoxyribonucleic acid. The relationship of ribonucleic acid to protein synthesis. Intermediate reactions in protein synthesis. The incorporation of analogues into nucleic acids and proteins. Speakers and discussants: G. Cohen, W. E. Cohn, F. Crick, B. Davis, P. Doty, A. Kornberg, C. Levinthal, F. Lipmann, R. Loftfield, M. Meselson, S. Moore, H. Neurath, S. Ochoa, V. Potter, J. Watson, and P. Zamecnik.

Coal

Alfred R. Powell, *chairman*
Henry C. Howard, *vice chairman*

23 June. Coal tar, W. M. Bywater, discussion leader: E. W. Volkmann, "The structure of coal tar"; R. W. Dornte, "Composition of high-temperature coke oven topped tar and creosote"; N. T. Shideler and F. Whittier, "Pitches and their modifications for special uses"; F. E. Cislak, "Pyridine bases—their characterization."

24 June. Martin B. Neuworth, "The composition of the low-temperature tar neutral oil"; H. R. Batchelder, "Battelle studies on lignite tar." *Coal hydrogenation,* E. E. Donath, discussion leader: F. J. Dent, "The hydrogenation of coal for gaseous hydrocarbons"; R. W. Hiteshue, "High-temperature coal hydrogenation."

25 June. H. R. Linden, "Coal pretreatment and hydrogenation to high-BTU gas"; M. D. Schlesinger, "Low-pressure coal hydrogenation." *Coal gasification,* L. L. Newman, discussion leader: Xavier Duval, "The reactions of carbon with water vapor"; C. G. von Fredersdorff, "Kinetics of fixed-bed and suspension systems of coal gasification."

26 June. W. H. Oppelt, "Considerations in the design of a liquid slag removal system for a pressurized fixed-bed generator"; F. J. Dent, "Experiments on the gasification of coal in fixed-bed pressure gasifiers"; Sabri Ergun, "Tracer techniques in the investigation of the nature of reaction sites"; C. D. Pears, "Process variables and parameters in the underground gasification of coal". *Paths in coal research,* Henry C. Howard, discussion leader.

27 June. H. H. Lowry, Martin B. Neuworth, Irving Wender.

Magnetic Resonance

H. S. Gutowsky, *chairman*
Clyde A. Hutchison, Jr., *vice chairman*

30 June. High resolution nuclear magnetic resonance, Harden M. McConnell, *chairman*: James N. Shoolery, "Interpretation of high resolution NMR spectra and current chemical applications"; H. J. Bernstein, "Methods of high resolution spectral analysis." H. S. Gutowsky, *chairman*: John R. Zimmerman, "Influence of intermolecular interactions on chemical shifts"; J. A. Pople, "The interpretation of proton chemical shifts"; S. Meiboom, "The study of chemical exchange kinetics by NMR."

1 July. Nuclear magnetic relaxation, N. Bloembergen, *chairman*: L. O. Morgan, "Proton spin relaxation by paramagnetic species"; C. A. Reilly, "Proton magnetic relaxation in some aromatic molecules"; D. W. McCall, "Diffusion and relaxation in simple liquids." *Paramagnetic resonance of free radicals,* Clyde A. Hutchison, Jr., *chairman*: George Fraenkel, "Topics in paramagnetic resonance of free radicals"; S. I. Weissman, "Electron exchange effects in electron spin resonance."

2 July. Irradiation-produced free radicals, H. S. Jarrett, *chairman*: Walter Gordy, to be announced; R. K. Waring, to be announced. *Theoretical aspects of magnetic resonance in molecular species,* B. P. Dailey, *chairman*: Martin Karplus, "Theoretical interpretation of electron coupled spin-spin interactions"; Harden M. McConnell, "Relation between magnetic resonance spectra and molecular electronic structure."

3 July. Magnetic resonance in solids, G. E. Pake, *chairman*: John Waugh, "Structure and ionic motions in complex salts"; R. G. Shulman, "NMR in magnetic solids." S. I. Weissman, *chairman*: H. S. Jarrett, "Ferrimagnetic resonance in $NiMnO_3$"; Clyde A. Hutchison, Jr., "Paramagnetic resonance of lanthanides and actinides."

4 July. Recent developments in high-resolution nuclear magnetic resonance instrumentation, E. G. Baker, *chairman*: W. A. Anderson and G. A. Williams, to be announced.

Organic Coatings

E. R. Mueller, *chairman*
D. F. Koenecke, *co-chairman*

7 July. Frederick R. Eirich, "Graft and block polymers"; John C. Cowan, "Vinyl ethers of unsaturated fatty alcohols: promising new protective coating vehicles."

8 July. Ray L. Heinrich and David A.

Berry, "Monocarboxylic aromatic acids in alkyd coatings"; J. K. Craver, "New epoxy resins in surface coatings"; D. W. Caird, "Solution and film forming properties of lexan polycarbonates."

9 July. Raymond R. Myers, "The rheology of film application by rollers"; James H. Taylor, "Application of hydrodynamic theory to the roll mill NIP."

10 July. Samuel Gusman, "A study of factors affecting the adhesion to metal of certain vinyl poylmers"; Elaine Shafrin, "Factors affecting wettability of organic surfaces."

11 July. H. Lacks, "Icephobic coatings."

Organic Reactions and Processes

Charles K. Bradsher, *chairman*
Robert I. Stirton, *vice chairman*

14 July. C. K. Bradsher, introductory remarks; C. D. Marshall, C. W. Smith, B. P. Geyer, G. W. Hearne, S. A. Ballard, H. DeV. Finch, and R. R. Whetstone, "Acrolein chemistry and derivatives"; B. C. McKusick, "Synthesis and chemistry of tetracyanoethylene."

15 July. Discussion on free radicals, Cheves Walling, discussion leader: Cheves Walling, introductory remarks; Frank R. Mayo, "Autoxidation of unsaturated compounds"; Bernhard Raecke, "The rearrangement of salts of aromatic and heterocyclic acids."

16 July. William D. Emmons, "The preparation, reactions, and synthetic applications of oxaziranes"; Nelson J. Leonard, "Amine oxidation"; H. C. Longuet-Higgins, "The molecular orbital theory of conjugated systems."

17 July. J. F. Bunnett, "Nucleophilic aromatic substitution"; P. O. Tawney, A. R. Williams, and R. H. Snyder, "The chemistry of maleimide, N-carbamylmaleimide and derived structures"; Benjamin Phillips, "The synthesis and reactions of aliphatic peracids."

18 July. N. B. Lorette, "The preparation and reactions of simple ketone acetals."

Statistics in Chemistry and Chemical Engineering

Frank Wilcoxon, *chairman*
Richard DeGray, *vice chairman*

21 July. R. Bradley, *chairman*: L. Moses, "Recent developments in ranking methods." M. Terry, *chairman*: W. Kruskal, "Population characteristics related to ranking methods."

22 July. O. L. Davies, *chairman*: D. Frazier, "The analysis of an inter-laboratory study"; J. Mandel, "Intra- and inter-laboratory testing—a general approach." G. E. Box, *chairman*: W. H. Glancy, "Experiences in the comparison of inter-laboratory data."

23 July. R. DeGray, *chairman*: C. M. Mottley, "The application of statistics in scientific investigation." E. Bianco, *chairman*: G. E. Ferris, "Subjective testing in industrial research."

24 July. B. Carpenter, *chairman*: A. Stein, "Uses and misuses of sampling inspection plans." S. M. Free, *chairman*: Harry Smith, Jr., "The simultaneous analyses of multiresponse designs."

25 July. Gertrude Cox, *chairman*: H. O. Hartley, "Application of balanced experimental designs in industry."

Steroids and Related Natural Products

Gilbert Stork, *chairman*
Elias J. Corey, *vice chairman*

28 July–1 Aug. D. H. R. Barton, "Some photochemical transformations in natural products chemistry"; C. Djerassi, to be announced; A. Bowers, to be announced; B. C. L. Weedon, "Some studies on natural polyenes"; A. Eschenmoser, to be announced; K. Wiesuer, "Recent progress in the chemistry of alkaloids"; E. P. Olivetto, "New chemistry of 11-oxygenated steroids"; L. H. Sarett, to be announced; R. B. Woodward, to be announced; W. S. Johnson, "Recent progress in the synthesis of steroids"; Oskar Jeger, to be announced; Josef Fried, to be announced.

Radiation Chemistry

William H. Hamill, *chairman*
Warren M. Garrison, *vice chairman*

4 Aug. H. C. Longuet-Higgins, "Structure and stability of ions"; J. L. Magee, "Charge transfer in gases."

5 Aug. H. M. Rosenstock, "Statistical theory of mass spectra"; Max Wolfsberg, "Theoretical study of mass spectra of alcohols"; D. P. Stevenson, "Survey of bimolecular processes in the mass spectrometer"; J. L. Franklin, "Ion-molecule reactions in the mass spectrometer."

6 Aug. T. H. Anderson, "Effects of irradiation of organic substances at 77°K"; W. Kanzig, "Structure of electron deficient color centers"; P. H. Yuster, "Effects of x-ray irradiation on alkali halide crystals containing impurity ions"; E. H. Taylor, "Effect of radiation on catalytic properties of solids."

7 Aug. M. Magat, "Effects of solutes in organic systems"; R. H. Schuler, "Radiation chemistry of organic systems"; C. D. Wagner, "Some aspects of radiolysis of *n*-paraffins"; R. Bell, "Common features of photo- and radiation-induced addition of chlorine to aromatics."

8 Aug. A. O. Allen, "Kinetics of water radiolysis under heavy particle irradiations"; (speaker to be announced), "Irradiation of aqueous systems."

Analytical Chemistry

Louis Gordon, *chairman*
John Mitchell, Jr., *vice chairman*

11 Aug. Charles N. Reilley, "Chelometric analysis"; Edward J. Griffith, "Thermogravimetry."

12 Aug. H. W. Kirby, "Progress report on radio chemistry in inorganic analysis"; G. Duyckaerts, "Infrared analysis of solids."

13 Aug. Harlan Foster, "Nuclear magnetic resonance"; open discussion.

14 Aug. W. Klyne, "Optical rotatory dispersion"; E. W. Abrahamson, "Analysis of reaction intermediates."

15 Aug. J. B. Neilands, "Enzymatic reactions."

Inorganic Chemistry

H. B. Jonassen, *chairman*
R. W. Mason, *vice chairman*

18–19 Aug. Organometallic complexes of the transition metals, Heinz Sternberg, *chairman*: J. Chatt, "Metal olefin complexes"; G. Ecke, "Recent developments in organomanganese chemistry"; R. P. Eischens, "Infrared spectra of chemisorbed species containing metal-carbon bonds"; H. H. Jaffe, "Nature of the metal-carbon bond"; R. S. Nyholm, "Substituted metal carbonyls"; P. L. Pauson, "Organometallic complexes of the transition metals"; R. E. Rundle, "Structure of organometallic complexes"; M. C. Whiting, "Structure and catalytic properties of some metal carbonyl complexes."

20 Aug. Nonaqueous solvents, Leonard Katzin, *chairman*: Dieter M. Gruen, "Molten salt solutions"; George Watson, "Molten fluorides as high-temperature solvents"; Max T. Rogers, "Interhalogen systems"; Alan F. Clifford, "HF solutions"; C. C. Addison, "Nitrogen oxide systems"; S. Bruckenstein, "Acetic acid systems."

21–22 Aug. Inorganic polymers, Charles Haber, *chairman*: L. F. Audrieth, "Inorganic polymerization reactions"; W. Conard Fernelius, "Semi-inorganic coordination polymers"; (speaker to be announced), "Theoretical consideration in search for inorganic polymer systems."

Chemistry of Adhesion

G. W. Koehn, *chairman*
Alan A. Marra, *vice chairman*

25–29 Aug. H. P. Brown and J. F. Anderson, "Adhesive properties of carboxylic rubbers"; K. R. Williams and H. T. Patterson, "Adhesion of fibers to elastomers"; J. S. Long, "Hydrophyl balance measurements"; B. W. King, "Adhesion of porcelain enamels to metal." *High temperature adhesives*: D. G. Bennett, "Ceramic adhesives"; H. H. Levine, "Triazine compounds"; F. H. Bair, "Other high performance adhesives"; C. A. Dahlquist, "Tack"; Turner Alfrey, "Role of cohesive failure in adhesive bonds"; C. E. Schildknecht, "Advances in graft polymerization"; D. S. Ballantine and D. J. Metz, "Graft polymerization by irradiation"; H. A. Smith, "Preparation and properties of monolayers on active metal surfaces."

Kimball Union Academy

Lipide Metabolism

Warren M. Sperry, *chairman*
Donald B. Zilversmit, *vice chairman*

9 June. Analytical methods, Donald B. Zilversmit, *chairman*: Hermann Schlenk, "Paper chromatography of lipides"; S. R. Lipsky, "The application of gas liquid chromatographic techniques to the analysis of lipide mixtures." *Analytical methods and complex lipides,* William Insull, *chairman*: Norman K. Freeman, "Infrared spectroscopy in lipide analysis"; Herbert Meltzer, "Separation of complex lipides by three phase countercurrent fractionation."

10 June. Analytical methods and sphingolipides, Martin Marcus, *chairman*: Norman Radin, "Sphingolipide metabolism and chromatography"; Maurice M. Rapport, "A serological expedition to the field of sphingolipides"; Samuel Bogoch, "Neuraminic acid in brain ganglioside and in cerebrospinal fluid." *Sphingolipides,* David M. Tennent, *chairman*: J. Folch-Pi, "Study of the brain ganglioside-strandin"; E. Klenk, "Mucoproteins and mucolipides of erythrocytes."

11 June. Sphingolipides, Michael C. Schutz, *chairman*: Eli Robins, "Biochemical changes in developing white matter"; Benjamin Weiss, "Synthesis of sphingosine derivatives"; Roy Gigg and Herbert E. Carter, "The chemistry of sphingolipides." *Biosynthesis of sphingolipides,* Leon Swell, *chairman*: Jonathan B. Wittenberg, "Sphingosine biogenesis"; Roscoe O. Brady, "The enzymatic synthesis of glycosphingolipides."

12 June. Biosynthesis of sphingolipides, sterols, and fatty acids, H. C. Meng, *chairman*: Irving Zabin, "Biosynthesis of sphingolipides"; George Alexander and Erwin Schwenk, "New experiments on the biosynthesis of sterols"; Marvin D. Siperstein, "The nature of the lipogenic defect in diabetes." *Biosynthesis of fatty acids,* Clyde T. Caldwell, *chairman*: D. E. Green, D. M. Gibson, S. J. Wakil, and E. Titchener, "The reconstruction of the fatty acid synthesis system of pigeon liver"; F. Lynen, "Biosynthesis of fatty acids by purified enzymes."

13 June. Biosynthesis of phosphatides and triglycerides, Alex Lesuk, *chairman*: K. P. Strickland and R. J. Rossiter, "Biogenesis of phosphatides and triglycerides"; E. P. Kennedy, "The enzymatic synthesis of complex lipides."

Cell Structure and Metabolism

Montrose J. Moses, *chairman*

The Muscle Cell

16 June. Definitive aspects: H. Ruska and C. A. Edwards, "Comparative structure and organization of the muscle cell"; S. V. Perry, "Chemical organization of muscle cells"; D. Wilkie, "Physiological parameters of muscle cell function"; A. Sandow, discussion leader.

17 June. Membrane limited structures of the muscle cell: G. Palade, "Fine structure of the sarcosomes"; E. G. Slater, "Biochemistry of the sarcosomes"; K. R. Porter, "The sarcoplasmic reticulum."

18 June. Contraction: A. Huxley, "Light microscopic observations on contracting muscle"; S. Inoué, "Polarized light studies of muscle contraction"; A. J. Hodge, "Changes in fine structure associated with contraction. A review of recent concepts"; A. G. Szent-Gyorgyi, discussion leader. J. Gergely, "Myosin and actomyosin: reality or artifact?"; H. Holtzer and J. Marshall, "Localization of muscle proteins."

19 June. Contraction: T. Hayashi, "Model contraction systems"; W. F. H. M. Mommaerts, "Energy supplying systems and contraction"; A. Csapo, "Possible link between intact muscle and models"; discussion; Ł. Lorand, "Relaxing factors."

20 June. Neuromuscular relationships: R. Couteaux, "Cytochemistry and morphology of the subneuronal apparatus"; J. del Castillo, "Physiological function of the motor end plates"; R. J. Barrnett, discussion.

Nuclear Chemistry

John R. Huizenga, *chairman*
Morris L. Perlman, *vice chairman*

23–27 June. Nuclear spectroscopy, application of the shell and unified nuclear models in the interpretation of experimental results. Coulomb excitation. Photonuclear reactions, dependence of the cross section for formation of an excited nucleus by gamma-ray absorption on nuclear deformation. Heavy ion reactions. Discussion of Γ_n *and* Γ_f *as function of energy, atomic weight, and number. Hot atom chemistry. Chemical techniques. Geochemistry including cosmic abundances and synthesis of the elements.* Speakers and detailed program to be announced.

Solid State Studies in Ceramics

M. L. Kronberg, *chairman*
William D. Kingery, *vice chairman*

High Temperature and High Pressure Phenomena

30 June–4 July. P. W. Gilles, "Vapor species above solids—particularly oxides"; A. J. Thorn, discussion. R. E. Carter, "Determination of dissociation pressures of oxides by use of galvanic cells"; S. L. Blum, discussion. A. Muan, "Equilibria among gas, liquid and crystalline phases in oxide systems involving changes in oxidation states"; T. B. King, "Water solubility and oxygen diffusion in molten silicates." C. E. Birchenall, J. E. Burke and G. C. Kuczynski, in a comprehensive discussion of "The current status and trends in the fields of diffusion and sintering." R. Roy, "Crystal chemical observations on high pressure phase relationships"; G. C. Kennedy, discussion. H. T. Hall, "Some recent developments in high pressure chemistry"; S. Zerfoss, discussion. R. Chang, "Creep of ceramic oxides at high temperatures and low stresses"; J. A. Pask, discussion. D. T. Griggs, "Some mechanical properties of minerals at high temperatures and high stresses"; M. L. Kronberg, discussion. S. P. Mitoff, "Electrical conductivity of single crystals of magnesium oxide at elevated temperatures." W. B. Crandall, "Unsteady-state heat transfer at elevated temperatures"; W. D. Kingery, discussion. R. B. Sosman, guest lecture, "A scientific-technologic survey of eating places." A number of scientists from abroad will attend and will report on current research in their respective institutions. They are: H. J. Oel, J. White, E. W. Gorter, A. L. Roberts, K. Hauffe, P. Murray or D. Livey, R. Lindner, and K. Torkar.

Chemistry and Physics of Isotopes

Russell Baldock, *chairman*
Ralph Weston, *vice chairman*

7–11 July. Natural abundance of isotopes (geological and biological significance). Theoretical aspects of kinetic isotope effects. Applications of kinetic isotope effects to reaction mechanisms. Solvent properties of heavy water. Isotope separation (emphasis on chemical exchange). Isotopes in geology. Some new applications in mass spectrometry. Brief progress reports on current research activities.

Chemistry, Physiology and Structure of Bones and Teeth

D. Dziewiatkowski, *chairman*
Wallace D. Armstrong, *vice chairman*

14 July. Elaboration of the inorganic structures in bones and teeth, Reidar F. Sognnaes, *chairman*: J. T. Albright and R. F. Sognnaes, "Fine structure of the inorganic elements in adult bones and teeth"; S. F. Jackson, "Structural relationship between inorganic and organic elements in embryonic bone." Baird Hastings, *chairman*: Honor B. Fell, "The study of skeletal physiology by the organ culture method."

15 July. Physics of the solid state, John H. Marshall, *chairman*: N. H. Nachtrieb, "Dynamics of the solid state"; W. F. Neuman, "The bone crystal"; A. S. Posner, discussion. Karl Meyer, *chairman*: Harry Bostrom, "Aspects of the metabolism of mucopolysaccharides."

16 July. Enzymes of bone, Alexander B. Gutman, *chairman*: P. Robbins and F. D'Abramo, "Active sulfate and the

NOW available from stock!

MEVALONIC ACID C^{14}

As N, N^1 — Dibenzyl Ethylenediamine Salt
Exhibits Full Microbiological Activity
(Method of Skeggs, et al.; J. Bact., Vol. 72, 519; 1956)

ALSO OTHER

BIOCHEMICAL TRACERS

- Amino Acids
- Purines
- Intermediates
- Krebs Cycle Compounds
- Steroids

Labeled with H^2, H^3, C^{14}, D^{32}, I^{131}, Etc.

manufactured by
Mucor ISOTOPES SPECIALTIES COMPANY INC.
a subsidiary of **nuclear corporation of america**

SALES OFFICES

Isotopes Specialties Co., Inc.
Box 688
Burbank, California

Nuclear Consultants, Inc.
400 Park Avenue
New York 17, New York

Nuclear Corp. of America Mid-America Sales Division
9842 Manchester Road, St. Louis 19, Missouri

Dajac LABORATORIES

OVER 150 NEW REAGENTS FOR MEDICAL RESEARCH AND BIOCHEMICAL TESTING

Compound	Use
Acetyl Choline Chloride	Acetyl choline esterase
p-Bromomandelic Acid	Zirconium
p-Bromoaniline	Pentose detection
Benzidine (purified)	Peroxidase
2-Hydroxy-3-Naphthaldehyde	Protein bound amino groups
AET Hydrobromide (2-amino-ethyl isothiouronium)	Antiradiation
Beta-Naphthyl Acetate, and 6-Bromo-2-Naphthyl acetate	Acetyl choline esterase
Sodium-6-Benzoyl-2-naphthyl phosphate	Phosphatase
2-(4-Hydroxybenzeneazo) benzoic acid	Albumin in blood plasma
Carbonaphthoxy choline iodide	Serum choline esterase
6-Bromo-2-naphthyl-beta-D-glucuronide	Beta-glucuronidase
Indoxyl acetate	Esterase and acetyl choline esterase
N-Benzoyl-dl-phenylalanine beta naphthol ester	Chymotrypsin
L-Leucyl-beta-naphthylamide hydrochloride	Leucine amino peptidase
Reinecke Salt	Choline
Thioacetamide	Precipitant for metal ions
Neutral Buffered formaldehyde solution	Fixation
5-Nitrobenzotriazole	Nitroreductase
Myristoyl choline chloride	Choline esterase
2,4,7-Trinitrofluorenone	Polynuclear complexes
2,3,5-Triphenyltetrazolium chloride	Reducing enzymes, carbohydrates

Custom Syntheses Invited

The Borden Company
5000 Langdon Street
P.O. Box 9522
Philadelphia 24, Pa.

THE Borden COMPANY
CHEMICAL DIVISION

Fast Accurate Weighing – Corrosion-Resistant – Economical

Welch TRIPLE-BEAM BALANCE

With Stainless Steel Beam And Pan



No. 4030

Capacity 111 grams
(201 grams using auxiliary weight)

SENSITIVE TO 0.01 grams or less

- **Hard, Cobalite Knife Edges**
- **Grooved Agate Bearings**
- *Patented One-Piece Beam*
- *Stainless Steel Pan with Retaining Rim*
- *Three Scales Easily Read at Eye-Level*
- *Extra Weights Nested in Base*
- *Silver-Gray Hammerloid Finish*

4030. TRIPLE-BEAM BALANCE, High Form. The balance is 13 inches long and 11 inches high. The pan is 4 inches in diameter and removable, and the hanger is 10½ inches high. Each, $27.50

4031. AUXILIARY WEIGHT. For use on the 100-gram notch of No. 4030 Balance to increase weighing capacity from 111 grams to 201 grams. This weight is matched to the balance with which it is to be used and should be ordered at the same time as the balance. Each, $1.50

4030C. PLASTIC COVER, For No. 4030. Each, $1.60

W. M. WELCH SCIENTIFIC COMPANY
DIVISION OF W. M. WELCH MANUFACTURING COMPANY
ESTABLISHED 1880
1515 Sedgwick Street, Dept. E, Chicago 10, Illinois, U.S.A.
Manufacturers of Scientific Instruments and Laboratory Apparatus

synthesis of chondroitin sulfate"; H. F. DeLuca, "Vitamin D and citrate metabolism." Franklin C. McLean, *chairman*: Nicolay Eeg-Larsen, "Glycolysis in epiphyseal cartilage."

17 July. Chemistry and physiology of the parathyroid hormone, John E. Howard, *chairman*: H. Rasmussen, "Studies on the isolation of the parathyroid hormone"; C. Rich, M. Horwith, D. Thompson, and H. Rasmussen, "Physiological effects of purified parathyroid hormone in humans." E. C. Reifenstein, Jr., *chairman*: E. Kodicek, "Metabolism of vitamin D."

18 July. Current research trends, Wallace D. Armstrong, *chairman*: contributed short papers, to be selected.

Chemistry at Interfaces

Stephen Brunauer, *chairman*
Norman Hackerman, *vice chairman*

21 July. Chemical reactions at interfaces, Herman E. Ries, Jr., *chairman*: E. A. Gulbransen, "Structural aspects of reactions at solid-gas interfaces"; Alexandre Rothen, "Studies of enzymatic reactions at a solid-liquid interface"; J. H. Schulman, "Selective interaction of sodium and potassium ions with surface active agents at solid-liquid and liquid-liquid interfaces."

22 July. Electrical phenomena at interfaces, H. van Olphen, *chairman*: Pasupati Mukerjee, "Some interactions of amphipathic ions in aqueous solutions"; D. T. Rogers, "Tribo-electric properties of distillate fuels"; David C. Grahame, "Factors affecting the adsorption of ions at interfaces."

23 July. Adsorption, L. E. Copeland, *chairman*: A. C. Zettlemoyer, "Chemisorption on metals"; Fred Karush, "Adsorption of small molecules by proteins"; G. M. Schwab, "Chemisorption and catalysis."

24 July. Interfaces in dispersed systems, A. J. G. Allan, *chairman*: R. K. Iler, "Recent developments in the surface chemistry of silica and silicates"; C. R. Singleterry, "Detergents in organic media"; R. D. Vold, "Packing and ionization of layers of sodium dodecyl sulphate adsorbed on carbon particles"; A. M. Gaudin, "Induced hydrophobicity in minerals."

25 July. General discussion.

High-Pressure Research

J. M. Lupton, *chairman*

28 July. High-pressure synthesis, C. M. Sliepcevich, *chairman*: H. Tracy Hall, "High-pressure, high-temperature developments"; C. Walling, "Organic reactions at high pressures." *Transport properties,* A. Michels, *chairman*: John Ross, "Transport processes in dense gases"; R. B. Dow, "Rheological properties at high pressures."

29 July. Measurement, correlation, and utilization of pressure, volume, and temperature data, W. C. Edmister, *chairman*: V. J. Berry, "Effects of pressure, temperature, and composition on the behavior of a gas condensate system"; A. Bondi, "A corresponding-states correlation without critical constants—application to the PVT properties of higher molecular weight hydrocarbons"; L. N. Canjar, "Treatment and correlation of light hydrocarbon PVT data"; J. B. Opfell, "Some limitations on applications of equations of states."

30 July. Solid state, H. G. Drickamer, *chairman*: H. Brooks, "Review of recent work on the effects of pressure on semiconductors"; W. B. Daniels and Charles S. Smith, "Single-crystal elastic constants to 10,000 atmospheres." *Optical properties,* A. W. Lawson, *chairman*: H. G. Drickamer, "Optical studies on the structure of solids"; B. Vodar, "Recent results on atomic and molecular spectra of compressed gases."

31 July. Geophysics, G. A. MacDonald, *chairman*: A. F. Birch, "Application of high-pressure research to problems in geophysics." *Molecular physics,* J. M. Lupton, *chairman*: A. Michels, "Some conclusions on interactions from recent high-pressure experiments."

1 Aug. Geochemistry, J. R. Gold-

ELEMENTARY PARTICLE ACCELERATORS
IN ENGLISH TRANSLATION

Supplement 4, 1957 Soviet Journal of Atomic Energy

Eight papers by 20 leading Soviet physicists, presented at the Session on Elementary Particle Accelerators at the All Union Conference on the Physics of High-Energy Particles, Moscow, May 1956. Of great value in work with cyclic or linear elementary particle accelerators. Contents: Physical Design Principles of the 10-Bev Proton Synchrotron; Magnetic Characteristics of the 10-Bev Protron Synchrotron at the Joint Inst. for Nuclear Research; Certain Features of High-Energy Cyclic Electron Accelerators; The Sector Cyclotron; Incoherent Electron Radiation in the Synchrotron and Its Applications in Studying Accelerator Operation; Features of the 280-Mev Synchrotron at the Inst. of Physics, Acad. Sciences, USSR; Experimental Basis for the Theory of Particle Capture in Betatron Acceleration; Concerning the Theory of Particle-Beam Focusing in a Linear Accelerator by a System of Transverse Lenses.
English translation, 75 pages, **$15.00**

***Special price to subscribers to our translation of the 1957 Soviet Journal of Atomic Energy:* only $10.00**

Now available: 1957 Issues 1–9, Soviet Journal of Atomic Energy

THE PHYSICS OF FISSION—Supplement No. 1. Published Oct. 1957. 12 papers, comprising 209 pp, presented at this Conference, Jan. 1956, at the Inst. of Atomic Energy, Acad. Sciences, USSR. Reviews most important theoretical and experimental problems.
English translation, **$30.00**

THE THEORY OF THERMAL-NEUTRON NUCLEAR REACTORS—Supplement No. 2–3. Published Jan. 1958. Textbook and handbook for design and operation of reactors, both power and experimental types.
English translation, 339 pp, 16 pg appendix, 2 parts, **$60.00**

Consultants Bureau's translations by *bilingual physicists.* Books staple bound in durable paper covers; text, which includes all integral diagrammatic and tabular material, is clearly reproduced by multilith process from IBM "cold type." **For free catalogs describing C.B.'s current Russian translation-publishing program, write to Dept. S.**

CONSULTANTS BUREAU, INC.
227 WEST 17th STREET, NEW YORK 11, N.Y.—U.S.A.
Telephone: ALgonquin 5-0713 • Cable Address: CONBUREAU, NEW YORK

LOURDES is pleased to announce the following NEW PRODUCTS

★ CONTINUOUS FLOW SUPER-SPEED CENTRIFUGE ROTORS (Pat. App'd For)

This new design angle type superspeed centrifuge rotor offers continuous forces up to 35,000 x gravity. The inside of the rotor is hollowed out with angled walls sloping downward to accommodate a polyethylene bag of similar shape. A stainless steel cover screws onto the rotor for sealing purposes.

Materials to be centrifuged are introduced from a central inlet tube and the lighter mediums are continually discharged into a surrounding stainless steel collector by means of a unique discharge cap which is attached to and turns with the cover. Heavier particles are forced downward as they impinge on the angular wall. This same rotor may be used for batch separation by use of a threaded sealing plug in the cover.

By simply replacing the polyethylene bag liner the rotor is ready for a new run or for continued operation. There is no need for rotor removal, rotor cleaning, or for handling of test tubes with sealing caps and individual lines to both inlet and outlet ports.

The considerable distance between the inlet tube and the ports of the outlet cap allows for faster and better separation. If inlet and outlet ports were close to each other, materials introduced would be discharged in almost the same form unless the rate of flow were very slow. Available in two sizes, these rotors offer high speed and force and greater capacity than any other super-speed continuous flow centrifuge.

★ FULLY AUTOMATIC SUPER-SPEED CENTRIFUGES

- FULLY AUTOMATIC ROTOR ACCELERATION
- ROTOR UNBALANCE ELECTRICAL SAFETY TRIP
- REMOVABLE PANEL FOR REMOTE CONTROL
- ACCOMMODATES ALL LOURDES' ROTORS INCLUDING CONTINUOUS FLOW
- PUSH BUTTON DYNAMIC BRAKING
- COMPLETE INSTRUMENTATION INCLUDING ELECTRIC TACHOMETER & TIMER
- COMPLETE SAFETY CONTROLS INCLUDING FORCED RESET RELAY
- HEAVY DUTY VENTILATED STEEL SAFETY TANK

★ THREE LITER CAPACITY ROTOR—SUPER-SPEED

As a follow up to the popular VRA rotor (1500 Ml.) this new rotor machined from a radial grained duralumin forging has six compartments for 500 ml bottles. It is the first rotor of its type which will spin such large capacity at forces exceeding 10,000 x gravity.

★ LARGE CAPACITY HOMOGENIZER

Similar in design to the small Multi-Mixer but with a higher horsepower motor for homogenizing within larger containers.

These new products plus the new design Model LR refrigerated centrifuge (pat. applied for) and other LOURDES' products will be displayed this spring at many of the forthcoming society meetings. Further details will be promptly furnished upon request.

LOURDES instrument corp.

53rd Street & 1st Avenue., Brooklyn 32, New York

BALANCE REPAIRS

We can now offer the same service on BALANCE REPAIRS and maintenance that we have been doing on microscopes.

Prompt service (48 hrs.)
Guaranteed work by factory trained men.

Loan instruments.

MONROE MICROSCOPE SERVICE

P.O. Box 656
Rochester 2, N.Y.

NEW SMALL SOURCE Ultra-Violet

pencil type lamp
3/8" in diameter, 4-6" in length

8 models, ideal for far U.V. examination of small areas.

High intensity, suitable for collimator use and laboratory instrumentation applications.

Also, complete line of near and far ultra-violet lamps 4-100 watts available in various sizes and models.

For specific information please write: dept. S-1

ULTRA-VIOLET PRODUCTS Inc.
San Gabriel, California

smith, *chairman*: G. C. Kennedy, Rustum Roy, "Application of high-pressure research to problems in geochemistry."

Toxicology and Safety Evaluations

John A. Zapp, Jr., *chairman*
Don D. Irish, *vice chairman*

4 Aug. The laboratory animal in toxicity studies, Margaret Ives, *chairman*: L. Royal Christensen, "The endemic disease pattern in experimental animals"; C. N. Wentworth Cumming, "The care and nurture of laboratory animals." *The laboratory animal in toxicity studies,* O. G. Fitzhugh, *chairman*: Lloyd W. Hazleton and Bernard L. Oser, "The choice of animals as related to the interpretation of toxicity studies."

5 Aug. Statistical methods in toxicology, Carrol S. Weil, *chairman*: Jerome Cornfield, "Biometric approach to the planning and analysis of toxicity studies." *Estimation of hazards for man,* David W. Fassett, *chairman*: Hardin B. Jones, "Extension of laboratory and other data to populations."

6 Aug. Health hazards of nuclear reactors, Norton Nelson, *chairman*: Charles R. Williams, "The public heath aspect of nuclear reactors." *Metabolic and biochemical investigations in toxicity evaluations,* Arnold J. Lehman, *chairman*: F. A. Denz, to be announced.

7 Aug. Air pollution toxicology, Eugene R. Krackow, *chairman*: Herbert E. Stokinger, "Experimental evaluation of the toxicity of air pollutants"; Geoffrey Carey, "Clinical approach to the toxicity of air pollutants." *The role of judgment in toxicological research,* Don D. Irish, *chairman*: Maurice H. Seevers, "Horse sense in collecting and interpreting toxicological data."

8 Aug. Training of toxicologists, a panel discussion; Henry F. Smyth, Jr.; *chairman*: Henry F. Smyth, Jr., "The work and responsibilities of a toxicologist"; Elliott A. Maynard, "Past and current training of toxicologists"; E. M. K. Geiling, "Appropriate future training of toxicologists."

Chemistry and Physics of Metals

J. A. Krumhansl, *chairman*
E. I. Salkovitz and J. W. McClure, *vice chairmen*

11 Aug. Electronic structure—general: J. C. Slater, "Electron energy bands in metals"; A. F. Kip, "Cyclotron resonance"; D. H. Tomboulian, "Soft x-ray valence band emission studies."

12 Aug. Specific band determinations: G. Lehman, "Band structure of uranium and thorium"; J. R. Reitz, "Band structure of selenium and tellurium"; J. W. McClure, "Band structure of graphite." *Liquid metals*: S. Strauss, "Size effects in liquid alloys."

13 Aug. Transport properties: E. I. Salkovitz, "Transport properties in dilute alloys"; T. G. Berlincourt, "Hall

effect in metals and alloys"; A. I. Schindler, "Band dependent properties in transition metal alloys." *Elastic properties of metals and alloys*: J. R. Reitz, "Elastic constants of metals and alloys and electronic structure."

14 Aug. Point defects and electronic properties: T. J. Rowland, "Nuclear magnetic resonance in copper and silver alloys"; W. Harrison, "Influence of lattice disturbances on point defect scattering"; L. Roth, "Scattering of Bloch waves"; F. J. Blatt, "Thermoelectric power of noble metal alloys."

15 Aug. Special topics: L. Apker, "Recent progress in photoelectric emission"; H. Brooks, recapitulation.

Infrared Spectroscopy

F. A. Miller, *chairman*
V. Z. Williams, *vice chairman*

18 Aug. Spectra of trapped species, B. Crawford, Jr., *chairman*: J. A. A. Ketelaar, "Infrared spectra of crystalline solid solutions"; G. C. Pimentel, "Matrix methods." *Infrared spectra of adsorbed molecules*: A. Terenin, "Infrared spectra of molecules adsorbed on solid surfaces"; William A. Pliskin and R. P. Eischens, "The infrared spectra of carboxylic acids chemisorbed on metals and metal oxides."

19 Aug. Measurement of vibrational relaxation times, G. C. Pimentel, *chairman*: K. E. Shuler, "Theoretical aspects"; S. H. Bauer, "Experimental aspects." *Detectors for the infrared region*: E. F. Daly, "Infrared detectors."

20 Aug. Infrared intensities, D. A. Ramsay, *chairman*: D. F. Eggers, Jr., "Infrared intensities from band area measurements"; J. H. Jaffe, "Infrared intensities from dispersion measurements." *Raman intensities*: M. V. Volkenstein, "Theoretical aspects"; L. A. Woodward, "Experimental aspects."

21 Aug. The origin of group frequency shifts, V. Z. Williams, *chairman*: D. H. Whiffen, "Physical effects"; L. J. Bellamy, "Chemical effects." *Group intensities*: R. N. Jones, "Infrared intensities in liquid and solution phases."

22 Aug. F. A. Miller, *chairman*: L. J. Bellamy, B. Crawford, Jr., J. A. A. Ketelaar, R. C. Lord, H. W. Thompson, and N. Wright, "Infrared: its present needs and future directions," panel discussion.

Glass

James E. Archer, *chairman*
R. J. Charles, *vice chairman*

Physicochemical Aspects of Glass

25 Aug. General introduction: R. W. Douglas, "Transport phenomena in glasses"; (speaker to be announced), "Thermodynamic considerations of glasses and slags."

26 Aug. J. Uys, "Water in silicate melts"; panel presentation, "Room temperature reactivity of glasses."

Cary / instrument abstracts

Applied Physics Corporation/Pasadena/California

For Ultraviolet-Visible Spectrophotometry

The Cary Model 11 provides performance comparable to the finest; cost comparable to the cheapest.



Considering the purchase of a recording spectrophotometer? The following comments may help you get much more for your money.

Most spectrophotometer users regard the Cary Model 14, with its 1860 Å to 2.6 mu wavelength as the finest recording spectrophotometer available. We have been surprised to discover that quite a few people do not realize that the Model 14 has a companion instrument—the Cary Model 11—which gives the same high quality of the Model 14 at a cost comparable to the lowest-price recording spectrophotometer. The difference between the Model 11 and the Model 14 is in wavelength range. Of course, where the wider wavelength range is required, the Model 14 *is* the finest instrument available. However, for applications in the ultraviolet and visible ranges (2100 Å to 8000 Å) the Cary Model 11 provides the same high degree of accuracy, ruggedness, and dependability as the Model 14, as well as its convenience and flexibility, including linear wavelength recording, speed of scanning, accessories, etc. Important performance data on the Cary Model 11 are outlined below.

Stray Light: Less than 0.0001% over most of the range.
Scanning Speeds: 1.0 Å per second (ultraviolet region) to 125 Å per second (visible region).
Resolution: 1.0 Å or better throughout most of the range.
Wavelength Accuracy: Better than 5.0 Å in the ultraviolet region and better than 10.0 Å in the visible region. *Reproducibility:* Better than 0.5 Å in the ultraviolet and 3.0 Å in the visible region.
Photometric Reproducibility: Reproducibility better than .004 in absorbance can be achieved with the Model 11.

20,000 HOURS OF SERVICE WITHOUT MAJOR REPAIRS

The first Cary Model 11 was produced in 1947, and since then nearly every leading analytical laboratory in the United States—and many abroad—has acquired one or more Model 11's. The performance, flexibility and reliability of the Model 11 have been proved in all kinds of research and control applications.

One of the first instruments to be manufactured—Serial No. 2—was recently overhauled at the factory after having been in use twelve hours per day for over six years without requiring any service other than routine maintenance. This instrument has now begun a second stint of reliable service which will undoubtedly run into additional thousands of hours.

FREE BULLETIN

If your spectrophotometer applications are in the visible or ultraviolet range, investigate the many advantages of the Cary Model 11. For complete information write to Applied Physics Corporation, 362 West Colorado Street, Pasadena 1, California, for Bulletin E338

SCHAAR *introduces...*

the NEW

Lab-Asco-Vac 10

MECHANICAL HIGH VACUUM PUMP

Free Air Displacement 50 Liters Per Minute

Guaranteed Absolute Pressure 0.1 Micron



This high vacuum laboratory pump presents a completely unique concept of pumping standards. Here are some of the most desirable features:



Insulation and rubber mounting eliminate noise; radical vertical design eliminates conventional, hazardous belt and pulley. Carrying handle on the supermount provides easy portability. Supplementing the low purchase price, this pump requires a much smaller volume of oil charge, with maintenance and cleaning operations simplified. The vertical design has made the pump leak-proof, and with the visible oil level cup, oil spillage is confined to a minimum. In filling the pump, oil is not introduced at the point of discharge, thereby eliminating the need for pump disconnect. The Lab-Asco-Vac Pump runs cooler and has a unique capillary gas ballast cleaner which provides efficient operation for longer periods.

SPECIFICATIONS

Cat. No.	SR-4492*
Model	Two-Stage
Guaranteed Absolute Pressure	0.1 Micron
Pumping (displacement) Speed	50 liters/minute
Operating Speed	1140 rpm
Oil Charge Required	1 pint
Dimensions	12" diam. x 20½" H.
Weight	45 lbs.
Voltage	110/220
Cycles	50/60
PRICE	**195.00**

*Mounted on rubber-cushioned cast base and supplied complete with electrical cord, switch and plug, one quart of Lab-Asco-Vac pump oil, operating and maintenance bulletin.

Additional Literature Available on Request

SCHAAR *and Company*

7300 W. MONTROSE AVE. . . . CHICAGO 34, ILLINOIS

GLASS ABSORPTION CELLS made by *KLETT*



Makers of Complete Electrophoresus Apparatus

SCIENTIFIC APPARATUS

Klett-Summerson Photoelectric Colorimeters—Colorimeters — Nephelometers — Fluorimeters—Bio-Colorimeters — Comparators — Glass Standards—Klett Reagents.

Klett Manufacturing Co.

179 East 87 Street, New York, New York

Old-Fashioned BOTTLE-POURING STILL IN VOGUE IN YOUR LABORATORY ?

SOLVE DISPENSING PROBLEMS WITH THE CORINTH *Finger-Tip* FLUID DISPENSER*

L-9500—complete with Pyrex Brand Glass nozzle, vial shield and Tygon R-3603 delivery tubing $17.50

* PATENT PENDING

PALO **LABORATORY SUPPLIES, Inc.**
81 Reade Street, New York 7, N. Y.

27 Aug. J. Gibbs, "Nature of the glass transition in linear polymers"; W. Hillig, "Kinetic stability of the glassy state."

28 Aug. S. W. Barber, "Dispersion of acoustic waves at low temperature in binary alkali silica glass and its relation to other mechanical properties"; R. J. Charles, "Effect of temperature and atmosphere on the corrosion fatigue of lime glass."

29 Aug. Summary discussion; overflow papers; business meeting.

W. GEORGE PARKS
Department of Chemistry, University of Rhode Island, Kingston

Society Elections

■ The Radiological Society: pres. and AAAS Council representative, Leo G. Rigler, Cedars of Lebanon Hospital, Los Angeles, Calif.; pres.-elect, Laurence L. Robbins, Massachusetts General Hospital, Boston; historian, Howard P. Doub, Henry Ford Hospital, Detroit, Mich.; sec.-treas., Donald S. Childs, 713 E. Genesee Street, Syracuse, N.Y. The vice-presidents are Robert D. Moreton, Fort Worth, Tex., James W. J. Carpenter, Chicago, Ill., and Everett L. Pirkey, Louisville, Ky.

■ Institute of Mathematical Statistics: pres., L. J. Savage, Eckhart Hall, University of Chicago; pres.-elect., Jacob Wolfowitz, Department of Mathematics, Cornell University (after late May 1958); sec., George E. Nicholson, Jr., Department of Statistics, University of North Carolina, Chapel Hill, N.C.; treas., A. H. Bowker, Department of Statistics, Sequoia Hall, Stanford, Calif. The representative to the AAAS is Harold Hotelling, Institute of Statistics, University of North Carolina.

■ American Academy for Cerebral Palsy: pres., William T. Green; pres.-elect, Robert A. Knight; treas., Samuel B. Thompson; sec., Raymond R. Rembolt, University Hospital, Iowa City, Iowa.

■ Optical Society of America: pres., Irvine C. Gardner; pres.-elect, John Strong; junior past pres., Ralph A. Sawyer; v. pres. for meetings, Stanley S. Ballard; sec., Kasson S. Gibson, National Bureau of Standards, Washington 25, D.C.; treas., E. D. McAlister; sec. for local sections, W. Lewis Hyde. The representative to the AAAS Council is C. C. Kiess, National Bureau of Standards, Washington, D.C.

■ American Mathematical Society: pres., Richard Brauer, Department of Mathematics, Harvard University; pres.-elect, E. J. McShane, University of Virginia; sec., John W. Green, Department of Mathematics, University of California, Los Angeles 24, Calif.; treas., Albert L. Meder, Jr., New York, N.Y. The vice presidents are Garrett Birkhoff, Harvard University, and Salomon Bochner and N. E. Steenrod, Princeton University. The representative to the AAAS Council is W. L. Duren, University of Virginia.

Forthcoming Events

March

31–2. Utilization of Atomic Energy, College Station, Tex. (R. E. Wainerdi, A.&M. College of Texas, College Station, Tex.)

April

1. Microcirculatory Conf., 5th, Buffalo, N.Y. (S. R. M. Reynolds, Dept. of Anatomy, Univ. of Illinois College of Medicine, 1853 W. Polk St., Chicago 12.)

1–2. Alabama Acad. of Science, annual. Birmingham. (H. M. Kaylor, Dept. of Physics, Birmingham-Southern College, Birmingham.)

1–2. Freezing and Drying Symp., 2nd Internatl., London, England. (L. G. Beckett, Institute of Biology, 41 Queen's Gate, London, S.W.7.)

1–3. Corrosion Control, 5th annual conf., Norman, Okla. (M. L. Powers, Extension Div., Univ. of Oklahoma, Norman.)

TRANSAMINASE DETERMINATION
(serum glutamic oxalacetic transaminase)
Now included in
HYLAND CLINICAL
CHEMISTRY CONTROL SERUM

Prepared only from freshly drawn human blood, Hyland Clinical Chemistry Control Serum provides the ideal control, since it is a *natural* reference standard with essentially the same composition as specimens under test. When run in parallel with your determinations on unknowns, there is nothing more dependable as a day-by-day check on instruments, reagents and techniques.

To assure accuracy, each production lot is assayed by three independent laboratories. Mean values and *acceptable range* for 13 components listed below (those found to be consistently reproducible and stable) are charted for each lot.

Calcium	Non-Protein Nitrogen	Sodium
Chloride	Phosphorus, inorganic	Total Protein
Cholesterol	Potassium	Transaminase (SGO-T)
Creatinine	Protein-bound Iodine	Urea Nitrogen
		Uric Acid

Simply add distilled water to prepare Hyland control standard for use. Reconstituted standard remains stable for *five days* when stored under refrigeration.

For "No Guesswork" Blood Chemistry Determinations —Specify Hyland Clinical Chemistry Control Serum (dried). Available in 5 cc. vials, 6 vials per box.

HYLAND

HYLAND LABORATORIES
4501 Colorado Boulevard, Los Angeles 39, California
252 Hawthorne Avenue, Yonkers, New York

2–4. American Assoc. of Anatomists, annual, Buffalo, N.Y. (L. B. Flexner, Dept. of Anatomy, School of Medicine, Univ. of Pennsylvania, Philadelphia 4.)

2–4. Instruments and Regulators Conf., Newark, Del. (W. E. Vannah, Control Engineering, 330 W. 42 St., New York 36.)

3–5. Pennsylvania Acad. of Science, annual, Easton, Pa. (G. R. Stevens, Dept. of Geology and Geography, Lafayette College, Easton.)

4–5. Southern Soc. for Philosophy and Psychology, annual, Nashville, Tenn. (W. B. Webb, U.S. Naval School of Aviation Medicine, Pensacola, Fla.)

7–11. American Assoc. of Cereal Chemists, annual, Cincinnati, Ohio. (J. W. Pence, Western Utilization Research Laboratories, Albany, Calif.)

8–10. Electronic Waveguides Symp., New York. (J. Fox, Microwave Research Inst., Polytechnic Inst. of Brooklyn, 55 Johnson St., Brooklyn 1, N.Y.)

9–12. National Council of Teachers of Mathematics, Cleveland, Ohio. (M. H. Ahrendt, NCTM, 1201 16 St., NW, Washington 6.)

9–14. Applied Psychology, 13th internatl. cong., Rome, Italy. (L. Meschieri, National Inst. of Psychology, Rome.)

10–11. American Inst. of Chemists, annual, Los Angeles, Calif. (L. Van Doren, AIC, 60 E. 42 St., New York 17.)

Packard

AUTOMATIC FRACTION COLLECTOR

Model 230



FOR COLUMN CHROMATOGRAPHY...

Both Time and Drop Counting Operation

Model 230 Automatic Fraction Collector utilizes the accurate drop-counting method of fraction cutting to provide precise volume measurement and clean separations.

Mixing, contamination and evaporation are precluded by avoiding the use of intermediate collecting vessels, glass arms and funnels. Drops are counted as they fall from the column directly into the collecting tubes.

Ease of operation and a high degree of reliability have been attained by not using complicated mechanisms or complex indexing systems. The overall result is high quality performance at moderate cost.



Request full information. Ask for bulletin 230.

Packard Instrument Company

DEPT. A • P. O. BOX 428 • LA GRANGE, ILLINOIS

10–12. Biometric Soc., ENAR, Gatlinburg, Tenn. (T. W. Horner, General Mills, Inc., 400 Second Ave. South, Minneapolis 1, Minn.)

10–12. National Speleological Soc., annual, Gatlinburg, Tenn. (G. W. Moore, Geology Dept., Yale Univ., New Haven, Conn.)

10–12. Ohio Acad. of Science, annual, Akron, Ohio. (G. W. Burns, Dept. of Botany, Ohio Wesleyan Univ., Delaware.)

11. Vitamin B-12 Symp., New York, N.Y. (Miss J. Watson, 451 Clarkson Ave., Brooklyn 3, N.Y.)

11–12. Eastern Psychological Assoc., annual, Philadelphia, Pa. (G. Lane, Dept. of Psychology, University of Delaware, Newark.)

11–12. Montana Acad. of Sciences, annual, Missoula. (L. H. Harvey, Montana State Univ., Missoula.)

11–18. Horticultural Conf., 15th internatl., Nice, France. (Secretariat General, 84, rue de Grenelle, Paris 7e, France.)

12. Society for the Scientific Study of Religion, New York. (L. Whitman, 297 Fourth Ave., New York, N.Y.)

13–14. American Soc. for Artificial Internal Organs, Philadelphia, Pa. (G. Schreiner, Georgetown Univ. Hospital, Washington 7.)

13–18. American Chemical Soc., 133rd, San Francisco, Calif. (R. M. Warren, ACS, 1155 16 St., NW, Washington 6.)

13–19. Federation of American Societies for Experimental Biology, annual, Philadelphia, Pa. (M. O. Lee, FASEB, 9650 Wisconsin Ave., Bethesda 14, Md.)

14–16. Automatic Techniques Conf. Detroit, Mich. (J. E. Eiselein, RCA, Bldg. 10–7, Camden 2, N.J.)

14–18. American Assoc. of Immunologists, annual, Philadelphia, Pa. (F. S. Cheever, Graduate School of Public Health, Univ. of Pittsburgh, Pittsburgh 13, Pa.)

14–18. American Soc. for Experimental Biology, annual, Philadelphia, Pa. (J. F. A. McManus, Univ. of Alabama Medical Center, Birmingham.)

14–18. American Soc. of Biological Chemists, annual, Philadelphia, Pa. (P. Handler, Dept. of Biochemistry, Duke University School of Medicine, Durham, N.C.)

15–17. Gas Measurement, 34th annual conf., Norman, Okla. (M. L. Powers, Extension Div., Univ. of Oklahoma, Norman.)

16–25. Instruments, Electronics and Automation Conf., London, England. (Industrial Exhibitions Ltd., 9 Argyll St., London, W.1.)

17–18. Environmental Engineers, 2nd annual institute, New York. (Institute of Environmental Engineers, 9 Spring St., Princeton, N.J.)

17–18. Midwest Benthological Soc., annual, Madison, Wis. (K. M. Mackenthun, 453 State Office Bldg., Madison 2.)

17–19. Association of Southeastern Biologists, annual, Tallahassee, Fla. (J. C. Dickinson, Jr., Dept. of Biology, Univ. of Florida, Gainesville.)

17–19. Eastern Colleges Science Conf., 12th annual, Wilkes-Barre, Pa. (Mrs. E. Stevens, Wilkes College, Wilkes-Barre.)

(See issue of 21 February for comprehensive list)

NYLAB

Supplying Your Complete

LABORATORY NEEDS..

● **Since 1931, New York Laboratory Supply Co., Inc., has been serving industry with all their laboratory requirements. This has not been an easy job—it has been a challenge—a challenge we meet and conquer every day. Below is listed a few of the many instruments and apparatus we carry:**

Balances & Weights
Baths
Calorimeters
Centrifuges & Accessories
Chemicals, Laboratory
Colorimeters
Crushers & Mills
Distilling Apparatus
Filter Papers
Furnaces
Gas Analysis Apparatus
Glassware
Heaters & Hotplates
Hydrogen-Ion Equipment
Hydrometers
Incubators
Metalographic Equipment
Microscopes & Accessories
Nitrogen Determination Equip.
Ovens
Petroleum Testing Equip.
Porcelain Ware
Powerstats
Pumps
Refractometers
Shakers
Sieves
Spectrophotometers
Stirrers—Mechanical & Magnetic
Thermometers, etc.

Let us help you efficiently solve your laboratory instrument and apparatus problems. Call on us, we will be glad to help you.

KEY TO ALL LABORATORY SUPPLIES

NYLAB

NEW YORK
Laboratory Supply
COMPANY, INC.
76 Varick Street, New York 13, N. Y.
Telephone CAnal 6-6504

2 NEW MICROTOMES by JUNG

Famous for Precision Microtomes Since 1872

UNIVERSAL QUICK-FREEZE

MODEL 1200

- For rapid sectioning of frozen or embedded tissues
- Automatic Object Feed—2 to 40 microns, in steps of 2 microns
- Instant transition from frozen to paraffin work by a mere change of object plate
- Integral two-way valve cools object as well as knife
- Tilting knife guards mounted for safe operation
- Ball Bearing Knife Action—free of play and vibration
- Streamlined design and compact, enclosed mechanism renders microtome dirt and dust proof
- Section control indicates thickness of specimen desired

ROTARY MICROTOME 1120



- Automatic Feed—1 to 40 microns in steps of 1, 2 or 5 microns
- Freezing chamber quickly converts microtome for frozen tissues
- Unique tilting arrangement for portability
- Special knife holder for safe operation
- Completely vibration-free instrument
- Built-in section counter and specimen control
- Accessories include conveyor belt and specimen trimmer

We shall be pleased to send complete illustrated details

WILLIAM J. HACKER & CO. INC.
82 Beaver St., New York 5, N.Y.
BO. 9-8750

LETTERS

The editors take no responsibility for the content of the letters published in this section. Anonymous letters will not be considered. Letters intended for publication should be typewritten double-spaced and submitted in duplicate. A letter writer should indicate clearly whether or not his letter is submitted for publication. For additional information, see Science **124**, *249 (1956) and* **125**, *16 (4 Jan. 1957).*

Auxiliary Languages

I was much interested in the issue of 12 July 1957, which editorially blessed the auxiliary language Interlingua [W. Davis, "Babel Resolved," *Science* **126**, 55 (1957)] and displayed it in the *tremendemente* readable article by F. F. Cleveland, "Communication in le Scientia" (page 64).

The article contains a number of words on which I should like to comment in the light of the claims made for Interlingua in the editorial, which boil down to the notion that it "can be read at sight by all who can read any Western European language."

Column 1, lines 11 and 12: Who besides Cleveland, the International Auxiliary Language Association, and the divinely inspired is going to understand *placiamento*? Even the faintly suggested English *placement* would be incongruous here.

Column 1, line 18: Jornales, here evidently used in the sense of "magazines," would be taken to mean "diaries" or "newspapers" by speakers of Romance languages. Semantic slippage of this sort is a common feature of Interlingua.

Column 1, line 22: Valorabile, apparently intended to mean "valuable," seems to be floating etymologically on nothing more solid than air, unless it be the rare Spanish *valorable*. It is not in the *Interlingua-English Dictionary*; this fact does not condemn the word, but it suggests that the composer in Interlingua may have his moments of mental torture.

Column 1 line 24: In what West European language does *tunc* occur, or anything remotely resembling it? Here is one thing, at least, that needs to be "studied and learned." It is immaterial whether or not one drags in the fact that it is taken from Latin.

Column 2, line 1: Where does the word *amonta* come from? Can it be English *amount*, pseudo-Romancified and tossed in the basket with the Latin first-declension feminines?

Column 2, line 7: The expression *facilitate de lectura* might well be interpreted by some over-relaxed English speaker as meaning "facility in lecturing" instead of "facility in reading."

Column 2, line 8: The idiom *in addition a* is completely foreign to the Romance languages. Unless Cleveland footnotes his Anglicisms, his Latin readers will have some things to study and learn.

Column 2, lines 11 and 12: In the expression *pro passar le examination*, two things call for comment. First, what is this dreadful word *examination* which is found in no language except English and is not listed in the *Interlingua-English Dictionary*? If a distinguished scientist who has been editing an Interlingua magazine since 1952 can still be the victim of such English mirages over his Interlingua landscape, what chance have the rest of us? Secondly, the word *passar* is semantically shaky here: does the phrase mean "*pass* an examination" like the equivalent English and Italian expressions (compare the Italian *passar ad un esame*), or does it merely mean "*take* an examination," like the French *passer un examen?*

Column 2, lines 34 and 35: The glib doctrine that Interlingua reads and writes itself has here tripped the writer over the word *singule*. His expression *in un singule lingua international* is evidently intended to mean "in a single [that is, one only] international language." The trouble is that neither the Latin *singulus* nor its derivative in any Romance language means "single" in the sense we are dealing with here.

Column 2, line 35: Cleveland has misspelled the word *preferabilemente*. The *Interlingua-English Dictionary* gives *preferibilemente*, which is required by the Interlingua principles of etymology. Was the text form a slip of the pen, or could the English *preferable* have beguiled the devotee of this painless auxiliary language?

Column 3, line 5: Where does the verb *maestrar* ("to master"?) come from? The closest thing on the Continent is French *maîtriser*, which is differently formed. Again, English dressed up in Romance feathers.

Column 3, line 10: When Cleveland writes *si multo* instead of *tanto*, his Latin colleagues have had it. But who can blame him? Interlinguists believe their language can be read without difficulty; they never claimed it could be read without exasperation.

Column 3, line 18: Ingagiate, according to the Interlingua dictionary, means "engaged" only in the sense of "employed, hired." Perhaps I mistake the writer's meaning, but I assume it is "occupied, busy." If so, another case of creeping Anglicism—none of the Continental cognates of *engage* has this meaning.

Column 3, line 22: Who will know *parve* ("small") except the Spaniard and the Latin scholar? (The Esperantist, by the way, doesn't have to know it.)

Column 3, line 27: Recipientes in the sense of English "recipients" will hardly do. The Interlingua dictionary, faithfully reflecting the usage of French, Italian, Spanish, and Portuguese, gives *recipiente* as a chemical term for a container and provides the distinct term *receptor* to represent the concept of a person receiving something.

It is hard to see how the writer in Interlingua can possibly keep faith with the spirit or the principles of the language. Having no firm rules of grammar or syntax, having no power to fix the meanings of words or to create new words, or to do anything apart from the welter and flux of the national languages—and, with all this, claiming to be a reliable and precise instrument for conveying scientific thought—Interlingua strikes me as a colossal rationalization. The notion that one does not have to *learn* a language, to master its disciplines, to bow to its caprices, seems to me an utter delusion. Perhaps one of these days we shall rediscover the solid virtues of a middle-ground auxiliary language such as Esperanto.

JAMES F. RETTGER
4412 Volta Place, N.W., Washington, D.C.

For the past year I have been following with interest the spread of the use of Interlingua for summaries of papers in a growing number of journals in the medical field, and have wondered who might be promoting it among the publishers and editors—a rather ultraconservative group of individuals. It would be wonderful if the problem so succinctly restated by F. F. Cleveland [*Science* **126**, 64 (1957)] could so easily be solved; I am not so sure it can.

Since I am by no means a linguist, I have no ready-made prejudices against a synthetic language, even such a bastard one as Interlingua. I should rather say that its justification lay in whether or not it really works—and at first glance Interlingua does seem to work, just as the advertisement on the editorial page promised it would. I have no doubt that any sampling of its readability among conventionally trained scientists would achieve a satisfyingly high score, at least in the presentation of summaries or news notes. I did not get the impression from Cleveland's account of his interesting experiment that the ultimate suitability of Interlingua as a precise, universal "scientific" language had been thoroughly demonstrated in connection with the actual texts of *technical papers*, but certainly his approach is a refreshing one.

But as I read his article, the heretical suspicion kept gnawing at me that if I had never had to sweat over my high-

PUMP

LIQUIDS
GASES
SLURRIES

WITHOUT CONTAMINATION OR CORROSION

Wavelike Motion of Steel Fingers Forces Material Through Tubing

Cap. 0.2 cc. per min. to 4.5 G.P.M.

Prices **$60.00** to **$550.00**
depending on size and accessories

Write for Descriptive Literature

SIGMAMOTOR, INC.
46 North Main St. • Middleport, N.Y.

PHOTOVOLT
EXPOSURE PHOTOMETER
Mod. 200-M



for PHOTOMICROGRAPHY

Accurate determination of exposure time in black-and-white and color photomicrography

Write for Bulletin #810 to **Price $105.00**

PHOTOVOLT CORP.
95 Madison Ave. New York 16, N. Y.

aloe

NEW IMPROVED ALOE

ELECTRIC MICROTOME KNIFE SHARPENER

FOR A KEENER EDGE IN LESS TIME

Less effort, too, in getting the keen, uniform edge you want. This new improved sharpener has heavy duty "T" guide holder that supports knife over the full length up to 13 inches, greatly simplifying operation. Holder is adjustable for differences of bevel required by various knives.

Special alloy honing wheel is powered by unusually quiet split phase ¼ h. p. motor. Entire mechanism is enclosed in attractive gray finish rubber-footed metal housing with aluminum platform. Overall dimensions: 13½" x 11" x 9". Operates on 115 volts A. C.

For additional information, request Bulletin 20-105.

BEFORE SHARPENING note ragged knife edge.

FIRST HONING removes nicks and rough spots after only a few strokes on honing wheel.

COMPLETE HONING gives fine edge but a fine wire or burr mars its keenness.

AFTER STROPPING cutting edge is smooth and even; uniformly sharp.

IMPROVED STROP ASSEMBLY ***Standard equipment with the sharpener***

Strop removes small wire or burr left by sharpening. Puts final fine edge on knife. Assembly consists of high quality horsehide strop and linen finishing strop mounted on heavy metal frame equipped with thumb screws for adjusting tension.

60040—Aloe Electric Microtome Knife Sharpener, improved model as described, with adjustable strop assembly, 3 sticks assorted abrasive paste, one can of abrasive powder, one can of special solvent, cord and plug. Each **$295.00**

aloe scientific
DIVISION OF A. S. ALOE COMPANY

5655 KINGSBURY, ST. LOUIS 12, MO.

14 DIVISIONS COAST TO COAST

RADIOACTIVITY AT WORK...#1

Our business is radioactivity—applying it, measuring it, protecting against it

Since our business might have bearing on *yours*, this is the first in a series of reports on work we're doing for a variety of clients, not only in the nuclear industry but in such diverse fields as chemicals, petroleum, pharmaceuticals, medicine, steel and coal.

Nuclear reactor developers and operators call on us for such services as analysis of reactor fuels, decontamination studies, and the development of data relating to the production of atomic power.

Research people and industrialists in all fields draw upon our specialized skills and equipment for applying the phenomena of radioactivity to improving processes and for highly complex studies which were not possible with "yesterday's" techniques.

So many people these days are curious about the possibilities of applied radioactivity, we thought you might be interested in reading about some of our current projects.

ENVIRONMENTAL RADIOACTIVITY SURVEYS

Since we started in business, one of our important activities has been conducting site surveys for operators of nuclear reactors. These studies are undertaken prior to start-up to determine the level of "background" radioactivity in the area surrounding the reactor.

This then provides a basis for measuring any increase in radioactivity after the reactor is in operation. Environmental radioactivity studies are required. Such studies should also be made on a continuing basis not only for safety's sake but to provide "third party" legal protection against lawsuits and insurance claims.

In conducting a site survey, NSEC takes samples from the surrounding area. These may be soil, ground water, plants, animals, fish, rainwater, dust, sewage or other materials. We consider carefully the nature of the facility, the terrain, direction of air movement, and surface and ground water flow. The samples are processed and analyzed in our labs. We are then able to establish the radioactivity level, the kinds of isotopes producing it, and the possible sources of these isotopes.

NSEC has conducted more site surveys of nuclear facilities than any other company in the United States. *For information on environmental radioactivity surveys of your nuclear site, phone us at HOmestead 2-4000 in Pittsburgh. We can either conduct the survey for you, or train your personnel on proper procedures.*

PREVENTING BEACH POLLUTION

Recently, in the largest radioactive tracer study ever conducted in the United States, NSEC successfully traced the dispersion of sewage effluent flowing into ocean waters. Our study helped the City of Los Angeles in planning expansion of its sewage system. First we injected the isotope scandium-46 into sewage about to be released into Santa Monica Bay. This enabled us to measure the pattern of sewage diffusion and its dilution in sea water to one part in ten thousand.

Write for a copy of "Radioactive Tracer Study of Sewage Field in Santa Monica Bay" by Dr. Ralph L. Ely, Jr. (He's our Vice President and Technical Director.) Or ask about our forthcoming study for the Republic of Venezuela, in which we will investigate littoral drift, using radioactive sand, to determine the feasibility of a certain harbor location.

RADIATION SICKNESS

It's common knowledge that excessive radiation produces harmful effects in human beings, ranging from mild nausea or skin burns to cancer and death. Recent experiments under the direction of Dr. A. Edelmann, Manager of our Department of Biology and Medicine, have indicated that radiation can also produce a toxic factor which appears in the blood. Analysis of the blood of rats subjected to X-rays under varying conditions not only indicates that a toxic element is produced but that it may be transferred by injection from one animal to another.

When and if this toxic substance is identified, it may be possible to devise an antitoxin to alleviate some of the effects of atomic radiation. *Medical and pharmaceutical applications of controlled radioactivity open up entirely new means of studying existing problems. Contact Dr. Edelmann about your problem.*

DETERMINATION OF BORON IN SILICON

A major problem plaguing the electronics industry is achieving ultra-pure silicon for transistors. Current methods are slow and costly, but effective. Nevertheless, boron still remains as a damaging impurity even in minute quantities of only a few parts per billion. Ordinary chemical methods cannot detect the presence of boron in such small concentrations.

However, NSEC scientists are now perfecting a process by which the boron is transmuted into radioactive carbon-11 and subsequently measured by its radioactivity.

This new method of analysis will be helpful in the quality control of silicon during production. *Once a routine method is established it will be offered on a commercial basis. Interested? Drop us a letter.*

We'll be glad to furnish detailed information on any of these studies. And if you'd like to keep abreast of new developments in the field, just ask us to put you on the mailing list for our monthly publication "Radioactivity at Work."

Our technical staff is available for consultation on your specific requirements and will make proposals and quotations without obligation.

Nuclear Science and Engineering Corporation

DEPT. S-1, P. O. BOX 10901, PITTSBURGH 36, PENNSYLVANIA

school Latin, if I had not majored in college German or had the minimum exposure to French with which to face the old-fashioned language requirements in graduate school, if I had not accidentally acquired a smattering of reading Spanish, and, most particularly, if my mother tongue were other than English, I could not have read more than a word or two here and there. I am quite sure this potential bias applies to Cleveland's entire test sample of scientific readers.

If, as has been suggested, scientific training programs should drop their language requirements, will not their future trainees have to "learn" Interlingua—less laboriously than they would learn French or German, perhaps, but learn it none the less—a language with no integral form, with a limited and makeshift vocabulary (apparently chosen simply as sops to half-a-dozen current languages), and with a basic syntax that actually requires a fair facility in English? If it should turn out that Swedish, Japanese, German, Russian, Hindi, or even English-speaking scientists require a basic facility in several languages in order to communicate precisely in Interlingua, then indeed we might have been hoaxed, and our energies might better have focused in the first place on the adoption, for international scientific use, of one of the modern languages—one in which precise communication *can* be effected and in which scientific literature can accurately be read by librarians, editors, and even laymen, as well as by scientists.

ALAN MATHER

Memorial Hospital, Wilmington, Delaware

Watson Davis's article on "Babel Resolved" [*Science* **126**, 55 (1957)] made interesting reading, even if not everybody would agree with every point of it. However, he touched only one out of four aspects of this problem.

For scientists, *babel* means difficulties (i) in reading foreign science abstracts; (ii) in reading foreign articles; (iii) in personal correspondence with foreign workers in the same field; and (iv) in oral discussions with foreigners at international conferences. International use of English has largely overcome some of these difficulties. We have, in Washington, services which translate abstracts directly into English without need for Interlingua. Most foreign scientists may not be expert in English but can at least write a decipherable letter in broken English. But at international conferences we keep meeting the Frenchman who does not understand your English question and who can answer it only in French after someone translates it for him, not to mention the American sci-

entist who feels ill at ease at a conference in Paris. Also, how many of us can read most of the foreign scientific literature easily enough to actually do so? Foreign articles and oral discussions in foreign languages are therefore our main problems.

Forrest F. Cleveland [*Science* **126**, 64 (1957)] rightly says that translation of articles is not a satisfactory solution, if it is practicable at all. Where would we find all the translators it would require? A solution will be found only if and when we scientists all write originally in one and the same chosen language, and do the writing ourselves.

I agree with Watson Davis that *if* one knows enough other languages, then one can usually *guess* the meaning of a sentence in Interlingua or Esperanto after reading it two, three, or four times. The question of readability at sight, however, is rather irrelevant. *Any* language with an international vocabulary (there are several) is more or less easy to decipher. The main difficulty is not in the reading but in the writing, the speaking, the understanding of the spoken word. The greater regularity of Esperanto over Interlingua makes Esperanto greatly preferable. The confusion created by Interlingua's so-called "natural" accentuation of syllables (whatever that means) is sufficient to make a person understand why, at conferences, Interlingua (though admitted for written abstracts) has never found oral use even as a secondary language, contrary to the situation with respect to Esperanto, which is used every year by thousands at international congresses in which is is the only congressional language.

Esperantists don't claim that texts in Esperanto would be completely understandable to persons too lazy to learn even the simplest elements of the language (though, if you try it out for yourself, you may find Esperanto just about as easy as Interlingua). But we do claim that it is some five times easier to learn it for active use than it is to learn any national language. I was able to translate *into* it, faultlessly, from the daily newspaper after 18 hours of pleasantly easy study. (Since I already knew a couple of other languages, learned in highschool, some may be a bit slower.) To learn to *read* Esperanto requires much less time.

I admit that if right now we could make Esperanto internationally a required subject for all sixth-grade school children, it would yet take many years before they would start using it generally for international communication. But at that time they would like to find abstracts of older papers published in Esperanto rather than in Interlingua.

There was a time when German was *the* international language for physics and for some other branches of science.

LINDE *Rare Gases*

Ne
A
Kr
He
Xe

Symbol of Highest Purity

...in cloud and bubble chambers

...in radiation detecting equipment

...in gas discharge devices and glow tubes

...as protective atmospheres for crystal growing

Rare gases produced by LINDE are continuously analyzed by mass spectrometer, gas chromatography, and chemical and physical methods. These analytical checks assure you of the purest rare gases obtainable.

LINDE argon, neon, helium, xenon and krypton are available in one- and two-liter glass bulbs, or in steel cylinders under pressure. Mixtures of gases are also available to your specifications. Prompt delivery is assured.

For detailed data on the physical and electrical properties of LINDE Rare Gases, write Dept. SC-3. LINDE COMPANY, Division of Union Carbide Corporation, 30 East 42nd Street, New York 17, N. Y. Offices in other principal cities. *In Canada:* Linde Company, Division of Union Carbide Canada Limited.

Linde TRADE-MARK Ne Kr He A Xe RARE GASES

UNION CARBIDE

The terms "Linde" and "Union Carbide" are registered trade-marks of Union Carbide Corporation.

IN THIS ISSUE

SCIENCE ANNOUNCES

A NEW SERVICE

FOR ITS READERS

To provide a convenient and rapid means for obtaining further information about Equipment News and advertised products, SCIENCE has inaugurated a Readers' Information Service for its subscribers.

Every week in SCIENCE you will find a coupon listing all advertisers and new product announcements for that issue. Form the habit of using this handy self-mailer to continually keep abreast of the latest developments in instruments, equipment and materials.

SEE PAGE 550 OF THIS ISSUE

Since 1933, English has taken its place. In this world nothing lasts forever. The present position of English will last an even shorter time if no funds and no legislation are available to get high-school children interested in science, as might be achieved if instruction were given by people who, by acquiring an M.S. or Ph.D. degree in the subject they teach, had shown that they are interested themselves and have, as background, an understanding of the epoch-making progress in science that is being made, to a degree not likely on the basis of undergraduate courses alone. If it is utopian to expect this, then I keep my fingers crossed for our English-speaking descendants and hope that the next change of international language will be a switch to Esperanto rather than to German, Russian, or what else. To achieve this in time, however, the Esperanto movement needs solid support now.

F. J. BELINFANTE
Department of Physics, Purdue University, Lafayette, Indiana

Significantly, the "spread in the use of Interlingua" in scientific publications has been largely spontaneous. Many editors have felt a need for such a means of increasing the number of readers of their journals and of thus facilitating the advancement of their field of science. Upon seeing a sample of Interlingua, they have been impressed with its readability, have investigated its suitability for use in their journal, and have decided finally to use it for summaries or otherwise.

The contents of *Spectroscopia Molecular* have included not only "summaries" and "news notes" but also short technical articles and three technical monographs published in serial form before being collected into book form. Copies of the first monograph have been sold in 25 states of the United States and in 19 other countries, while the second has been sold in 15 states and in 9 other countries—despite the fact that the material was already available in the journal. It seems quite certain that this demand for the monographs, and for the quite technical issues of the journal, would not have existed unless the buyers had felt that Interlingua was a "precise, universal, and 'scientific' language."

Most persons, including scientists, will (and should) continue to have some knowledge of European languages as a part of their general educational and cultural background. The greater this knowledge the easier it will be to use Interlingua. But even if scientists must learn Interlingua from the very beginning, they will find that this requires less time than is needed to learn one of the national languages. Besides, it seems

quite improbable that any national language will approach universal usage. Much material is now published in English, but many cannot read English. For example, the recent UNESCO report [*Scientific and Technical Translating and Other Aspects of the Language Problem*, J. E. Holmstrom, Ed. (Columbia Univ. Press, New York, 1957), p. 13] says: "Nearly two-thirds of engineering literature appears in English, but more than two-thirds of the world's professional engineers cannot read English and a still larger proportion of English-reading engineers cannot read scientific literature in other languages. In other words, leaving qualitative differences aside, the greater part of what is published is inaccessible to most of those who could otherwise benefit from it."

The average scientist can probably read Interlingua at sight with 80 percent comprehension. Thus, material written in Interlingua is immediately useful to him, since much of his reading consists in scanning articles to see if they contain material of importance for his work. For articles which require 100 percent comprehension, or for writing in Interlingua, use of the dictionary and grammar will of course be necessary. [To test whether Esperanto would be equally readable and useful, the reader may compare the parallel texts in Interlingua and Esperanto in the *American Journal of Physics* [**21**, 471 (1953)] or in the UNESCO report (p. 200)].

To speak for myself, if a scientist who is by no means a linguist could first see a sample of Interlingua in February and begin editing and publishing a periodical the first issue of which appeared in May of the same year, despite a concurrent heavy schedule of teaching and research, it certainly cannot be too hard to learn to write in Interlingua.

The scientist is a busy person. If he has to take the time to study a new language, however simple, before it begins to be of use to him, he probably will not do it. But if there begins to appear literature of importance to him in a language he can largely comprehend at sight, he will probably scan it. And if by such scanning, and by use of the dictionary and grammar for careful reading of those articles that are of importance for his work, he is able gradually to perfect his comprehension while obtaining information that is of use to him, then it is possible that he may begin to appreciate the advantages of this common language. He may even finally begin to write and speak it in order to carry his ideas and results to a wider audience. Let us hope so. For if this were universally done, the gain to science would be substantial.

FORREST F. CLEVELAND
Department of Physics, Illinois Institute of Technology, Chicago

Type LC1-18A. Chamber: 18″ by 30″. Ultimate pressure: 2 x 10^{-5}mm Hg. Diffusion pump speed: 475 liters per second at 2 microns.

Type LC1-14A. Close-up shows control panel. Chamber: 14″ by 24″. Ultimate pressure: 1 x 10^{-5}mm Hg. Diffusion pump speed: 300 liters per second at 5 x 10^{-5}mm Hg.

High-vacuum systems

A don't do-it-yourself project

Type LC1-12A. Chamber: 12″ by 18″. Ultimate pressure: 1 x 10^{-5}mm Hg. Diffusion pump speed: 200 liters per second at 5 x 10^{-4} mm Hg.



Type LC2-18. Two 18″ by 30″ chambers. Each performs same as LC1-18A. Chambers can be worked separately, providing great flexibility.

Unless you're really an expert, *doing-a-vacuum-system-yourself* saves little. It certainly takes time. And most likely you'll get no marks for quality.

So why fuss when you can get a *complete* CEC system with exactly the *right* pumps, gauges, and valves? A system that's ready to operate—leakproof, completely accurate—built by specialists in the fabrication of high vacuum equipment.

While designed primarily for metal evaporation, these packaged systems are versatile. They can readily be used for pulling and growing crystals, leak detection on small containers, melting small metal samples, etc.

We'll be glad to send you complete details and prices of these CEC systems.

Consolidated Electrodynamics

Rochester Division, Rochester 3, N. Y.

formerly Consolidated Vacuum

SALES AND SERVICE OFFICES IN PRINCIPAL CITIES



KENNAMETAL* components help valve a 646-mph flow!

Builders of chemical equipment must frequently find components with unusual service properties.

When the Manton-Gaulin Mfg. Co., Inc., of Everett, Mass., designed and built this Sub-Micron Disperser Valve, they encountered a problem.

The solid-fluid dispersion materials must move through the valve at almost supersonic speeds. Components in the path of the flow are exposed to severe erosion and abrasion . . . plus corrosive action in some applications.

The company found that Kennametal tungsten carbides provide the necessary properties to stand up against such destructive forces. Vulnerable parts are being made of Kennametal as they have proven to be the most economical solution to the service-maintenance problem.

If at any time you need materials with unusual resistance to erosion, abrasion, or corrosion . . . materials that can retain normal properties under prolonged exposures at 2200°F and above; materials with rigidity three times greater than the hardest steel, it will pay you to investigate the contribution Kennametal compositions are making in scores of varied applications. Just write: KENNAMETAL INC., Dept. SA, Latrobe, Pennsylvania.

*Trademark 3121

INDUSTRY AND KENNAMETAL ...Partners in Progress

EQUIPMENT NEWS

The information reported here is obtained from manufacturers and from other sources considered to be reliable. Science *does not assume responsibility for the accuracy of the information. All inquiries concerning items listed should be addressed to* Science, *Room 740, 11 W. 42 St., New York 36, N.Y. Include the name(s) of the manufacturer(s) and the department number(s).*

■ CRYSTAL LATTICE MODELS of German manufacture now include feldspar, alpha quartz I, alpha quartz II, beta quartz I, and beta quartz II. Models, consisting of wooden spheres fixed and joined by metal rods, are designed on the basis of x-ray- and electron-diffraction data. Linear magnification is 2.5×10^8, so that 1 A is 25 mm. (Arthur S. LaPine & Co., Dept. S907)

■ POWER-SUPPLY REGULATION ANALYZER measures applied d-c voltage, the percentage change in applied voltage, and the root-mean-square ripple of regulated and unregulated power sources. Voltage range is 1 to 3000 v; accuracy is ± 0.1 percent. Percentage regulation is measured in four ranges of sensitivity from 0.005 percent to 5 percent each side of the null position. Ripple voltage is measured in 11 ranges to 100 v r.m.s. Provision is made for oscilloscope display and for external recording. (Kepco Laboratories Inc., Dept. S917)

■ TRAVELING-WAVE OSCILLOSCOPE is designed to display transient and repetitive phenomena in the millimicrosecond region. Frequencies as high as 2000 Mcy/sec and voltage levels of 40 to 50 mv can be detected. The total size of the display is 0.4 by 0.6 in., but the extremely small size of the cathode-ray beam spot, 0.002 in., permits resolution equivalent to that of a standard 5-in. cathode-ray tube. In terms of trace widths, sensitivity is 0.06 v per trace width. (Edgerton, Germeshausen & Greer, Inc., Dept. S925)

■ DENSITY MEASURING SYSTEM consists of a probe and a power supply. The probe is coated to resist the action of liquids being observed. A standard model has a range of 0.60 to 1.45 g/cm³. Time response for a change of density of 0.01 g/cm³ is about 1 sec. Temperature range is 0° to 100°C. Output from the instrument can be used for recording density. (General Communication Co., Dept. S930)

■ OSCILLOGRAPH allows simultaneous and directly visible recording of up to 16 processes. Recording is rectilinear. Frequency response is from d-c to 165 cy/sec. Sensitivity is 3 mv, peak-to-peak, per millimeter, and each record is 20

Significant Advance in Film Badge Dosimetry by

THE STANDARD FOR RADIATION SAFEGUARDS

CON-RAD



gives you all these special features in

MEASUREMENT...

Extreme sensitivity — 5 mr for soft x and gamma rays; 10 mr for hard x and gamma rays

Wide exposure range — from 5/10 mr to 600R

Complete coverage—beta-gamma, x-ray, and neutron film packets are held in one badge

DESIGN...

Tamper-proof — special unlocking device required to open badge

Combined film and security badge — has space for standard 1½ × 2 identification photo

Lightweight — sturdy, moulded plastic badge weighs less than 1 oz.

SERVICE...

Prompt weekly reports, supplemented by quarterly and annual cumulative report

For data on the newest advances in film-badge dosimetry write for Bulletin S-3

CON-RAD controls for radiation INC.

130 ALEWIFE BROOK PKWY., CAMBRIDGE, MASS.

mm wide. Five attenuation steps are provided. Input impedance is about 1 megohm. Chart speeds are selectable from 10 to 200 mm/sec. (Brinkmann Instruments Inc., Dept. S931)

■ SIEVE SHAKER uses a shaking pattern which involves rotation of the sieve platform in a small circular arc at the same time that it is being swayed in a vertical arc. An impact is imparted to the platform six times per revolution. Hand-operated and motorized models are available in sizes for 8- or 12-in. diameter sieves (Soiltest Inc., Dept. S932)

■ TEMPERATURE - COMPENSATING TIMER permits compensation for the influence of temperature on photographic development. The temperature change to be compensated is detected by a thermistor and is used to control the frequency of current supplied to an electric clock. Thus the clock rate is retarded or advanced as required to insure proper development. Range of compensation is ±4°F. Calibration can be accomplished for almost any film-developer combination. (Eastman Kodak Co., Dept. S934)

■ CORE TESTER provides a display of coercive force, saturation flux density, *Br* to *Bm* ratio and differential permeability, and the shape of the hysteresis loop. The tester is of the current-reset type. Characteristics are displayed 60 times each second. (Mack Electronics Division of Mack Trucks Inc., Dept. S937)

■ PROXIMITY DETECTOR is sensitive to change of position of metallic objects passing within ½ in. of the pickup. A 1/16-in. change in position is detectable. Response rate is 400 per minute. Output is nominally 5v, dc across a 5 Meg load. (Autron Engineering Inc., Dept. S938)

■ REACTOR PERIOD AND POWER LEVEL indications are provided by a combination of a logarithmic picoammeter and a reactor-period meter. Current is measured from 10^{-13} to 10^{-6} amp; positive and negative reactor period from 3 to 30 sec. After warm-up, drift of the log circuit is within 0.05 decade in 24 hours. The period meter has 5-sec recovery time from overload and adjustable response time over a 10-to-1 range. (Keithley Instruments Inc., Dept. S939)

■ HEIGHT GAGE uses a glass scale and glass vernier scales to provide readability to 1 mil. Height adjustment knobs are located in the base of the device to avoid any tilting tendency on adjustment. Available sizes range from 18 to 84 in. (George Scherr Co., Inc., Dept. S940)

JOSHUA STERN
National Bureau of Standards

Schwarz® Biochemicals for RESEARCH in CANCER

NUCLEIC ACIDS
for growth studies.

YEAST ADENYLIC ACID
for its inhibition of tumor growth in mice.

PURINE COMPOUNDS
for growth inhibition studies.

***N*-ETHYL MALEIMIDE**
for its reported antimitotic effect in tissue culture of chick fibroblast.

TRIPHENYL TETRAZOLIUM CHLORIDE
for determination of cancerous tissue.

TRIPHOSADEN®
(Schwarz Brand of Adenosine Triphosphate) for phosphorylation studies.

These Schwarz fine chemicals satisfy the exacting requirements of products intended for laboratory and biochemical use.

To assure the user of highest quality and purity, rigid specifications in accordance with latest literature are established for each product, each lot is carefully analyzed and checked before shipment, complete records are permanently kept, and an analysis is furnished the user if desired.

Quantity production resulting from the wide preference and demand for Schwarz high-quality biochemicals provides ample supplies at low cost. Write for informative technical bulletins, specifications, references to literature and latest complete price list.

Visit our Booth #46 at the Federation Meeting, Philadelphia, April 14–18

SCHWARZ LABORATORIES, INC.
Leading Manufacturers of Yeast Biochemicals and Fine Chemicals
230 WASHINGTON STREET, MOUNT VERNON, NEW YORK SL-388

A Single Source for

STABLE ISOTOPES

CARBON 13
NITROGEN 15
OXYGEN 17
OXYGEN 18

- Highest available enrichments and purity
- Wide variety of standard labeled compounds
- Special labeled compounds synthesized to order

Write for
***Technical Bulletin* 256A**

ISOMET CORPORATION
P.O. Box 34
Palisades Park, N.J., U.S.A.

WANTED

Director of Research

by leading ethical pharmaceutical company

There is an unusual opportunity for an outstanding investigator, age 35 to 45, with M.D. and Ph.D. degrees, who has administrative experience either in academic research or industry. This is a top job offering a challenging opportunity to direct all phases of research.

Congenial environment, excellent working conditions, comprehensive security program. Location: Metropolitan New York area.

Write Box 59, SCIENCE

PERSONNEL PLACEMENT

CLASSIFIED: 25¢ per word, minimum charge $4.25. Use of Box Number counts as 10 additional words. Payment in advance is required.

COPY for classified ads must reach SCIENCE 2 weeks before date of issue (Friday of every week).

DISPLAY: Rates listed below—no charge for Box number. Monthly invoices will be sent on a charge account basis — provided that satisfactory credit is established.

Single insertion	**$26.00 per inch**
13 times in 1 year	**24.00 per inch**
26 times in 1 year	**23.00 per inch**
52 times in 1 year	**22.00 per inch**

For PROOFS on display ads, copy must reach SCIENCE 4 weeks before date of issue (Friday of every week).

Replies to blind ads should be addressed as follows:
Box (give number)
Science
1515 Massachusetts Ave., NW
Washington 5, D.C.

POSITIONS OPEN

Anatomist. Assistant professor or instructor for medical and dental school teaching, prefer person experienced in teaching of gross anatomy. Box 49, SCIENCE. 3/7, 14

(a) **Bacteriologist**; B.S. or M.S. to head department, 250-bed hospital, large affiliated clinic; to $5000, housing for single personnel, married couples available at no charge; lake resort area; East. (b) **Clinical Chemist**; M.S.; California research, testing laboratories. (c) **Senior Research Virologist**; Ph.D. experienced tissue culture, original independent research involving chemotherapeutic research, human, animal virus; development work in vaccine production; minimum $7500; Eastern concern. (d) **Bacteriologist**; M.S., Ph.D. to head department, very large general hospital; to $8400; midwestern industrial city. (e) **Associate Biochemist**; Ph.D. for research, physical chemistry of proteins; knowledge instrumentation required; $7000 up; important eastern company. (f) **Chemist**; Ph.D. preferred, individual training, experience important factors; head active department, teach newest procedures; 270-bed general hospital; large college city; Southwest. Woodward Medical Bureau, Ann Woodward, Director, 185 North Wabash, Chicago. X

Graduate Research Assistant. Microbiology major; M.S. candidate; strong background in chemistry; $1800, 12 months; free tuition, metropolitan New York area. Box 40, SCIENCE. 3/7

MEDICAL TECHNOLOGIST
Male or female
College graduate with experience or training in the development of control of serological and blood coagulation products. Modern laboratory. Good starting salary, employee benefits. 37½ hour week. Send résumé to:
Employment Manager
ORTHO PHARMACEUTICAL CORP.
Route 202 Raritan, N.J.
RAndolph 5-1400 — Ext. 279

(a) **Research Director**; Ph.D., organic chemistry with broad experience in manufacturing chemistry industry; sense of economics, flair for administration required; East. (b) **Clinical Chemist** to direct hospital laboratory; preferably one interested in cancer research, teaching related to cancer; program planned for clinical and non-clinical levels; 500-bed teaching hospital; East. (c) **Chemist** well qualified in clinical biochemistry, Ph.D.; association group of Board pathologists; university city; Midwest. (d) **Professor of Chemistry**; university outside United States; teaching to be done preferably in French. (e) **Microbiologist** qualified in virology or experimental immunology; medical school pediatric research department; South. S3-1 Medical Bureau, Burneice Larson, Director, 900 North Michigan Avenue, Chicago. X

POSITIONS OPEN

M.D., Pharmacologist, experienced with successful career in academic and/or industrial research and ability to work with teams. To assist in scientific direction of pharmacology laboratory of one of the largest pharmaceutical companies, Midwest location. Excellent chance for the right man to head department in the near future. All correspondence will be treated in strict confidence. Box 54, SCIENCE. 3/14, 21, 28

MICROBIOLOGIST, Ph.D.
. . . to head research section, Eastern ethical pharmaceutical company. Some industrial experience desirable. Work covers broad field of microbiology in expanding organization. Reply to
Box 55, SCIENCE

NEW WORLD-WIDE SUMMER PLACEMENT DIRECTORY. Thousands of opportunities in all states, many foreign lands for science teachers, and so forth, who have the summer free. Includes study awards, industry, camps, resorts, ranches, travel tour agencies, earning free trips to Europe, and so forth. Earn, learn, and travel while you vacation. Complete information, including salaries. Send $2 now. CRUSADE, Sci., Box 99, Station G, Brooklyn 22, N.Y. eow

SCIENCE TEACHERS, LIBRARIANS, ADMINISTRATORS urgently needed for positions in many states and foreign lands. Monthly non-fee placement journal since 1952 gives complete job data, salaries. Members' qualifications and vacancies listed free. 1 issue, $1.00. Yearly (12 issues) membership, $5.00. CRUSADE, SCI., Box 99, Station G, Brooklyn 22, N.Y. ew

Supervising Hospital Biochemist for a clinical chemistry laboratory of a large university hospital affiliated with a medical college; also teaching opportunity. Broad experience is required. Salary range up to $7830. Liberal personnel policies. Please address communication indicating your background and experience to the Administrator, H. N. Hooper, Cincinnati General Hospital, 3231 Burnet Avenue, Cincinnati 29, Ohio. 2/21, 28; 3/7

VIROLOGIST, Ph.D.
Experienced in tissue culture techniques. Eastern ethical pharmaceutical company. Some industrial experience desirable. Work covers broad field of microbiology in expanding organization. Reply to
Box 56, SCIENCE

POSITIONS WANTED

Biologist. B.S., horticulture, M.S., genetics; Ph.D., physiology; now teaching, research at northeastern university; publications; specialties hormones, developmental genetics, flowering. Desires teaching, research outside Northeast. Box 51, SCIENCE. 3/14

Bioscience, Ph.D. Age 45. Seeking position in medical institution teaching bioscience or mathematics while studying for M.D. Location immaterial. Box 48, SCIENCE. 3/7

Botanist, Ph.D. Teaching-research. Experienced publications. Ecology, taxonomy, conservation. Box 46, SCIENCE. 3/7

Microbiologist-Biochemist, Ph.D.; 10 years' experience, including teaching or research in intermediate metabolism, protein fractionation, medical microbiology. Seeks challenging academic or industrial post. Box 50, SCIENCE. X

(a) **Physician**; 4 years' experience in research (nutrition and biochemistry); 5 years as director of research, pharmaceutical company. (b) **Biochemist**; M.S. (biochemistry); 10 years, chemist, large industrial company; 4 years, director of biochemistry, government research unit. Medical Bureau, Burneice Larson, Director, 900 North Michigan Avenue, Chicago. X

POSITIONS WANTED

Photographer, medical and scientific, specialized, infrared and ultraviolet; black, white and colored; macro, micro, motion, static. Many years experience. Wants to change position. Box 52, SCIENCE. X

Physiologist, Ph.D., 35; 4 years of medical teaching, 5 years of research experience in carbohydrate and fat metabolism. Desires academic position with research opportunities. Box 53, SCIENCE. X

Plant Physiologist, experience in directing graduate students, southern university. Training, publications involving radioisotopes. Wishes teaching and/or research position near South or Midwest. Box 58, SCIENCE. X

Zoologist, 30, Ph.D.; 2 years of college teaching experience. Desires academic position. Box 57, SCIENCE. X

Zoologist, Ph.D.; 1 year grant supported postdoctoral research. Publications; 6 years' teaching and research at midwestern universities. Vertebrate zoology, ornithology, mammalogy, and ecology. Dynamic, lucid, and meticulous lecturer. Desires university position in teaching and research. Box 41, SCIENCE. 2/28; 3/7

COURSES

TISSUE CULTURE COURSE

The annual course in **Principles and Techniques of Tissue Culture** sponsored by the Tissue Culture Association will be given at the University of Colorado Medical Center, Denver, 7 July to 1 August 1958. A limited number of participants (postdoctoral research workers and teachers) can be admitted. The course will be directed by Dr. John Paul of Glasgow University. For further information and application forms, address Dr. Mary S. Parshley, College of Physicians & Surgeons, 630 West 168 Street, New York 32, N. Y. Tuition $100. Deadline for application: 15 April 1958. 3/21

The Market Place

BOOKS • SERVICES • SUPPLIES • EQUIPMENT

DISPLAY: Rates listed below—no charge for Box number. Monthly invoices will be sent on a charge account basis — provided that satisfactory credit is established.

Single insertion	**$26.00 per inch**
13 times in 1 year	**24.00 per inch**
26 times in 1 year	**23.00 per inch**
52 times in 1 year	**22.00 per inch**

For PROOFS on display ads, copy must reach SCIENCE 4 weeks before date of issue (Friday of every week).

BOOKS AND MAGAZINES

Your sets and files of scientific journals

are needed by our library and institutional customers. Please send us lists and description of periodical files you are willing to sell at high market prices. Write Dept. A3S, CANNER'S, Inc. Boston 20, Massachusetts

PROFESSIONAL SERVICES

TO AUTHORS

seeking a publisher

Learn how we can publish, promote and distribute your book on a professional, dignified basis. All subjects considered. Scholarly and scientific works a specialty. Many successes, one a best seller. Write for booklet SC—its free.

VANTAGE PRESS Inc. • 120 W. 31 St., N.Y. 1
In Calif.: 6253 Hollywood Blvd., Hollywood 28
In Wash., D.C.: 1010 Vermont Ave., NW
Midwest Office: 220 S. Mich. Ave., Chicago, Ill.

PROFESSIONAL SERVICES

NDI — Coordinated Research — New Drug Institute

TOXICITY TESTS

following FDA procedures, for chemicals, foods, drugs, cosmetics, pesticides, additives. Biological assays. Screening tests. Complete research and development services. No obligation for estimates. Call or write Arthur D. Herrick, Director.

NEW DRUG INSTITUTE

130 East 59 St., New York 22 • Mu 8-0640

WISCONSIN ALUMNI RESEARCH FOUNDATION

LABORATORY SERVICES

for the FOOD, FEED, DRUG and CHEMICAL INDUSTRIES

Analyses, Biological Evaluation, Toxicity Studies, Insecticide Testing and Screening, Flavor Evaluation.

Project Research and Consultation

Write for Price Schedule
P. O. Box 2217 • Madison 1, Wis.

PROFESSIONAL SERVICES

Your Book Published

Our famous plan has launched 700 authors. We edit, publish, advertise, distribute. Send manuscript for free report or write for Brochure 8S

PAGEANT PRESS, 101 FIFTH AVENUE, N. Y. 3

SUPPLIES AND EQUIPMENT

• HYPOPHYSECTOMIZED RATS

Shipped to all points via Air Express
For further information write
HORMONE ASSAY LABORATORIES, Inc.
8159 South Spaulding Ave., Chicago 29, Ill.

7 March 1958

Readers' Service

Information Requisition

Use this easy self-mailer to obtain further information

It's simple: Mark — Clip — Fold — Mail

This coupon is for your convenience—to facilitate your requests for further information about advertised products and items in Equipment News.

From:

Name ..... **Position** .....

Company .....

Street .....

City ..... **Zone** .... **State** .....
(Please print or type)

Mark, clip coupon — FOLD HERE along this line — stamp, mail

3¢ STAMP

To:

Readers' Service
SCIENCE MAGAZINE
Room 740
11 West 42 Street
New York 36, New York

Fasten Here Only
Staple, Tape, Glue

SUPPLIES AND EQUIPMENT

SWISS MICE

Send for booklet

TACONIC FARMS

GERMANTOWN NEW YORK

SUPPLIES AND EQUIPMENT

Special LaMOTTE Reagents for Analysis

BORON—Use LaMotte "BORAN" (diaminochrysazin) A new standardized reagent, synthesized in cooperation with Prof. John H. Yoe. Available for immediate delivery.
Sensitivity—1 part in 25,000,000 parts solution.

LaMotte **MUREXIDE** (pure acid ammonium purpurate) High tinctorial power, brilliant color, available for immediate delivery. LaMotte Murexide joins our TIRON and ZINCON as effective indicators in E.D.T.A. titrations.

* * *

Send for LaMotte Catalog on CHEMICAL CONTROLS for
pH, Chlorine, Phosphates and Polyphosphates, etc.

LaMOTTE CHEMICAL PRODUCTS CO.
Dept. H **Chestertown, Md.**

SUPPLIES AND EQUIPMENT

albino rats *

*Descendants of the Sprague-Dawley and Wistar Strains

•

Hypophysectomized Rats

•

HENRY L. FOSTER, D.V.M.
President and Director
THE CHARLES RIVER BREEDING LABS.
P.O. Box P, Brookline 46, Mass.

AMINO ACIDS C^{14}
and other tagged compounds
OF HIGH RADIOPURITY

Nucor ISOTOPES SPECIALTIES COMPANY INC.
P.O. Box 688, Burbank, California

CHERRY HILL FARMS

RATS
MICE
RABBITS
GUINEA PIGS

P.O. BOX 840 CAMDEN, N.J.

Sprague-Dawley, Inc.
Pioneers in the development of the standard laboratory rat.
Sprague-Dawley, Inc.
P.O. Box 2071, Madison 5, Wisconsin
Phone: CEdar 3-5318

THE JUNIOR
Garceau
Electroencephalograph
Price $575.00 complete.
No Batteries
Requires no Shielding
Prompt Delivery
A.C. Operated
Inkless Writing
Shipped Ready to Run

ELECTRO-MEDICAL LABORATORY, INC.
South Woodstock 2, Vermont

MICROSLIDES
Insects, Marine Life, Zoological, Botanical, British Fresh Water Algae
FREE Send for Complete List FREE
ESBE LABORATORY SUPPLIES
459 Bloor St., W.,
Toronto, Ontario, Canada

THE SCIENTIFIC MONTHLY
October 1915-December 1957
Available Issues
$0.75 per copy • $7.50 per year
SPECIAL OFFER
10 copies of one issue .. $ 6.00
50 copies of one issue .. $25.00
Postage included in all prices
AAAS
1515 Mass. Ave. NW, Washington 5, D.C.

7 March 1958

Readers' Service

Information Requisition

Use this easy self-mailer to obtain further informatin about items or literature from the Equipment News section as well as from advertised products.

Circle below desired number corresponding to:

EQUIPMENT NEWS

S907	S917	S925	S930	S931	S932	S934
S937	S938	S939	S940			

ADVERTISERS IN THIS ISSUE

Check page number in list below of advertiser from whom you would like more information. If more than one item appears in ad, letters (A, B, C, etc.) are used to indicate particular items available in order of appearance in advertisement. Where more than one ad appears on a page, **"U" indicates upper ad, "L" lower ad, "I" inside ad, "M" middle ad,** and **"O" outside ad.** Coupon advertisements and advertisements in Personnel Placement and Market Place are not keyed. A multiplicity of items are indicated by *. Readers are requested to specify on this coupon the particular item in which they are interested; otherwise, the request cannot be processed.

☐ 490	☐ 492	☐ 494	☐ 495	☐ 496*	☐ 497	☐ 498
☐ 532UO	☐ 532UI	☐ 532L	☐ 533A	☐ 533B	☐ 533C	☐ 534U
☐ 534LO	☐ 534LI	☐ 535	☐ 536O	☐ 536UI	☐ 536LI	☐ 537
☐ 538	☐ 5391*	☐ 5390, A	☐ 5390, B	☐ 541UI	☐ 541UO	☐ 541L
☐ 542*	☐ 543	☐ 545*	☐ 546O	☐ 546I	☐ 547*	☐ 548UO
☐ 551	☐ 552					



PHOTO BY WILL CONNELL

An almost invisible sample of xylene...barely one-tenth of a microliter...produced this spectrum in 8 minutes, right at the chemist's bench. ⌘ The instrument used was Beckman's low-cost double-beam IR-5...the infrared spectrophotometer chemists are using in their own labs for rapid, reliable analysis of solids, liquids and gases. ⌘ The IR-5 is the only instrument in its price range that can accurately analyze such small amounts of sample as the xylene droplet on the tip of the capillary tube pictured here. It's the only one with horizontal recorder and full-size chart. And that's not all. ⌘ You'll find the complete story of the double-beam IR-5 and the inexpensive single-beam IR-6 in a brand new booklet. Write today for Data File L-42-38. **Beckman**

Scientific Instruments Division
2500 Fullerton Road, Fullerton, California
a division of Beckman Instruments, Inc.

ULTRAVIOLET AND INFRARED SPECTROPHOTOMETERS · GAS CHROMATOGRAPHS · pH METERS · ELECTROCHEMICAL INSTRUMENTS
SALES AND SERVICE FACILITIES ARE MAINTAINED BY BECKMAN/INTERNATIONAL DIVISION IN FIFTY COUNTRIES

Maintains temperature constant within ± 0.05°C
using a 12 x 12-inch bath

SELF CONTAINED . . . THERMO-REGULATOR, HEATING UNIT, STIRRER AND CIRCULATING PUMP IN ONE UNIT

- **For attachment to any vessel with wall thickness up to 1¼ inches**
- **Can be preset at any desired temperature 0 to approx. 90°C**



9935.

TECHNE "TEMPUNIT"

CONSTANT TEMPERATURE CONTROLLER

TECHNE "TEMPUNIT" (Patented). A self-contained unit incorporating all components required for maintaining open water baths at temperatures up to approximately 90°C, and for circulating water to external apparatus at a rate of 1¼ quarts per minute at 1½ ft. head.

The unique indicating thermoregulator system, with pneumatically actuated switch for control of heater, has the sensitivity of electrical contact methods but with greater dependability and longer life. Maintains temperature constant within ±0.05°C in a 4-gallon cylindrical glass vessel, 12 × 12 inches, without insulation.

Control housing, 6¾ inches wide × 4⅝ inches deep × 5½ inches high, contains stirring motor, thermoregulator with temperature indicator dial graduated from 15 to 95°C and pilot lamp, and has built-on clamp for attachment to vessels with wall thickness up to 1¼ inches.

The helical, bimetallic sensing element, stirrer, aspirator tube and 1000-watt tubular immersion heater are integrally attached beneath the housing. Heater is wound in a coil which encircles the six-blade propeller of stirrer and tip of aspirator tube.

Stirring motor, 1/20 h.p., is fan cooled, induction type, with self-lubricating bearings, suitable for continuous use. Immersed parts, with exception of bimetallic helix, are nickel plated. Housing is finished with glossy, green hammered effect.

Overall dimensions 6¾ inches wide × 7 inches deep × 11½ inches high. When mounted, the unit projects 4½ inches beyond inner edge of bath and extends 5⅝ inches below rim. For proper operation, bath must be filled to within 2 inches of rim. Tubulation for connection of pump to external apparatus is ⅜-inch outside diameter.

9935-A.

Method of Use. In use it is necessary only to set the control pointer at desired temperature on dial. A second pointer, driven by the bimetallic helix, continuously indicates the bath temperature. Suction produced by stirring action at tip of aspirator tube, contracts a plastic bellows, closing a switch which turns on the heater. Expansion of helix rotates the indicating pointer until it reaches selected temperature on dial, at which point a valve is opened, inflating the bellows and shutting off the heater. Heater is also automatically shut off if stirrer or aspirator pump is not operating properly, or if water level of bath should fall below aspirator tube.

9935. Constant Temperature Bath Controller, Techne "Tempunit" (Patented), as above described, complete with 4-ft., 3-wire connecting cord with 2-prong, parallel blade attachment plug cap, and directions for use. Power consumption 1040 watts. For use on 115 volts, 50 or 60 cycles, a.c. Without bath **135.00**

9935-A. Ditto, complete with bath consisting of cylindrical jar of Pyrex brand glass, 16 inches diameter × 12 inches high, capacity 8½ gallons..... **178.59**

QUALITY AND SERVICE
A.H.T.CO.
PHILA. U.S.A.
LABORATORY APPARATUS

ARTHUR H. THOMAS COMPANY

More and more laboratories rely on Thomas / Laboratory Apparatus and Reagents

VINE ST. AT 3RD • PHILADELPHIA 5, PA.